

# YOBE STATE MULTISECTORAL CRISIS RECOVERY PROJECT (MCRP)

Environmental & Social Impact Assessment (ESIA)

For

# **Rehabilitation of 40km Gujba-Ngalda Road** INFRASTRUCTURE PROJECTS UNDER COMPONENT 2 OF MCRP

# DRAFT REPORT

MARCH, 2020

# **Table of Contents**

List of Tablesvi
Acronyms and Abbreviations vii
Executive Summaryix
CHAPTER ONE: INTRODUCTION
1.1 Background2
1.1.1 Technical Approach and Methodology to the ESIA
1.1.2 Desktop Research
1.1.3 Reconnaissance Survey and Field Visits
1.2 Applicable Laws and International Regulatory Framework4
1.3 International Treaties and Conventions on Environment
1.5 Gender-Based Violence7
1.5.1 International Treaties Relevant to GBV
1.5.2 Regional Treaties Relevant to GBV8
1.5.3 National Polices Relevant to GBV
1.6 International Treaties Relevant to Social Protection 8
CHAPTER TWO: DESCRIPTION OF THE PROJECT
2.0 Project Description 11
2.0 Project Description
2.1 Description of the MCRP 40km Gujba-Ngalua roau renabilitation activities 11
2.1.1. Design Standards
2.2 Description of MCRP Intervention Activities
2.3. Scope of Civil Works
2.4.1 Process Inputs
2.4.2 Sources of Energy Available to the Project
2.5 Labour, Manpower and Human Resource19
2.6 Campsite & Staging Areas
2.7 Sourcing of water & other materials
2.7 Sourcing of water & other materials
2.7 Sourcing of water & other materials
2.7 Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0 Introduction22
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives22
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative22
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative223.2.2Using Alternative Travel Modes22
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative223.2.2Using Alternative Travel Modes223.2.3Alternative Alignments23
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative223.2.2Using Alternative Travel Modes223.2.3Alternative Alignments233.2.4Construction of new Road23
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative223.2.2Using Alternative Travel Modes223.2.3Alternative Alignments233.2.4Construction of new Road233.3Development Options24
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative223.2.2Using Alternative Travel Modes223.2.3Alternative Alignments233.2.4Construction of new Road233.3Development Options243.3.1No Project Development24
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative223.2.2Using Alternative Travel Modes223.2.3Alternative Alignments233.2.4Construction of new Road233.3Development Options243.3.1No Project Development243.3.2Delaved Project Development24
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative223.2.2Using Alternative Travel Modes223.2.3Alternative Alignments233.2.4Construction of new Road233.3Development Options243.3.1No Project Development243.3.2Delayed Project Development243.3Road Surfacing Alternative25
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative223.2.2Using Alternative Travel Modes223.2.3Alternative Alignments233.2.4Construction of new Road233.3Development Options243.3.1No Project Development243.3.3Road Surfacing Alternative253.3.4Immediate Project Development25
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative223.2.2Using Alternative Travel Modes223.2.3Alternative Alignments233.2.4Construction of new Road233.3Development Options243.3.1No Project Development243.3.2Delayed Project Development243.3.3Road Surfacing Alternative253.3.4Immediate Project Development25
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative223.2.2Using Alternative Travel Modes223.2.3Alternative Alignments233.2.4Construction of new Road233.3Development Options243.3.1No Project Development243.3.2Delayed Project Development243.3.3Road Surfacing Alternative253.3.4Immediate Project Development25
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative223.2.2Using Alternative Travel Modes223.2.3Alternative Alignments233.2.4Construction of new Road233.3Development Options243.3.1No Project Development243.3.2Delayed Project Development243.3.4Immediate Project Development253.3.4Immediate Project Development25CHAPTER FOUR: DESCRIPTION OF THE PROJECT ENVIRONMENT264.1Overview of the Project Environment26
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative223.2.2Using Alternative Travel Modes223.2.3Alternative Alignments233.2.4Construction of new Road233.3Development Options243.3.1No Project Development243.3.2Delayed Project Development243.3.4Immediate Project Development253.3.4Immediate Project Development25CHAPTER FOUR: DESCRIPTION OF THE PROJECT ENVIRONMENT264.1Overview of the Project Environment264.1Guiba LGA27
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative223.2.2Using Alternative Travel Modes223.2.3Alternative Alignments233.2.4Construction of new Road233.3Development Options243.3.1No Project Development243.3.2Delayed Project Development243.3.3Road Surfacing Alternative253.3.4Immediate Project Development25CHAPTER FOUR: DESCRIPTION OF THE PROJECT ENVIRONMENT264.1Overview of the Project Environment264.1.1Gujba LGA274.2.1Cimate27
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative223.2.2Using Alternative Travel Modes223.2.3Alternative Alignments233.2.4Construction of new Road233.3Development Options243.3.1No Project Development243.3.2Delayed Project Development243.3.3Road Surfacing Alternative253.3.4Immediate Project Development25CHAPTER FOUR: DESCRIPTION OF THE PROJECT ENVIRONMENT264.1.1Gujba LGA274.2.1Climate274.2.1Climate274.2.2Deiafell27
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative223.2.2Using Alternative Travel Modes223.2.3Alternative Alignments233.2.4Construction of new Road233.3Development Options243.3.1No Project Development243.3.2Delayed Project Development243.3.3Road Surfacing Alternative253.3.4Immediate Project Development25CHAPTER FOUR: DESCRIPTION OF THE PROJECT ENVIRONMENT264.1Overview of the Project Environment264.1.1Gujba LGA274.2.2Rainfall274.2.2Rainfall274.2.2Rainfall27
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative.223.2.2Using Alternative Travel Modes223.2.3Alternative Alignments233.2.4Construction of new Road233.3Development Options243.3.1No Project Development243.3.2Delayed Project Development243.3.4Immediate Project Development25CHAPTER FOUR: DESCRIPTION OF THE PROJECT ENVIRONMENT264.1Overview of the Project Environment264.1.1Gujba LGA274.2.2Rainfall274.2.3Temperature274.2.3Temperature27
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative.223.2.2Using Alternative Travel Modes223.2.3Alternative Alignments233.2.4Construction of new Road233.3Development Options243.3.2Delayed Project Development243.3.3Road Surfacing Alternative253.3.4Immediate Project Development253.3.4Immediate Project Development25CHAPTER FOUR: DESCRIPTION OF THE PROJECT ENVIRONMENT264.1Overview of the Project Environment264.1.1Gujba LGA274.2.2Rainfall274.2.3Temperature274.2.4Geology28
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative.223.2.2Using Alternative Travel Modes223.2.3Alternative Alignments233.2.4Construction of new Road233.3Development Options243.3.1No Project Development243.3.2Delayed Project Development243.3.3Road Surfacing Alternative253.3.4Immediate Project Development25CHAPTER FOUR: DESCRIPTION OF THE PROJECT ENVIRONMENT264.1Overview of the Project Environment264.1.1Gujba LGA274.2.2Rainfall274.2.3Temperature274.2.4Geology284.2.5Drainage28
2.7Sourcing of water & other materials20CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS223.0Introduction223.1Analysis of Alternatives223.2.1No-Action Project Alternative.223.2.2Using Alternative Travel Modes223.2.3Alternative Alignments233.2.4Construction of new Road233.3Development Options243.3.1No Project Development243.3.2Delayed Project Development243.3.3Road Surfacing Alternative253.3.4Immediate Project Development25CHAPTER FOUR: DESCRIPTION OF THE PROJECT ENVIRONMENT264.1Overview of the Project Environment264.1.1Guja LGA274.2.2Rainfall274.2.3Temperature.274.2.4Geology284.2.5Drainage284.2.6Agriculture.28

4.2.8 Ecological Problems
4.3.1 Air Ouality
4.3.2. Noise
4.3.3. Water Quality
4.3.3.1Total dissolved solids (TDS)
4.3.3.2Dissolved Oxygen
4.3.3.3Exchangeable Cations
4.3.3.54Heavy Illetais
4.3.3.6Microbiology of Water
4.3.4 Soil Quality
4.3.4.1Textural composition
4.3.4.1 Soil Properties
4.4 Site Specific Environmental & Social Conditions
4.5 Description of The Socio-economic Environment
4.5.1 Population
4.5.3 Land Tenure
4.5.4 Transportation
4.5.3 Infrastructure
4.6 Gender and Gender-Based Violence Information
CHAPTER SIX: ENVIRONMENTAL IMPACT MITIGATION AND MONITORING PLAN 57
6.1 Background
6.2 Additional Mitigation for Gender Based Violence (GBV)/ Sexual Exploitation
6 3 Institutional Δrrangements 97
6.4 Contractual Measures
6.5 Capacity Building for Implementation of ESMP and Permit Conditions 100
6.7 Estimated Budget for ESMP Implementation
5.8 ESIA Disclosures
CHAPTER SEVEN: GRIEVANCE REDRESS MECHANISM
7.1 Introduction
7.2 Grievance Redress Committee
7.3 Grievance Redress Process Error! Bookmark not defined.
7.4 Expectation when Grevances anse
7.6 Financing the Grievance Redress Mechanism and Cost of Remediation 111
CHAPTER EIGHT: STAKEHOLDER CONSULTATIONS
8.1 Introduction
8.2 Objectives of Consultation
8.3 Stakeholder Consultation Strategy and Plan112
8.4 Stakeholders Consulted
8.5 Outcome of Stakeholder Consultations carried out during ESIA Preparation 116
CHAPTER NINE: RECOMMENDATIONS AND CONCLUSION 119
9.0 Conclusion & Recommendations
9.1 Recommendations
9.2 Conclusion

References	121
Annex 1: Questionnaire	122
Annex 2: Occupational Health & Safety (OHS) Plan	124
Annex 3: Sample Company Code of Conduct	128
Annex 4: General Environmental Management Conditions for	
Maintenance/Maintenance Contracts	137
Annex 5: Project Traffic Management Plan (Sample)	144
Annex 6: Contingency and Emergency Response Plan (Sample)	147
Annex 7: Waste Management Plan	153
Annex 8: Cultural Heritage Management/Chance Find Procedure	155
Annex 9: Labour Influx Plan	158
Annex 10: List of Persons Met During Study	161
Annex 11: Camp Management Plan	163
Annex 12: Security Management Plan (Sample)	171
Annex 14: Certificate of Laboratory Report Error! Bookmark not defin	ıed.
Annex 15: Air quality standards along 40km Gujba-Ngalda road	182
Annex 16: Physico-chemical properties of water along 40km Gujba-Ngalda road	t
	184
Annex 19: Sample Copy of Grievance Procedure for Stakeholders	
Annex 20: Chain of Custody for Sampling 1	189

# **List of Figures**

Figure 1: Map of Yobe State showing 40km Gujba-Ngalda	road
Figure 2: Map showing 40km Gujba-Ngalda road Figure 3: Engineering design showing 40km Gujba-Ngalda	
Figure 4: Engineering design showing typical cross section road	<b>of</b> 17
Figure 5: Map of Yobe State; Source-INEC Figure 6: Noise Level along 40km Gujba-Ngalda road Corri Figure 7: Surface Water Quality along 40km Gujba-Ngalda Corridor	dor 31 road
Figure 8: Ground Water Quality along 40km Gujba-Ngalda Corridor	<b>road</b>
Figure 9: Texture composition of soil along 40km Gujba-Neroad Corridor Figure 10: Sub-soil Quality along 40km Gujba-Ngalda road	<b>galda</b> 36
Figure 11: Map of 40km Gujba-Ngalda road showing Environmen Social Sensitivities	
Figure 14: Socioeconomic features of project area Figure 15: Flow Chart for GRM Figure 16: Pictures from Stakeholder Consultations	47 111 117

# List of Tables

Table 1: Relevant Federal/State Policies, Legislations, Regulations &           Guidelines	4
Table 2: International Treaties and Conventions on Environment to which	
Nigeria is a Party	6
Table 3: Potential Safeguard Policies Triggered	7
Table 4: Description of 40km Guiba-Ngalda road location	11
Table 5: Design standards of Guiba-Ngalda road	12
Table 6: Activities for 40km Guiba-Ngalda road Rehabilitation Work	13
Table 7: Project activities by phases	
Table 8: Air quality standards along 40km Gujba-Ngalda road	29
Table 8: Nigeria's Standard Noise Levels (FEPA, 1991)	30
Table 9: Baseline Environmental & Social Conditions of sub-projects	38
Table 11: Socioeconomic characteristics of project area	43
Table 12: Socioeconomic characteristics of project area	47
Table 13: Project Phases & Activities	53
Table 14: Evaluation of potential positive impacts.	54
Table 15: Environmental and Social Management and Monitoring Plan	58
Table 16: Institutional Arrangement for ESMP Implementation	97
Table 17: Contractual Measures	99
Table 18: Capacity building plan for implementation of the ESMP & permit	
conditions	.101
Table 19: Implementation Schedule	.103
Table 20: ESMP Budget	.104
Table 21: Breakdown of Disclosure process	. 104
Table 22: GRM Framework for 40km Gujba-Ngalda road Construction Wor	'k
	.108
Table 23: Stakeholders Engagement Strategy	.113
Table 24: Concerns raised and how they were addressed	.117

# **Acronyms and Abbreviations**

ACHPR-	African Charter on Human and Peoples' Rights				
ACRWC-	African Charter on the Rights and Welfare of the				
CAT-	Convention against Torture				
CBO-	Community Based Organization				
CEDAW-	Convention on the Elimination of All Forms of				
	Discrimination against Women				
CERC-	Contingency Emergency Response Component				
C-ESMP	Contractors Environmental and Social Management Plan				
CoC-	Code of Conduct				
CRA-	Child Right Act				
CRC-	Convention on the Rights of the Child				
CRPD-	Convention on the Rights of Persons with Disabilities				
DO	Dissolved Oxygen				
ESHS	Environmental and Social Health and Safety				
ESMF-	Environmental and Social Management Framework				
ESMP-	Environmental and Social Management Plan				
ESSU-	Environmental and Social Safeguard Unit				
FGD-	Focus Group Discussion				
FMEnv-	Federal Ministry of Environment				
FMF-	Federal Ministry of Finance				
FMWASD-	Federal Ministry of Women Affairs and Social				
	Development				
FPMU-	Federal Project Management Unit				
GBV-	Gender Based Violence				
GHGs-	Green House Gases				
GRC-	Grievance Redress Committee				
GRM-	Grievance Redress Mechanism				
GRS-	Grievance Redress Service				
HSE-	Health Safety and Environment				
IASC	Inter Agency Standing Committee				
ICCPR-	International Covenant on Civil and Political Rights				
ICESCR-	International Covenant on Economic, Social and Cultural				
	Rights				
INGO	International Non-Governmental Organisations				
LGAs-	Local Government Areas				
MCRP-	Multi-sectoral Crisis Recovery Project				
MOH	Ministry of Health				
MOJ	Ministry of Justice				
MSAWD	Ministry of Women Affairs and Social Development				
NDHS-	Nigeria Demographic and Health Survey				
NEDC-	North East Development Commission				
NESREA-	National Environmental Standards and Regulations				
	Enforcement Agency				
NGO-	Non-Governmental Organization				
OHS-	Occupational Health and Safety				

PAD	Project Appraisal Document
PAP-	Project Affected Person
PC -	Project Coordinator
PCU-	Project Coordinating Unit
PCU-	Project Coordinating Unit
PDO-	Project Development Objective
PIU-	Project Implementation Unit
PPE-	Personal Protection Equipment
RAAMP-	Rural Access and Agricultural Marketing Programme
RAP-	Resettlement Action Plan
RPF-	Resettlement Policy Framework
SARC	The Sexual Assault Referral Centre
SEA-	Sexual Exploitation and Abuse
SPC-	State Project Coordinator
SPCU-	State project coordinating Unit
SPIU-	State Project Implementation Unit
SPU-	State Project Unit
TA-	Technical Assistance
TDS	Total Dissolved Solids
TC-	Technical Committee
TPH	Total Petroleum Hydrocarbon
UN	United Nations
UNFPA	United Nations Funds for Population Activities
UNHCR	United Nations High Commissioner for Refugees
UNICEF	United Nations Children's Fund
VAPP-	Violence against Persons Prohibition
VAWC	Violence against women and children
VES-	Vehicle Exhaust Screening
VET-	Vehicle Emission Testing
WB-	World Bank
VAWG	Violence Against Women Group

# **Executive Summary**

### ES 1: BACKGROUND

Federal Government of Nigeria has received financing from the World Bank (WB) for the implementation of Multi Sectoral Crisis Recovery Project (MCRP) currently in three States of Borno, Adamawa and Yobe. The Project Development Objective (PDO) of the MCRP is to "support the Government of Nigeria towards rehabilitating and improving critical service delivery infrastructure, improving the livelihood of conflict and displacement-affected communities, and strengthening social cohesion in the States of Borno, Adamawa and Yobe.

Yobe State MCRP is proceeding to undertake the rehabilitation of the 40km Gujba – Ngalda road and this proposed project when completed will deliver better transport access and create employment opportunities for skilled and unskilled labour during the construction and operational phases. Also, there are indirect employment opportunities such as food vendors, petty traders and suppliers of raw materials for construction. During the operational phase, job opportunities will be created for maintenance workers and suppliers, waste management companies, etc.

Notwithstanding these positive impacts, the project is envisaged to have negative environmental and social impacts due to nature of civil works and has triggered four of the World Bank Operational Policies: Environmental Assessment OP 4.01; Natural Habitats OP/BP 4.04; Physical Cultural Resources OP/BP 4.11 and Involuntary Resettlement OP/BP 4.12.

The Yobe State Project Coordinating Unit (PCU) has prepared this Environmental and Social Impact Assessment (ESIA) as an instrument whose objective is to address the environmental and social safeguard concerns for the proposed Gujba-Ngalda road by identifying the potential negative impacts and proffering mitigation for the impacts as well as assigning responsibilities for mitigation and monitoring.

### Project Rationale

Although the MCRP is rated Category B, the impacts of the 40km Gujba-Ngalda road rehabilitation are likely to have direct and widespread impacts (large category B project), as such it is important that these impacts be adequately mitigated, planned, executed and monitored to ensure holistic management of envisaged environmental and social impacts. The nature of this sub-project is likely to represent a large-scale intervention cutting across 5 communities of Gujba LGA (Gujba, Wagir, Nyakire, Bukkiyel & Mutai) and will not fundamentally change the environment if adequately mitigated. In this instance, the appropriate safeguard instrument to use here is an Environmental and Social Impact Assessment (ESIA) given the fact that the exact nature of the works associated with rehabilitation of 40km Gujba-Ngalda road are large and not site specific.

### **ES 2: PROJECT DESCRIPTION**

The transport sector - 40km Gujba-Ngalda road rehabilitation sub-project has been selected for intervention under this phase of the MCRP rehabilitation work. The location of this road is shown in table ES1.

#### Table ES1: Location of 40km Gujba-Ngalda road Intervention Sub-Project

Sub-projects	LGA	Location
Rehabilitation of 40km	Gujba LGA	Start – N10.53072 E0 13. 27713
Gujba-Ngalda road -	-	End - N10.26757 E0 13. 29283

#### Scope of Works

- Provision of reinforced concrete line drain (80 x 70 x 0.15) m and (1 x1x 0.15) m using grade concrete
- Maintenance of erosion control structures, fencing walls screens and other environmental barriers
- Laying of 50mm thick asphalt wearing course on carriage section of 7.3m for 40km Gujba-Ngalda road
- Routine maintenance and replacement Road civil works generally including:
  - Site clearance;
  - Ground works & earthworks;
  - Excavate for all culverts, concrete side drains to any depth in any material except rock including back filling to 100% B.S. compaction and dispose of surplus material as directed (including dewatering).
  - Provide sandcrete block connecting drain; fill block hollows and capping with grade 15 concrete and good rendering finish.
- Carry out pavement and surfacing work as follows:
  - Provide, spread, shape and compact to 100% West African Standard Compaction naturally occurring laterite as base in carriageway and shoulders in layers of 150mm of compacted thickness (Haul inclusive).
  - Provide, haul any distance, spread, shape and compact approved material (crushed rock, wet or dry) in carriageway base as specified to a compacted thickness of 150mm
  - Provide and lay prime coat using MCI cut back bitumen at 1.2 litre per sq.m including blinding with river sharp sand or quarry fines
  - 0
    - Provide, spread, shape and compact asphaltic concrete wearing course to carriageway to a compacted thickness of 40mm as specified.
  - Provide and set in concrete Grade 25 and paint standard triangular section concrete kilometer post as per drawings or as directed.
  - Excavate for, provide and lay approved type precast concrete kerbs 450mm x 150mm set in 1:3:6 concrete bedding 225mm wide by 100mm backing to full height, chamfered back at 45° from back of kerb and to show 125mm face in high embankments, urban areas and medians or as directed.

The engineering design for the road and culvert is shown in Figure 2 and 3, respectively.

### ES 3: ANALYSIS OF ALTERNATIVES

The objective of the MCRP is to support the Government of Nigeria towards rehabilitating and improving critical service delivery infrastructure, improving the livelihood of conflict and displacement-affected communities, and strengthening social cohesion in the States of Borno, Adamawa and Yobe. Consequently, the different alternatives and options that were considered for the proposed project were in line with the overall objectives of the project in Yobe State. These alternatives include taking no action, using alternative travel modes and alternative alignment construction as other methods of achieving the objectives of the sub-project. The 'No Project' Development, 'Delayed Project' Development and Immediate Project Development have been extensively contemplated under Chapter 3 of this ESIA report.

### **ES 4: DESCRIPTION OF THE PROJECT ENVIRONMENT**

Yobe state lies mainly in the dry Savannah belt; hence the state is dry and hot for most the year except in the Southern part of the State, which has a milder climate. The distinctly hilly nature of the terrain in Yobe presents a general topography that has significant impact on the local variations and pattern of rainfall. There are two distinct seasons; the dry and wet season. The climate of Yobe State is hot and dry for most periods, of the year. The rainy season usually ends in the month of November, which indicates the beginning of the dry season. The geology of Yobe principally comprises crystalline and sedimentary rocks, underlain by basement complex rocks.

The 40km Gujba-Ngalda road sub-project transcends a route through Gujba LGA of Yobe State. Majority of the people in the villages such as Gujba, Wagir, Nyakire, Bukkiyel & Mutai communities are farmers. Other forms of occupation carried out include trading and artisanship. Agriculture is therefore, the mainstay of the economy. Crops grown include guinea corn, millet, maize, rice, wheat, groundnut, cassava, beans and cowpeas. Others are vegetables, onions, okra and tomatoes.

Mitigation measures for envisaged impacts such as dust, noise, traffic disturbance, waste management, health and safety of workers, communities and risk associated with labour influx and sexual exploitation and abuse (SEA) during construction have been addressed in this ESIA.

#### **ES 5: POTENTIAL ENVIRONMENTAL AND SOCIAL IMPACTS**

The potential positive environmental and social impacts are listed in Table ES2:

No.	Impact	Key receptor(s)	Evaluation
1	Improved transport infrastructure Improved motorable access to communities	Community leadership and users of transport infrastructure	The proposed project when completed will deliver these benefits: Better road access Improved transportation services for people in communities Strengthen social cohesion through increased community access, inter groups and inter communal relations
	route		Reduced travel time for motorist travelling from Gombe to Damaturu and Maiduguri who will bypass Potiskum axis.
2.	Improved access to education	Children of school age	Pupils of secondary school age can now be able to attend and return from school due to reduced travel time along the road leading to Gujba where the only secondary school in the area is situated.
3.	Improved access to farmlands & markets	Farmers in neighboring communities	Livelihoods restoration by increasing access to farmlands for agricultural productivity as well as nearby markets for commercial activities.
4.	Increase access to health services	Community members	Improved access for general population including pregnant women, children and people with disability in emergency situations
5.	Employment generation	Community members	The proposed rehabilitation/construction sub- project activities will create employment opportunities for skilled and unskilled labour during the construction and operational phases. Also, there are indirect employment opportunities such as food vendors, petty traders and suppliers of raw materials for construction. During the operational phase, job opportunities will be created for maintenance workers and suppliers, waste management companies, etc.
6.	Improvement in local and national economy	Neighboring communities, LGA and national economy	The creation of direct and indirect job opportunities during the construction and operational phases of the project will boost the

Table ES2: Environmental & Social Impacts of 40km Gujba-Ngalda roadRehabilitation/Construction sub-project

No.	Impact	Key receptor(s)	Evaluation	
			local and national economy	
7.	Stakeholders' engagement	State Government, LGAs	Improvement of public goodwill and satisfaction towards governance in Yobe State.	
8.	Improvement in management of resources	Neighboring communities, State Government, MDAs	Provision of a lead way to drive the State Government towards ensuring improved infrastructure	
9.	Optimal utilization of Ngalda/Garin Chindo irrigation scheme	Farmers/communities	The rehabilitation of Gujba-Ngalda road in the area will boost the economy and increase sources of income to the people	
10.	Capacity building and strengthening of institutions	State Government, MDAs	Capacity building through: Strengthening of facility rehabilitation works and supervision systems of personnel involved in sub-project activities, including improvement in institutional responsibilities for construction and maintenance. Transfer of skills	

The potential negative environmental impacts include mainly impacts on air quality, soil quality, noise levels, water quality and Occupational health and safety while social impacts include risks of labour influx, child labour, sexual exploitation and abuse, GBV and conflict. These are elaborated in the report.

### ES 6: ENVIRONMENTAL AND SOCIAL MITIGATION AND MONITORING

Detailed environmental and social mitigation measures for pre-construction, construction and operational phases have been provided in table below. The environmental and social management actions is estimated at Sixteen Thousand, Two Hundred and Sixty Five Thousand, Seven Hundred Naira Only (\$16,265,700.00), and a Dollar equivalent of Fifty Three Thousand, One Hundred and Fifty Six Dollars Only (\$53,156.00). This is as shown in Table 18 of this report. The cost of mitigation by the Contractor will be included in the contract as part of the implementation cost by the Contractor. The Yobe MCRP SPCU will coordinate the implementation of this ESMP in conjunction with the relevant State Ministries. This is shown in Table ES3 for ESIA mitigation & monitoring.

		Total*	
#	Item	Local <del>N</del>	US\$
1	Mitigation (Including the cost of PPEs)	9,185,000	30,015
2	Capacity Building (including training on Code-of- conduct)	1,150,000	3,758

 Table ES3: Budget for ESIA mitigation & monitoring

	Grand Total	16,265,700	53,156
8	Contingency (10% of sub Total)	1,478,700	4,832
	Sub-Total	14,787,000	48,324
7	Disclosure	1,000,000	3,268
6	Monitoring (including the cost of hand-held monitoring instruments)	1,452,000	4,314
5	Consultations	500,000.00	1,634
4	Grievance Redress Mechanism	750,000	2,451
3	GBV, STIs and HIV Mitigation	750,000	2,451

Currency Unit = Nigerian Naira US\$1 = N306

### ES 7: GRIEVANCE REDRESS MECHANISM

The likelihood of disputes to occur during the sub-project implementation will be greatly reduced because consultations have already been carried out with some of the affected persons. Nevertheless, in the event that grievances arise, this redress mechanism has been prepared. A Grievance Redress Mechanism (GRM) is provided in chapter 7, which is anchored on the need to provide a forum locally to receive, hear and resolve disputes arising from construction activities and implementation in the best interest of all parties to forestall the lengthy process of litigation, which could affect the progress of project.

Even though a GRM has been developed for the entire MCRP, however this GRM will be for the implementation of the road construction & rehabilitation sub-project in Yobe State and will take direction from the MCRP GRM.

### **ES 8: STAKEHOLDERS CONSULTATION**

Extensive consultation was conducted with relevant stakeholders with details in chapter 6. The Stakeholders Consultation meeting was carried out from January 22<sup>nd</sup> – 26<sup>th</sup> 2020 in Gujba, Wagir, Nyakire, Bukkiyel & Mutai communities within the project area. Concerns centred mainly on time for commencing the civil works as well as involvement of members of the community as skilled and unskilled labour during the civil works. Concerns were noted and responses provided by consultant. Consultation with the stakeholders will continue throughout the life cycle of the project. Summary of issues raised and how they were addressed is contained in Table ES4.

S/n	Tesues raised during	How they were addressed
5/11	concultations	now they were dutiessed
Teenec		Altornative route will be prested
Issues	Disruption of movement	Alternative route will be created
raised in	auring construction phase	for motorists and pedestrians
general	since this is the only road	during construction phase to ease
forum	linking communities in the	movement of people, goods and
	area	services
	Project to take cognizance	Project activities will not affect
	of existing ponds and earth	any pond or earth dam as
	dams used for livestock	revealed by screening and
	farming in the area.	fermations in the proper will
		formations in the areas will
		prevail since the road is in
		existence and will only be
	MCDD to consider	Tendomilateu.
	ovtonding the project up to	allow for only 40kms new
	Nalda instand of taking	However this will be against
	anly 40km	riowever, this will be against
		funding will accommodate
		Communities were advised to
		engage policy makers in the state
		on the need for state government
		to take the remaining part from
		Mutai to Ngalda
	Expansion of existing	Component 2 manager responded
	culvert at the entrance of	that the design consultant has
	Wagir	made the recommendation for
	Wagn	the expansion has been cantured
		in the design
Τςςιμος	At a dedicated session with	Contractors will be trained on
raisod	women there were	GBV prevention and all their staff
during	concerns about gender	will sign code of conduct against
aunng	based violence (GBV).	engaging in sexual exploitation
meetings	violence against women	and abuse as well as violence
with	and children and sexual	against women. Project has
Women	exploitation and abuse	established GRM with GBV
	likely to be exacerbated by	sensitive channels to offer
	the project activities.	referral pathways for survivors.
		Project safeguard team will
		closely monitor activities of
		contractors and their staff during
		implementation phase to ensure
		compliance. The team advice the
		community members, particularly
		parents to monitor their children
		(girl child) and continue to warn
		them to be careful with those
		who will lure them into such
		activities.
	Women have raised	Labour influx management plan

Table ES4: Issues & Concerns	raised & how the	y were addressed
------------------------------	------------------	------------------

	concern about job opportunities to be created by the project during construction phase, especially for their children who are staying idle without job.	will be developed as part of the ESIA for contractor's compliance to ensure community members are considered in the recruitment of staff on the project.
Issues raised during meetings with Youths	The youths have expressed concern about employment opportunities during the project implementation.	Contractors will be trained on how to manage labour influx. Part of the strategy for managing labour influx is to look inward for various skills within the communities, unless such are not available before resorting to external source. Therefore, the project will provide job opportunities to the teeming youth, especially those who are disposed to road construction related works
Issues raised during meetings with elderly	Community elders advocated for construction of additional road from Gujba to Goniri to connect more communities in the area,	The team responded that Gujba – Gonir road is entirely a new project while MCRP is focusing on rehabilitation of existing infrastructure
persons	Extension of the project up to Ngalda (95kms) to cover more communities in the area	This will be considered when funding is available. The community members were advised to advocate with the state government, north east development commission for the execution of the project
	Contractors to exercise caution during construction to ensure safety of animals, children, women, aged and other vulnerable people who will be routinely moving around to pursue their daily needs	Traffic management plan will be developed as part of the ESIA. Dangerous and hazardous areas will be cordoned off during construction phase to safeguard the lives and well-being of human beings and animals

### ES9 CONCLUSION

The ESIA has provided in detail the mitigation measures for identified potential adverse impact for the various phases of the project, and a monitoring program to ensure compliance. In concluding, with adequate application of mitigation measures the impacts identified and anticipated will be avoided, reduced or mitigated.

# CHAPTER ONE: INTRODUCTION

# 1.1 Background

The Yobe State Project Coordinating Unit (PCU) has prepared this Environmental and Social Impact Assessment (ESIA) as an instrument whose objective is to address the environmental and social safeguard concerns for the proposed Gujba-Ngalda road by identifying the positive and also the potential negative impacts and proffering mitigation for the impacts as well as assigning responsibilities for mitigation and monitoring.

The Federal Government of Nigeria has received financing from the International Development Association (IDA) (the ''Bank'') in the form of a credit towards the cost of the Multi Sectoral Crisis Recovery Project (MCRP). The Government of Nigeria is implementing the Multi Sectoral Crisis Recovery Project (MCRP) in an effort to support recovery and stability in the North East, which is financed by the World Bank. The MCRP was initiated in 2014 and is targeted at three states: Borno, Adamawa and Yobe (BAY) while being monitored at the Federal Level by the MCRP Federal Project Coordinating Unit (FPCU) and implemented through the MCRP State Project Coordinating Units (PCU).

The PDO of this project is supporting the Government of Nigeria towards rehabilitating and improving critical service delivery infrastructure, improving the livelihood opportunities of conflict and displacement-affected communities, and strengthening social cohesion in the North East Participating States of Borno, Adamawa and Yobe; In the event of an eligible crisis or emergency, the provision of immediate and effective response to said eligible crisis or emergency, through the proposed Contingent Emergency Response Component (CERC).

Yobe State is proceeding to undertake the rehabilitation of the 40km Gujba-Ngalda road intervention under this phase of the MCRP intervention work. The proposed project when completed will deliver better road access; will create employment opportunities for skilled and unskilled labour during the construction and operational phases. Also, there are indirect employment opportunities such as food vendors, petty traders and suppliers of raw materials for construction. During the operational phase, job opportunities will be created for maintenance workers and suppliers, waste management companies, etc.

Notwithstanding these positive impacts, the project is envisaged to have limited negative environmental and social impacts due to the nature of civil works and has triggered four of the World Bank Operational Policies: Environmental Assessment OP 4.01; Natural Habitats OP/BP 4.04; Physical Cultural Resources OP/BP 4.11 and Involuntary Resettlement OP/BP 4.12 Although the MCRP is rated Category B, the impacts of the 40km Gujba-Ngalda road rehabilitation are likely to have direct and widespread impacts (large category B project), as such it is important that these impacts be adequately mitigated, planned, executed and monitored to ensure holistic management of envisaged environmental and social impacts. The nature of this sub-project is likely to represent a large-scale intervention cutting across 5 communities (Gujba, Wagir, Nyakire, Bukkiyel & Mutai communities) and will not fundamentally change the environment if adequately mitigated. At this instance, the appropriate safeguard instrument to use is an Environmental and Social Impact Assessment (ESIA) given the fact that the exact nature of the works associated with rehabilitation of 40km Gujba-Ngalda road are large and not site specific.

# 1.1.1 Technical Approach and Methodology to the ESIA

The methodology used in the preparation of the Environmental and Social Impact Assessment (ESIA) for the project is based on guidelines proposed by the:

- Federal Government of Nigeria EIA Law and subsequent Federal Ministry of Environment standard procedures for conducting EIA in Nigeria
- World Bank Environmental Assessment Operational Policies OP 4.01

The general approach includes:

## 1.1.2 Desktop Research

Desktop research was carried out on roads in Yobe State, specifically, similar projects as implemented in Nigeria and elsewhere, and the impacts of such projects as well as its mitigation measures. It was carried out to establish the environmental and social baseline information. Other materials consulted include:

- Project Appraisal Document (PAD) for the MCRP
- Detailed Engineering Design
- World Bank Safeguards Policies
- Federal and State Environmental Laws, Regulations, Policies and Guidelines

## 1.1.3 Reconnaissance Survey and Field Visits

A reconnaissance survey was first undertaken to familiarize the consultants with the 40km Gujba-Ngalda road and to commence fieldwork. The survey was conducted along with the Yobe PCU staff from January 8th-9th 2020. The Key activities undertaken during the survey include:

### 1.1.3.1 Stakeholders Consultation

The result of the stakeholder consultation during the reconnaissance survey formed the basis for further consultation with other key stakeholders. These consultations had to be conducted with consideration for the security timelines provided by armed forces that require the roads are opened from only 7am - 5pm, daily. The stakeholders consulted for this project include but are not limited to:

- Yobe State Ministry of Environment
- Yobe State Ministry of Works
- Traditional and community leaders
- Communities along the proposed routes (Gujba, Wagir, Nyakire, Bukkiyel & Mutai communities)
- Other Agencies whose activities relate to the project.

### 1.1.3.2 Biophysical Sampling

Baseline data gathering and laboratory analysis of samples of soil, ground and surface water, air and noise taken or measured in the field (in-situ) at selected sites along the project road to verify and complement information obtained from literature. The fieldwork covered all the relevant aspects of the traffic survey, ecological, community health and socio- economic environment.

### **1.1.3.3** Socio-Economic Assessment

Socio-economic data was collected through key informant interviews, Focus Group Discussion (FGD), direct observation, administration of structured questionnaire and collection of primary sources of data. The data collected were analyzed and the results are presented under Chapter 4 of this ESIA Report.

### **1.2** Applicable Laws and International Regulatory Framework

A number of national and international environmental guidelines are applicable to the operations of the MCRP. This ESIA is prepared in consonance with relevant Yobe State and Federal Government policies, laws, regulations, guidelines, and applicable World Bank Operational Policies (See MCRP PAD). The relevant Federal and State policy and regulatory instruments are summarized in the Table 1.

# Table 1: Relevant Federal/State Policies, Legislations, Regulations &Guidelines

S/N	Policy Instrument	Year	Provisions
1	National Policy on the Environment	1989 revised 1991	Describes the conceptual framework and strategies for achieving the overall goal of sustainable development in Nigeria.
	Legal/Regulatory		
Instr	rument		
2.	Environmental Impact Assessment (EIA) Act No. 86	EIA Act CAP E12 LFN 2004	Provide guidelines for activities of developmental projects for which EIA is mandatory in Nigeria. The Act also stipulates the minimum

		-	
			content of an EIA as well as a schedule of projects, which require mandatory EIAs.
3.	Land Use Act	1978	The Act vests all land comprised in the territory of each state in the Federation in the Governor of the state and requires that such land shall be held in trust and administered for the use and common benefit of all Nigerians in accordance with the provisions of the Act.
4.	Forestry Act	1994	Provides for the preservation of forests and the setting up of forest reserves.
5.	Endangered Species Act	1985	Provides for the conservation and management of Nigeria's wildlife and the protection of some of her endangered species in danger of extinction as a result of over- exploitation
6.	FEPA/FMEnv EIA Procedural Guidelines	1995	The Procedural Guidelines indicate the steps to be followed in the EIA process from project conception to commissioning in order to ensure that the project is implemented with maximum consideration for the environment.
7.	National Guideline and Standard for Environmental Pollution Control	1991	Provide guidelines for management of pollution control measures
8.	S.I.15 National Environmental Protection (Management of Solid and Hazardous Wastes) Regulations	1991	Regulates the legal framework for the effective control of the disposal of toxic and hazardous waste into any environment within the confines of Nigeria.
9.	Urban and Regional Planning Decree No. 88	1993	Planned development of urban areas (to include and manage waste sites).
10.	Workmen Compensation Act	1987 reviewed 2010	Occupational Health and Safety
11.	Child Rights Act	Act No. 26 of 2003	Best interests of a child are to be paramount in all actions and clearly states the rights of the

				child.
12.	Yobe Environmental	State	-	Making and enforcing environmental and health polices
	Protection Law			and laws

### **1.3 International Treaties and Conventions on Environment** Some of the international Treaties and Conventions on environment to which Nigeria is a party are summarized in Table 2 below.

# Table 2: International Treaties and Conventions on Environment towhich Nigeria is a Party

S/N	Treaties and	Year	Agreement
1	Conventions	1072	Drovido quidolingo for protocting the
1.	Environmental	1972	integrity of the global environment
	Guidance Principles		and the development system
2.	Montreal Protocol on Substances that deplete the Ozone Layer	1987	An international treaty to eliminate Ozone depleting chemical production and consumption.
3.	United Nations Convention on Biological Diversity	1992	Places general obligations on countries to observe sustainable use and equitably share the plants and animals of the earth
4.	United Nations Framework Convention on Climate Change	1994	It calls on developed countries and economies to limit her emissions of the greenhouse gases which cause global warming
5.	Convention on International Trade in Endangered Species of Wild Fauna and Flora	1973	Restricts the trade of fauna and flora species termed as endangered Species
6.	Convention on Conservation of Migratory species of Wild animals (Bonn Convention)	1979	Stipulates actions for the conservation and management of migratory species including habitat conservation
7.	Vienna Convention for the Protection of the Ozone Layer	1985	Places general obligation on countries to make appropriate measures to protect human health and the environment against adverse effects resulting from human activities, which tend to modify the ozone layer.

# **1.4 Environmental Safeguards Issues**

Nigerian EIA laws and the World Bank Environmental and Social Safeguard Policies by which the activities of the MCRP project have triggered four out of the ten environmental & social safeguard polices: Environmental Assessment OP 4.01; Natural Habitats OP/BP 4.04; Physical Cultural Resources OP/BP 4.11 and Involuntary Resettlement OP/BP 4.12 is shown in Table 3.

Policy	Y e s	N O	Applicability due to	How this Project Addresses Policy Requirements
Environm ental Assessme nt (OP 4.01)	X		Construction & civil works on the 40km Gujba-Ngalda road will trigger site-specific impacts. Potential impacts include construction impacts on environment etc.	As targeted sites have been identified, a proper assessment has been carried out to determine actual environmental and social issues in project area.
Involuntar y Resettlem ent (OP 4.12)	X		Project impacts that may arise in loss of assets, loss of access to livelihood or disturbances.	A RAP shall be prepared for specific project locations to identity Project Affected Persons (PAPs) in the project area.
Natural Habitats OP/BP 4.04	X		From conversion or degrading of natural habitats.	The project includes mitigation measures acceptable to the Bank. Such mitigation measures include, as appropriate, minimizing habitat loss.
Physical Cultural Resources OP/BP 4.11	X		The project may include sites having archaeological (prehistoric), paleontological, historical, religious, and unique natural values.	The project includes measures to assist in their preservation, and to seek to avoid their elimination.

Table 3: Potential Safeguard Policies Triggered

## **1.5 Gender-Based Violence**

Nigeria has ratified or acceded to the core international human rights treaties and is a party to the major regional human rights instrument which obliged States to respect, protect and fulfil human rights of all persons within the territory and subject to the jurisdiction of the State, without discrimination. Rape may violate several human rights obligations enshrined in the instruments ratified by Nigeria and is also a form of gender-based violence and a manifestation of violence against women. As a State party to the Convention on the Elimination of All Forms of Discrimination against Women (CEDAW) and the Protocol to the African Charter on Human and Peoples' Rights on the Rights of Women in Africa (the "Maputo Protocol"), Nigeria has made legally binding commitments to exercise due diligence to combat gender-based violence and discrimination.

# **1.5.1 International Treaties Relevant to GBV**

- The International Covenant on Civil and Political Rights (ICCPR) (2004)
- The International Covenant on Economic, Social and Cultural Rights (ICESCR) (2004)
- The Convention against Torture and Other Cruel, Inhuman or Degrading Treatment or Punishment (CAT) (1993)
- The Convention on the Elimination of All Forms of Discrimination against Women (CEDAW) (1984)
- The Convention on the Rights of the Child (CRC) (1990), and the Convention on the Rights of Persons with Disabilities (CRPD) (2012)
- International Convention on the Elimination of All Forms of Racial Discrimination (1976)

## 1.5.2 Regional Treaties Relevant to GBV

- The African Charter on Human and Peoples' Rights (ACHPR) (1982)
- The African Charter on the Rights and Welfare of the Child (ACRWC) (2007)
- The Protocol to the ACHPR on the Rights of Women in Africa (the "Maputo Protocol") (2007)

# **1.5.3 National Polices Relevant to GBV**

- The National Action Plan for the Implementation of United Nations Security Council Resolution 1325 (2009)
- The National Gender Policy (2010)

# **1.6 International Treaties Relevant to Social Protection**

Some relevant international treaties on social protection include

## The International Covenant on Civil and Political Rights (ICCPR)

(2004); which pursues the promotion of self-realization by upholding the right of self-determination. By virtue of that right they freely determine their political status and freely pursue their economic, social and cultural development. Also, all peoples may, for their own ends, freely dispose of their natural wealth and resources without prejudice to any obligations arising out of international economic co-operation, based upon the principle of mutual benefit, and international law. In no case may a people be deprived of its own means of subsistence. The International Covenant on Economic, Social and Cultural Rights (ICESCR) (2004); which undertakes to take steps, individually and through international assistance and co-operation, especially economic and technical, to the maximum of its available resources, with a view to achieving progressively the full realization of the rights recognized in the present Covenant by all appropriate means, including particularly the adoption of legislative measures.

The Convention against Torture and Other Cruel, Inhuman or Degrading Treatment or Punishment (CAT) (1993) that promotes the protection of people from "torture", which means any act by which severe pain or suffering, whether physical or mental, is intentionally inflicted on a person for such purposes as obtaining from him or a third person information or a confession, punishing him for an act he or a third person has committed or is suspected of having committed, or intimidating or coercing him or a third person, or for any reason based on discrimination of any kind, when such pain or suffering is inflicted by or at the instigation of or with the consent or acquiescence of a public official or other person acting in an official capacity. It does not include pain or suffering arising only from, inherent in or incidental to lawful sanctions.

The Convention on the Elimination of All Forms of Discrimination against Women (CEDAW) (1984), discourages the discrimination against women by any distinction, exclusion or restriction made on the basis of sex which has the effect or purpose of impairing or nullifying the recognition, enjoyment or exercise by women, irrespective of their marital status, on a basis of equality of men and women, of human rights and fundamental freedoms in the political, economic, social, cultural, civil or any other field.

The Convention on the Rights of Persons with Disabilities (CRPD) (2012); which adopts a broad categorization of persons with disabilities and reaffirms that all persons with all types of disabilities must enjoy all human rights and fundamental freedoms. It clarifies and qualifies how all categories of rights apply to persons with disabilities and identifies areas where adaptations have to be made for persons with disabilities to effectively exercise their rights and areas where their rights have been violated, and where protection of rights must be reinforced.

International Convention on the Elimination of All Forms of Racial Discrimination (1976), which discourages any distinction, exclusion, restriction or preference based on race, colour, descent, or national or ethnic origin which has the purpose or effect of nullifying or impairing the recognition, enjoyment or exercise, on an equal footing, of human rights and fundamental freedoms in the political, economic, social, cultural or any other field of public life.

Generally, with regards to environmental and social management issues, legislation is in a continuing process of development in Nigeria. Nevertheless, in the event of divergence between the two, the World Bank safeguard policy shall take precedence over Nigeria EA laws, guidelines for these intervention projects.

## CHAPTER TWO: DESCRIPTION OF THE PROJECT

### 2.0 **Project Description**

This chapter describes the details of the 40km Gujba-Ngalda road intervention sub-project.

# 2.1 Description of the MCRP 40km Gujba-Ngalda road rehabilitation activities

This intervention sub-project is located in Gujba LGA of Yobe State. Some of the villages along this road are Gujba, Wagir, Nyakire, Bukkiyel and Mutai communities. The location details of the 40km Gujba-Ngalda road are as shown in Table 4, while Figures 1 & 2 show the location map of the road in the State.

S/n	Description	Coord	inates
1.	Road start point	N11.2946.92	E11.565.78
	(Gujba Community)		
2.	Wagir Community	N11.2124.41	E11.4839.10
3.	Nyakire Community	N 11.209.42	E11.4625.31
4.	Bukkiyel Community	N 11.193.76	E114359.60
5.	Mutai Community	N 11.1610.13	E11.4329.86
6.	End of road	N11.25188	E11.71268

### Table 4: Description of 40km Gujba-Ngalda road location



Figure 1: Map of Yobe State showing 40km Gujba-Ngalda road



Figure 2: Map showing 40km Gujba-Ngalda road

# 2.1.1. Design Standards

The design standards for this road are shown in Table 5.

<u> </u>	Beorgin Standardo or Cujba rigarda road		
Standard	Description		
Type of road	Single carriageway		
Right of Way	50m		
Road width (carriageway)	7.3m		
Road shoulders	1.5m (each)		
Design speed	100km/hr (50km/hr built up areas)		
Maximum grade	4.0%		
Cross slope	1.5%		
Minimum curve length	150m		
Crest	50m		
Sag	35m		
Surfacing	50m		
Road base	175m		

Table 5: Design standards of Gujba-Ngalda road

# 2.2 Description of MCRP Intervention Activities

The activities involved in this 40km Gujba-Ngalda road rehabilitation work are as shown in Table 6:

Project Phase	Proposed Intervention		Activities
	W	ork	
Pre- construction		Marking	<ul> <li>Marking of road right of way (ROW)</li> </ul>
		Clearing	by surveyors
		Mobilizatio n	<ul> <li>Preparation of staging area</li> <li>Mobilization of plant, equipment &amp; personnel to site</li> </ul>
		Road works: Groundworks	<ul> <li>Scarification</li> <li>Sub-grade preparation</li> <li>Earthworks</li> <li>Preparation of burrow pit</li> </ul>
Construction	Construction / Rehabilitatio n of 40km Gujba- Ngalda road	Pavement & Surfacing	<ul> <li>Provide, spread, shape and compact laterite material</li> <li>Provision of Box Culverts at designated locations</li> <li>Provision of reinforced concrete line drain (80x70x0.15)m and (1x1x0.15)m using grade concrete</li> <li>Construction of stone pitches or side drainage in areas</li> <li>Provision of first coat surface dressing for entire length of road</li> <li>Provision of second coat surface dressing</li> <li>Laying of 50mm thick asphalt wearing course on carriage section of carriage section of carriage section of coat surface dressing</li> </ul>

 Table 6: Activities for 40km Gujba-Ngalda road Rehabilitation

 Work

	Side drains	<ul> <li>Provide concrete kerbs as directed</li> <li>Provide triangular section concrete kilometre post as directed</li> <li>Construction of drainage structure and facilities</li> <li>Construction of retaining walls and earthfilling</li> <li>Other ancillary</li> </ul>
		works
	Culverts & River Crossing	<ul> <li>Piling</li> <li>Construction of pile caps</li> </ul>
Operation	Road, culverts & river crossing/bridg e maintenance works	<ul> <li>Clearing of culverts and trenches of solid waste and silt</li> <li>Routine inspection of drainage structures and road (pavement) surface</li> <li>Scheduled &amp; unscheduled integrity checks for culvert structural components (foundation, joins etc.)</li> <li>Maintenance of erosion control structures, fencing walls screens and other environmental barriers</li> <li>Routine maintenance and replacement of wearing/faulty/dam aged parts (e.g. binder)</li> </ul>
Domobilizatio	Sito	traffic controls
n	demobilization activities	<ul> <li>Lanuscape restoration and rehabilitation</li> <li>Burrow pit restoration work</li> </ul>

# 2.3. Scope of Civil Works

The scope of civil works to be carried out on the 40km Gujba-Ngalda road sub-project includes:

- Rehabilitation/construction on existing alignments as well as realigned portions where required
- Road civil works generally including:
  - Site clearance;
  - Ground works & earthworks;
  - Excavate for all culverts, concrete side drains to any depth in any material except rock including back filling to 100% B.S. compaction and dispose of surplus material as directed (including dewatering).
  - Provide sandcrete block connecting drain; fill block hollows and capping with grade 15 concrete and good rendering finish.
- Carry out pavement and surfacing work as follows:
  - Provide, spread, shape and compact to 100% West African Standard Compaction naturally occurring laterite as base in carriageway and shoulders in layers of 150mm of compacted thickness (Haul inclusive).
  - Provide, haul any distance, spread, shape and compact approved material (crushed rock, wet or dry) in carriageway base as specified to a compacted thickness of 150mm
  - Provide and lay prime coat using MCI cut back bitumen at 1.2 litre per sq.m including blinding with river sharp sand or quarry fines
  - 0

Provide, spread, shape and compact asphaltic concrete wearing course to carriageway to a compacted thickness of 40mm as specified.

- Provide and set in concrete Grade 25 and paint standard triangular section concrete kilometer post as per drawings or as directed.
- Excavate for, provide and lay approved type precast concrete kerbs 450mm x 150mm set in 1:3:6 concrete bedding 225mm wide by 100mm backing to full height, chamfered back at 45° from back of kerb and to show 125mm face in high embankments, urban areas and medians or as directed.

The engineering designs for the 40km Gujba-Ngalda road and culvert are shown in Figures 3 and 4, respectively, while the different phases of project activities for the rehabilitation work is shown in Table 7.



Figure 3: Engineering design showing 40km Gujba-Ngalda road



# Figure 4: Engineering design showing typical cross section of road

Project Phases	Activities
Preconstruction	Preconstruction phase activities include among
Phase Activities	others:
	Siting of workers camp
	Mobilization of workforce and signing of the code
	of conduct
	Training of workforce on OHS
	Establishment of health camps
	Provision of first aid equipment
	Procurement of PPEs
	Removal of trees and vegetation
	of beneficiary institutions field studies and
	environmental screening:
	Preparation of environmental and social screening
	reports, Environmental and Social Management
	plan and preparation and implementation of the
	Resettlement Action Plan;
	Statutory permitting activities from Yobe WMA/
	Yobe State MCRP PCU
Construction	Construction phase activities include among
Phase Activities	others:
	Editiworks Robabilitation work:
	Mobilization of equipment materials and
	nersonnel to site
	Pipelaying & reticulation activities
	Identification of storage area for construction
	material;
	Transportation and handling of materials and
	equipment;
	Civil & Construction Works
	Construction of waste bin bays (where
	Disposal of construction waste/rubble and waste
	in general
	Installation of safety signage
Operations and	Operations and maintenance phase activities
Maintenance	include:
Phase Activities	Housekeeping;
	Waste management (collection and disposal);
	Maintenance and repair works; and
	Materials management and storage (including
	personal protective equipment, etc.).
Decommissioning	Removal of construction equipment;

## Table 7: Project activities by phases

Phase	Disposal of construction spoil and waste in
	Dismantling of temporary work camp of the
	contractor; and
	Waste management.
	Compensatory tree planting where necessary

## 2.4 Raw Material Supply

Major inputs in this Yobe State MCRP road intervention sub-project include the various construction equipment and machinery for vegetation (bush) clearing, earth (soil) movement, topographic leveling, alignment and re- alignment of road segments, creation of road drainage, gravel and fill material usually excavated on site from burrow pits that may be established for this purpose.

### **2.4.1 Process Inputs**

Road pavement is usually of lateritic materials stabilized with crushed stone as base course. Quarry and crushed rock aggregates that meet the requirements stipulated in relevant sections of the Federal Ministry of Works General Specification are not visible around the Gujba-Ngalda road, however, this can be sourced from the nearby quarry with close proximity to the site. In addition, the type of sand to be used should be free of clay and silts, being composed of angular quartz grains with low percentage of fine (silt) particles. This quality of sand can be sourced in economic quantity around the site, while borrow materials can be sourced along the Damaturu-Potiskum road. This should be tested to confirm their suitability for use as road fill materials. The public safety considerations for the haulage and conveyance of these materials have been properly articulated in the ESMP (Table 15) of this ESIA.

### 2.4.2 Sources of Energy Available to the Project

Energy will be provided from generating set machines dependent on petroleum products, which include motor gasoline, dual-purpose kerosene, and automotive gas oil, which represent major energy sources in Yobe available to the project.

### 2.5 Labour, Manpower and Human Resource

The project will require specialized (skilled) and unskilled human resource and labour. The contractor's workforce will mostly consist of skilled personnel such as engineers, surveyors, and technicians, environmental and social safeguard officers, health and safety officer, etc. Majority of the ancillary workforce will comprise of local labour.

### 2.6 Campsite & Staging Areas

To ensure ease of coordination of operations, a site office and campsite will be established for this sub-project, while the contractor will be

required to identify a staging area for plant & equipment that will be in conformity with the requirements of this ESIA.

The location for the establishment of the contractor's and the Resident Engineer's camps and sites should be determined in consultation with the Resident Engineer, the PCU and the local communities, taking into account the following aspects:

- Be located outside the protection zone of watercourses (100 m) and wetlands;
- Be located within an acceptable distance from existing residential areas, school field or around where little children gather;
- Not located in areas with intact vegetation;
- The contractor must first obtain the necessary licenses and consents from the relevant local government actors or from the owner of the needed area;
- Although it is the contractor's decision, it is recommended that whenever possible the camps should be handed over to the administrative or community authorities for future use;
- The contractor must submit for the prior approval of the Resident Engineer, the implementation design and other project structures and specifications related to the camps and sites that are intended to be built;
- The contractor shall take all necessary measures and precautions to ensure that the execution of the works is carried out in accordance with environmental, social, legal and regulatory requirements, including those set out in this document;
- The contractor shall take all measures and precautions to avoid any disturbance in the local communities and among the users of the road, as a result of the project execution;
- The contractor shall, whenever possible, apply measures to reduce or eliminate any sources of disturbances;
- The contractor shall follow the provisions of this document, as well as the applicable legislation and standards, during the use, operation and maintenance of the camps and sites, in particular with regard to water supply and sanitation, solid waste management, handling and storage of dangerous substances, etc., and
- The areas occupied by the camps and sites must be recovered at the end of the project, when the contractor is demobilized, through the replacement of previously existing conditions, unless other uses are intended.
- The contractor must develop and implement a camp management plan

## 2.7 Sourcing of water & other materials

Naturally occurring construction materials such as water, fine sand and aggregates are available in the project area; where applicable

approvals may be required for the extraction of raw materials. Materials that will be used are:

**Water:** Water for the proposed road rehabilitation and construction works can be sourced from streams/rivers within the vicinity of the 40km Gujba-Ngalda road.

**Fine Sand:** Like water, river sand can be sourced from some of the rivers along the project area. The river sand may be compensated with fine aggregates (quarry dust) if river sand is found not to be in sufficient quantity for the roads' rehabilitation and construction.

**Aggregates:** Aggregates (coarse sand) and laterite can be purchased and stock piled from existing quarries in the local government areas of the State. The aggregates must meet the requirements stipulated in relevant sections of Federal Ministry of Works General Specification, Vol. II (Roads and Bridges).

**Bitumen:** Bitumen is also available in the State and can be purchased.
### **CHAPTER THREE: PROJECT ALTERNATIVES AND OPTIONS**

## 3.0 Introduction

The objective of the MCRP is to support the Government of Nigeria towards rehabilitating and improving critical service delivery infrastructure, improving the livelihood of conflict and displacement-affected communities, and strengthening social cohesion in the States of Borno, Adamawa and Yobe. Consequently, this chapter contemplates the different alternatives and options that were considered for the proposed project in line with the overall objectives of the project in Yobe State. These alternatives include taking no action, using alternative travel modes and alternative alignment construction as other methods of achieving the objectives of the sub-project. The options considered include the 'No Project' Development, 'Delayed Project' Development and Immediate Project Development.

### **3.1** Analysis of Alternatives

The study alternatives considered here have properly examined the need for the project and the option that best suits the project purpose. Potential alternatives include:

- (1) taking no action;
- (2) using alternative travel modes;
- (3) alternative alignments construction; and,
- (4) construction of new roads.

In comprehending the development options and scenarios, the following main factors were also considered:

- availability of raw materials,
- process facilities,
- cost effectiveness and more effective utilization of resources

#### 3.2.1 No-Action Project Alternative

A no-project or no-development scenario is one in which the 40km Gujba-Ngalda road intervention project is not executed. With the "no-project" option, this road will typically continue to be in use with the existing weak agricultural marketing service levels being experienced... This coupled with the safety concerns and the increasingly worsening security challenges in the project area, will further contribute to inadvertently driving prices of basic items high and probably beyond the reach of the rural dwellers. Inadvertently, this would have an undesirable impact on the local and national economy, as these prices are highly sensitive to availability of a good road network. This option is therefore unsuitable, as it would inhibit meeting the MCRP development objectives and the nation's growing transport needs.

#### 3.2.2 Using Alternative Travel Modes

Other modes of efficient passenger travel and goods movement over long distances include; air, rail, transit, and marine. With regards to

goods movement in this part of the country the only realistic alternative to trucking that has the advantage of cost effectiveness and preservation of the quality of goods, is rail. Nevertheless, the ongoing insurgency is a worrisome situation in the northeast and has continued to be a deterrent to such investment decisions as currently, there is no passenger and goods rail service that would offer this extensive linkage between the neighboring communities identified that would be serviced by this road intervention project. Furthermore, the other modes of travel are not seen as effective alternatives.

# 3.2.3 Alternative Alignments

Alternative alignment options can be achieved from modification or changes to the engineering design. However, this could be more expensive as this implication would attract more costs in terms of additional raw materials required for the work. Also, it would be more disruptive as a result of the likelihood of physical and economic displacement, prolonged road closures and traffic diversions, which can lead to loss of revenues from this diverted traffic and increased costs from additional construction materials. There is also a possibility of very high costs for property acquisitions from land take and compensation claims, lost employment and reduced access. This alternative is not suitable as the likelihood of additional cost implications is high.

# 3.2.4 Construction of new Road

The Nigeria road network is relatively dense consisting of about 194,000 km of roads. This includes 34,000 km of federal roads, 30,000 km of state roads and 130,000 km of registered rural roads<sup>1</sup>. The road density is about 0.21 km of roads per square kilometre. In spite of the relatively high road density, the rural accessibility index for Nigeria (defined as the proportion of the rural population living within 2 kilometres away from an all-weather road) is low, at only 25.5 percent, leaving about 92 million rural dwellers unconnected. Rural access is limited where the poor population is concentrated.

The 40km Gujba-Ngalda road under consideration in this sub-project is already in existence, however, due to deteriorating conditions, over time, there is an increasing demand for its rehabilitation and the conservation of road/transport assets network in Yobe State, as most are no longer in their proper state. Unfortunately, a new road will likely attract additional costs related to the terrain; the attendant budgetary provision required for the construction translates to a higher aggregated expenditure on costs such as security personnel to protect construction team due to the insurgency (depending on road route eventually selected), the fuel for running equipment and bituminous product prices locally, technology used in road works, contract

<sup>&</sup>lt;sup>1</sup> RAMP2 Project Appraisal Document (PAD)

management practices, and the availability and quality of road construction materials.

Consequently, considering the urgency and of the need of this subproject by the communities, the proponent considers that embarking on the construction of an entirely new road, as opposed to rehabilitation of this existing Gujba-Ngalda road would attract significantly higher intervention costs, that will undoubtedly require more materials and will in the long run take a longer time before the benefits of the project can be enjoyed by these communities. Thus, the option of constructing an entirely new road is not practicable, in this regard.

# **3.3 Development Options**

# **3.3.1 No Project Development**

This option assumes the status quo is maintained with no development of the proposed road intervention works. Ultimately, the adoption of this option will imply that the envisaged socioeconomic and health benefits of the project will not be realised. With the increasing focus of the government at both the Federal and State levels on the agricultural sector, a lack of development of the roads infrastructure to enhance the transport linkages in Yobe State could hamper the envisaged socioeconomic development of the State and the neighboring States to which Yobe has strong economic ties (such as Borno & Taraba States). Inadvertently, rural dwellers especially in Gujba, Wagir, Nyakire, Bukkiyel & Mutai communities would continue to experience losses from the poor motorability of the Gujba-Ngalda road, while the forces of demand and supply would mean that the prices of the agricultural items will remain high in the markets and may remain uncompetitive in comparison with goods from other States, thereby stifling the potentials of economic growth. Furthermore, travel time will continue to be long and arduous due to the current terrible condition of the road. Consequently, the 'No development' option is not appropriate on the basis that the road is of absolute necessity for transport of people, goods and is therefore vital for enhancing socioeconomic growth.

# 3.3.2 Delayed Project Development

This option implies that this planned road intervention sub-project will be delayed until a much later date. Adopting this option would suggest that there is a strong likelihood that population within the project area will continue to be denied a very good alternative route as opposed to the otherwise longer route out of Gujba. Also, with the current poor motorability of this road, travel time and travellers security along this road will continue to worsen. This would be further exacerbated during the wet season when the motorability along the road would be more difficult. Unintentionally, this will continue to challenge socio-economic development, as other alternative routes would take longer travel time and are therefore not as economically favorable. In addition, the delay may also result in unnecessary increase in the cost of the intervention project in the future, especially considering the impact of the inflationary forces on prices of materials further worsened by the security challenges in and around Yobe State. For these reasons, a "delayed Project Option" is unsuitable.

# 3.3.3 Road Surfacing Alternative

Roadway surfacing is an increasingly relevant consideration for road interventions. Consequently, three major roadway-surfacing options have been proposed for this MCRP road intervention project. The Road Economic Decision (RED) model has been used to select the most viable options. These three options are:

- Laterite Gravel Road Base
- Single Coat Bituminous Surface Treatment
- Double Coat Bituminous Surface Treatment

The third option using asphaltic concrete wearing course with thickness specified after the  $\mathbb{R}$  determination of base course bearing capacity has been selected for this road.

# **3.3.4 Immediate Project Development**

This option implies that the project will go ahead as planned. In general, all the interactions with the communities to determine the perceived impact of this road were positive. In fact, these stakeholders wanted the project to commence in earnest. The results of the public meetings and the completed questionnaires supported the project and considered it a necessity to promote economic development and reduce poverty in the region.

The "immediate project development" option will ensure that the construction and rehabilitation of this road will be carried out, by mobilising all materials, plant and equipment necessary for execution of intervention work. This would attract multiple benefits of improved transport access and enhanced road motorability, thereby providing an opportunity to shorten the travel distance, especially for travelers from Gombe to Damaturu or Maiduguri who can now bypass Potiskum. This would derive additional benefits such as improved local economy from encouraging trade among neighboring communities, restoring and growing confidence of the people in their security as they travel, while business, trade and conveyance of farm produce to and from Gujba is unrestricted.

So, the rural communities in these areas will begin to enjoy the environmental, social, economic and health benefits of this intervention project as highlighted in this ESIA report. This option is therefore considered the most viable and is therefore most suitable for implementation.

## CHAPTER FOUR: DESCRIPTION OF THE PROJECT ENVIRONMENT

#### 4.1 Overview of the Project Environment

Situated in the North Eastern flank of Nigeria, Yobe State occupies a landmass of 45,502 square kilometers. Yobe State shares borders with Borno State to the East, Gombe State to the South, Bauchi and Jigawa States to the West and Niger Republic to the North. Yobe State lies between 12°00'N & 11°30'E. The State has 17 Local Government Areas with Damaturu as the capital city. This road intervention project is in Gujba LGA. Map of Yobe is shown in Figure 5.



Figure 5: Map of Yobe State; Source-INEC

# 4.1.1.Gujba LGA

The road intervention project starts from Gujba LGA, which has its headquarters in the town of Buni Yadi at  $11^{\circ}16'08''N 11^{\circ}55'49''E$  towards the south of the area; the town of Gujba lies in the north of the area. It has an area of  $3,239 \text{ km}^2$  (1,251 sq. mi).

The project area of Yobe State is typical of Savannah vegetation with the guinea savannah towards the southern part and Sahel savannah in the North.

# 4.2.1. Climate

Yobe state lies mainly in the dry Savannah belt; hence the state is dry and hot for most the year except in the Southern part of the State, which has a milder climate. Climate is determined by the interaction of the warm moist Tropical Maritime air mass and the hot and dry Tropical Continental air mass. The two air masses converge along the Inter-Tropical Convergence Zone (ITCZ), which moves in response to the seasonal disposition of the overhead sun.

# 4.2.2. Rainfall

The distinctly hilly nature of the terrain in Yobe presents a general topography that has significant impact on the local variations and pattern of rainfall. There are two distinct seasons; the dry and wet season. Rainfall in the State is highly irregular in space and time, which makes farming difficult since small differences in the amount and timing of rain received at a site may determine the success or failure of critical stages in vegetation development and hence crop production. The rains commence from around April till between the months of August and September with levels between 760mm -1051mm. The rainfall sometimes produces hailstorms.

# 4.2.3. Temperature

The climate of Yobe State is hot and dry for most periods, of the year. The rainy season usually ends in the month of November, which indicates the beginning of the dry season. The State falls within the North Eastern part of the country that has experienced a 1.2°C increase in average temperature in studies carried out with data collected between 1900 and 2005<sup>2</sup>. The State exhibits a remarkably high annual range of mean monthly temperatures.

Nevertheless, mean daily temperature could be as low as 20°C during the months of December and January when the cool dry Harmattan wind blows in from the Sahara Desert.

<sup>&</sup>lt;sup>2</sup> Odjugo, P.A. (2009). Regional Evidence of Climate Change in Nigeria. Journal of Geography and Regional Planning Vol. 3(6), pp. 142-150, June 2010

# 4.2.4 Geology

The geology of Yobe principally comprises crystalline and sedimentary rocks, underlain by basement complex rocks. The crystalline rocks are represented by older granites found in pockets of places in the southern part of the State. Another crystalline rock formation of younger age is located in the northwestern tip of the state in the Machina area. The older granite is Precambrian in origin consisting of metamorphic structures of gneiss and amphibolite's. The Biu basalts found in the southern end of the state are believed to have been extruded during the Tertiary/Quaternary periods as lava flows. However, the influence of climatic fluctuations is reflected in the superficial deposits overlaying most of Yobe State. This, for instance, has led to the deposition of series of longitudinal and traverse dunes around Yunusari, Yusufari, Machina, Geidam and Bade local government areas.

# 4.2.5 Drainage

Yobe State generally lies between 300m and 600m above sea level, except in the southern part of the state where volcanic rocks occur. The rock formation also contains water-bearing aquifers from which much of the water supply in the state is derived. The River Yobe, from which the state derived its name, is the biggest river in the state. It flows eastwards and drains into Lake Chad. It has a few tributaries, one of the most important being River Alkalam, where the famous yearly Bade fishing and cultural festival takes place

# 4.2.6 Agriculture

Yobe State is noted for agricultural production such as farming, fishing and livestock rearing, which provides employment to over 80% of the States population. This area falls within the Sudan and Guinea Savannah vegetational zones. While Yobe state is an agricultural state it also has rich fishing grounds and mineral deposits of gypsum, kaolin, and quartz. The State's agricultural products include: gum Arabic, groundnuts, beans, cotton. Yobe is also said to have one of the largest cattle markets in West Africa located in Potiskum.

# 4.2.7 Vegetation

There are two vegetation zones in the State. These are the Sahel in the North and the Sudan Savannah in the South. Vegetal cover is sparse as the grass grows in individual tufts leaving bare surfaces in-between. The grasses in the Sahel are short and tussocky, 0.5m to 1.0m high. They are interspersed with sand dunes are the most common types in Yobe. The acacia is a thorny, narrow leafed tree, fairly short and some times umbrella shaped. In the Sudan Savannah, the actual vegetation is made up of short grasses, 1.5m to 2.0m high, and some stunted tress. Typical trees include the Acacia, dum palm, silk cotton and baobab.

# 4.2.8 Ecological Problems

The increasing incidence of desertification is one of the most disturbing ecological problems faced in Yobe State. Wind Erosion is found to aggravate the problem by creating sand dunes in the northern parts of the state, especially in Yunusari, Yusufari, Geidam, Nguru and Machina areas. This has also led to soil degradation resulting to lower agricultural yields. Consequently, the social impact is that the communities and people living in these areas are seriously threatened such that the trend in migration is southwards. Furthermore, the poor management of the fragile land resources through deforestation, overgrazing, over-cultivation, bush burning, and adverse climatic conditions are identified as some of the factors responsible for the growing menace of desert encroachment. The more frequently experienced flooding events from torrential rains & flash floods have also continued to be a concern in Yobe.

# 4.3 Analysis of Environmental Media in Project Area

This section contains the results of analysis of one-season environmental media samples obtained from project site and thereafter tested to determine air, soil & water quality. Analysis of samples were undertaken at the Federal Ministry of Agriculture & Rural Development Laboratory in Kaduna (accredited by FMEnv), as the nearest laboratory to the project area because Maiduguri was inaccessible as at the time of conducting this study due to the security challenges that persisted along the Maiduguri-Damaturu road. Chain of custody that guided the quality control for sampling is contained in Annex 20. Constraint to this study was predominantly that of security concerns from the current insurgency that necessitates closure of the road from 4pm till 9am the following day.

# 4.3.1 Air Quality

Air quality assessment was conducted using MSA ALTAIR® 5x Multi Gas detector. All values of major air quality parameters were within FMEnv limits. The air quality levels from samples taken at three locations each for the 5-different villages along the 40km Gujba-Ngalda road were assessed and the outcome of the air quality tests showed that values were below the FMEnv standards for all the parameters considered (SPM, CO, NO<sub>2</sub>, VOC). This is as represented in Table 8.

rable of All quality standards along rokin sujba rigulaa road						
Description	SPM mg/ms	СО РРМ	NO2 PPM	H23 PPM	302 PPM	VOC PPM
Gujba	0.21	0	0	0.02	0.01	0.03
Ngalda	0.2	0	0	0	0.01	0.01
Bukkiyel	0.23	0	0	0	0	0

Table 8: Air quality standards along 40km Gujba-Ngalda road

Mutai	0.17	0	0	0.01	0.01	0.01
Wagir	0.17	0	0	0.01	0.01	0.01
FMEnv	0.25	0.02	0.06	0.05	0.26	0.15

Source: Field Survey, 2020

#### 4.3.2. Noise

Noise is ''unwanted sound'' while sound is periodic fluctuation of air pressure. The noise level within the project area corridor was measured on site. A total of five samples (three composites) noise quality study sites were selected and the measurement was done using Deselbe meter model PCEmsL1. FMEnv standard noise levels are presented in Table 8.

Duration per Day, hour	Permissible Exposure Limit, dB (A)
8	90
6	92
4	95
3	97
2	100
1.5	102
1	105
0.5	110
0.25 or less	115

**Table 9:** Nigeria's Standard Noise Levels (FEPA, 1991)

The noise levels of 40km Gujba-Ngalda road corridor showed mean noise values around Wagir were highest at 49 dB (A), which is still below the FMEnv limit. Maximum limit must have resulted from vehicular traffic, which were operational at the time of measurement. In general, the noise level of 40km Gujba-Ngalda road corridor was below the FMEnv maximum Limit. This is as shown in Figure 6, while Annex 16 presents table of measurements obtained.



Figure 6: Noise Level along 40km Gujba-Ngalda road Corridor

# 4.3.3.Water Quality

A total of eleven water samples; comprising nine samples with two control samples were collected using a 1-liter glass stopper to check for Physico-chemical qualities and 1-liter plastic cover to check for heavy metals. Groundwater samples were collected from the wells in each of different communities of Gujba, Wagir, Bukkyel, Mutei & Ngalda. Analysis of water samples for non-metals was carried out using the US-EPA 600/4-79-020-preparation procedure and method and water samples were analyzed using 100 Cary UV-VS spectrophotometer, while heavy metals in water were analyzed using Perkin Elmer Pinacle 500 Flame Atomic absorption spectrometer. Quality assurance measures that guided the sampling chain of custody presented in Annex 20.

The values for the surface water quality tests conducted are as presented in Figures 7 and 8. The values are all slightly higher than the acceptable limit of neutral showing an alkaline medium and if this water is used for the construction work it will cause damage to the roads as bituminous and asphalt layers performs better at pH 6. Water having pH of 11 and above as in the project area is aggressive towards the materials.



Figure 7: Surface Water Quality along 40km Gujba-Ngalda road Corridor

The pH values of groundwater in the study area ranges between 7.00 - 7.35, which is slightly basic. While the pH of the surface water ranges between 7.10 - 7.35 which is also slightly basic. This suggests that the surface water and ground water have a point of contact with one another. Also, the depth of the existing wells where groundwater is sourced is less than a few meters on average. This is in support of the thin nature of the chad formation within this axis. FMEnv maximum limit of pH in water is between 6.5-8.5.



Figure 8: Ground Water Quality along 40km Gujba-Ngalda road Corridor

### 4.3.3.1 Total dissolved solids (TDS)

The measure of the sum of the cations and anions dissolved in water is refers to as its total dissolve solid (TDS). The measured values of TDS of ground water in this corridor ranges between 66-416ppm, while that of the surface water ranges between 336-316ppm. 500ppm is FMEnv maximum limit of TDS for water.

#### 4.3.3.2 Dissolved Oxygen

Dissolved oxygen measured in the groundwater samples in the project area ranges between 2.4 - 4.1, while the surface water samples ranges between 1.0-3.5. These values are lower than the FMEnv maximum value for DO in water, which is 7.5.

#### 4.3.3.3 Exchangeable Cations

Presence of exchangeable bases in water contributes to shifts in the pH of the water to basic region of the scale and makes the water saltier. Basic pH adversely affects asphalt, which forms the pavements of the roads. While contact of salty water destroys the binding properties of concretes which forms the foundation of embankments of roads. exchangeable bases in surface and ground water in the area are high but the values are lower than maximum permissible limit of FMEnv.

# 4.3.3. 4Heavy metals

Contact between water and rocks or soil are the principal source of heavy metal ions in water naturally. Heavy metals can also be found in water as a result of pollution. Cadmium was not detected in any of the water sample; however, Lead was found in ground water samples near Gujba and the up-stream surface water in Bukkiyel. There was presence of zinc in all water samples. The range of concentration is between 0.370-0.450 in ground water. Surface water has zinc concentration range from 0.215-0.436ppm and the values are less than permissible limit of <1 in water sample. Iron was also present at concentration bellow 10ppm recommended by FMEnv.

# 4.3.3.5 Hydrocarbons

Total petroleum hydrocarbon (TPH) was not present in this corridor at extractable level. This was expected because the communities in the corridor hardly engage in activities that contribute to an increment of hydrocarbon in the environment.

### 4.3.3.6 Microbiology of Water

The most probable number of microorganisms (MPN) in ground water per 100ml ranges between 180-310/100ml while that of surface water ranges from 605-722/100ml. E.coli was absent in ground water but was present in surface water and this calls for health precautions for the construction/contractor staff as they may decide to use this water as an alternative for drinking. *Salmonella sp.* was present in Ngalda and absent in the other communities, while *Shigella sp.* was present only in water samples of Bukkiyel and Ngalda communities.

#### 4.3.4 Soil Quality

Soil samples were collected at depths of 0-30cm (top-soil), and 30-60cm (sub-soil). Generally, the soils on the surfaces of the road are sandy and silty. The characteristics of the soil in the project area are presented in Figure 9, while Annex 14 shows details of values obtained from analysis of soil samples.

#### 4.3.4.1 Textural composition

In roadways construction soil with high aggregate base course (ABC) are desirable in use under asphalt pavement, backfill materials and embankment works including underground utilities work within the roadways. Soil with moderate to high percentage of sand in the composition was observed for the 40km Guiba –Ngalda road as represented in Figure 10.



Figure 9: Texture composition of soil along 40km Gujba-Ngalda road Corridor



Figure 10: Sub-soil Quality along 40km Gujba-Ngalda road Corridor

#### 4.3.4.1 Soil Properties

The pH of both top and sub soil taken from the study area ranges from 6.60-7.45 indicating a range from slightly acidic to slightly basic, which is a good soil for roadway construction since asphaltic admixture and bitumen emulsion used in road construction are acidic. Soil plasticity which is its ability to undergo deformation without cracking depends partly on the moisture content and also the mineral composition of the

soil. The moisture content of soils in these corridor ranges from 3.1-10.2%, which is favorable for road construction.

The conductivity level of  $4\mu$ s/cm corresponds to osmotic pressure of 3.5 atm in the soil solution. In the project area, the conductivity of soil ranges from 0.0609-0.2641ds/m.

The Total Organic Matter (TOM) of soil sample collected in 40km Percentage organic carbon in the road corridor ranges between 0.019 -0.323%, this values are lower than FMEnv limit of 5%, while Total Petroleum Hydrocarbon (TPH) was present in all the soil samples but was undetectable in the sediments. The TPH range in the soil samples are between 14.8 - 22.6 and this is lower than FMEnv maximum acceptable limit in soil. However, generally, in the test for heavy metals, the concentrations of lead were higher than FMEnv Limit at places where they are present. Chromium zinc and cobalt were equally above the limit. However, Manganese concentration was below the The sources of these trace heavy metals are likely from limit. vehicular emissions that ply the Gujba-Ngalda road and the high values may be from the low-lying trajectory and topography of the surrounding area, which allows run-off from the road side soils to wash off heavy metals and deposit them in low lying areas.

The heterotrophic bacteria (HB) encountered in 40km Gujba-Ngalda road soil were proteus, pseudomonas, micrococcus, klebseila, bacillus and actinomycetes. The hydrocarbon utilizing Bacteria (HUB) were; pseudomonas, micrococcus, Bacillus, and Actinomycetes; while the heterotrophic fungi (HF) include Botrycis, Aspergillus, penicillium, mucor, candida and tricoderma. Hydrocarbon Utilizing Fungi (HUF) in the area includes Penicillium, Aspergillus, and mucor. (The microorganism count of 40km Gujba-Ngalda road corridor, at the period of sampling).

# 4.3.5 Flora and Fauna

The vegetation along the study area is predominantly of the Sudan savannah type, with scattered acacia trees. There is also an area of Sahel savannah, consisting of sandy soils and thorn scrub, which is located in the far north. The Sudan Savannah is characterized by the coexistence of trees and grasses. Dominant tree species predominantly belong to the Combretaceae and Caesalpinioideae, The dominant grass species were Andropogoneae, especially the genera *Andropogon* and *Hyparrhenia*, on shallow soils also *Loudetia* and *Aristida*. Much of the Sudan Savannah region is used in the form of parklands, where useful trees, such as shea, baobab, locust-bean tree and others are spared from cutting, while sorghum, maize, millet or other crops are cultivated beneath. Wild animals found in the study area include lions, leopards, and cheetahs, as well as elephants, giraffes, rhinoceroses, and numerous varieties of antelope. Several species of monkeys are found in the forests. Resident birds include bustards, guinea fowl, and storks. Reptiles include crocodiles and various lizards. Insect life is abundant, and the tsetse fly is found south of latitude 12° N whenever suitable conditions occur. include elephants, giraffe. Domestic animals include drought resistant animals like camel, cattle, donkeys and sheep.

# 4.4 Site Specific Environmental & Social Conditions

Site visits for reconnaissance have been carried out to assess the subproject environmental & social baseline conditions along the 40km Gujba-Ngalda road. Some environmental sensitivities observed are gully formation concerns, potholes, drainage & erosion issues while social sensitivities observed include delays in travel time & security concern along the road. Most of the commuters use cycles, tricycles and occasionally cars, Lorries and trucks. Other observations are as shown in Table 9, while Figure 11 is a map of 40km Gujba-Ngalda road indicating the environmental & social sensitivities.

True f	Tune of interact	Leasting	D: -+
I YPE OT	i ype of intervention	Location	Picture
ntal			
Sensitivity			
Drainage	Hydraulic structure -	Ν	
& Erosion	The existing culvert	11.4617	
	to be upgraded to	11	Serves Aller II
	effectively discharge	E	
	water	11.8886	
		12	Contraction of the second second
Gully	Damago to sido drain	N	
erosion	due to gully erosion	11 /5//	
CIUSIUII	Construction of	11.4J44 07	A state of the sta
	nroper side drainage	F	The second second
	hasing on the	∟ 11 8807	A CONTRACTOR
	northern side to	76	
	nrevent edge	, 0	
	depression of the		
	pavement from being		and the second s
	completely eroded		
			the Participant and a second

# Table 10: Baseline Environmental & Social Conditions ofsub-projects

Gully erosion	Road borders have been washed away the culvert. Construction of side drainage on the northern side of the road will aid channeling of water away from road.	N 11.4523 54 E 11.8793 79	
Erosion of drainage walls	Side drain: Construction of side drainage on the northern side of the road will prevent road damage.	N 11.4039 75 E 11.8384 51	
Gully erosion & flooding	Erosion forces have completely washed away the road at the entrance of Wagir community. The existing culvert is unable to accommodate the volume of water flooding the area. 4 ring culverts will be constructed to effectively discharge floodwater.	N 11.3576 54 E 11.8113 62	
Gully erosion	Hydraulic structure - Construction of new culvert for discharge of rainwater to prevent build up or flooding events.	N 11.34382 4 E 11.79379 0	

Erosion	Expansion of the existing culvert to enable passage of higher run-off water volume & provide effective channelization of run off.	N 11.30785 8 E 11.73103 16	
Safety	Disruptions in travel times between communities	N 11.45449 7 E 11.88077 6	
Security	Security concerns from travel delays deepened by flooding of roads.	N 11.35765 4 E 11.81136 2	



Figure 11: Map of 40km Gujba-Ngalda road showing Environmental & Social Sensitivities

## 4.5 Description of The Socio-economic Environment

In achieving the objectives of the study, a socio-economic survey was carried out in order to collect the baseline information of the project area. The approach adopted involved a combination of the following:

- 50 questionnaires were administered for data collection on existing livelihood opportunities, income, gender characteristics, age profile, health and transport access. Out of this number four were returned. Quality assurance measures taken include different samples taken from men, women and youth groups.
- Focus group discussion (FGD), conducted to obtain information about the analysis of existing formal and informal grievance redress mechanisms, the fears and expectations of the people. Separate sessions were held for the women to ensure that they were free enough to communicate gender related issues without fear of retribution. Pictures of the FGDs conducted are shown in Figure 15.
- Key informant interviews to elicit in-depth information about community structure, norms and values, among others
- Participant observation and estimation

A summary of socio-economic survey carried out in the project areas is summarized in the Table 10, while socioeconomic features of project area is shown in Figure 14.

Description	Category	No.	Percentage	Chart	Remarks
Age	18-30	14	33.3		This reveals that more than half of
	31-50	16	38.1		the persons interviewed are in the productive age hand of between 18-
	51-70	10	23.8	45	50yrs (71.4%) and so offers a
	71+	2	4.8	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	labour pool from which contractors can source for workers for the sub- projects.
Sex	MALE	26 16	61.9 38.1	Sex MALE Sex FEMALE	This indicates that the higher proportion of the men in the population interviewed (61.9%) will provide sufficient human capital from the communities that the contractor can recruit personnel for the execution of this project.

# Table 11: Socioeconomic characteristics of project area

Description	Category	No.	Percentage	Chart	Remarks
Length of	From Birth	28	66.7	Below 5 years	This implies that with 85.7% of
Community	Above 15	3	7.1	5-9 years	project area for over 10 years; there
	10-14 years	5	11.9	10-14 years	is every tendency that they will be
	5-9 years	6	14.3	Above 15 years	social challenges facing their
	Below 5 years	3	7.1	From Birth	communities.
				0 20 40 60 80	
Religion	Islam	42	100		Results show that all of respondents
	Christianity	0.0	0.0		were Muslims.
	Others	0.0	0.0		
Marital	Married	39	92.9	Married	Results obtained indicates that
Status	Single	2	4.8	4.8.3 Maineu	majority (92.9%) are married and this indicates the high positive
	Widowed	0.0	0.0	Single	impact this road project will have on
	Divorced/Sep arated	1	2.3	Widowed	the households in these family units
				92.9 Divorced/ Separated	
Occupation	Civil Servants	2	4.8	4.8 16.7	This suggests that two-thirds
	Other	7	16.7	26.2 Civil Servants	(76.2%) are either farmers or self
	Farmers	21	50.0	50 Farmers	the local and national economy by
	Self employed	11	26.2	Self employed Traders	creating opportunities for suppliers & vendors
	Traders	1	2.4		

Description	Category	No.	Percentage	Chart	Remarks
Income	Below 500	4	9.5		This implies that an improvement in
(weekly)	500-900	13	31.0	40 31 Below	the local economy will further enhance the earning capacity &
	1000-5000	3	11.9	30 500 500-900	income of persons in the project
	6000-10000	17	40.5	20 119 1000-	area.
	11,000 +	3	7.1	$10 + \frac{9.5}{10} + \frac{7.1}{5000} = \frac{5000}{6000}$	
				0	
				Below 500 500 500 500 1000 11000 11000	
Household	10+	0.0	0.0	· · · · · · · · · · · · · · · · · · ·	73.8% of families interviewed are
Size	7-9	20	47.6		between 4-9 persons in size. This implies
	4-6	11	26.2	0	that the sub-project will have significant
	1-3	11	26.2	26.2	impact on the persons in these family
				47.6	units.
				26.2	
Educational	FSI C/non-	10	23.8		Almost half of the persons
Level	formal	10	25.0		interviewed have formal education
	WASC/SSCE	6	14.3		(49.3%), while the other half
	Higher	2	4.8		background and therefore
	Certificate				consultation strategy will take this
	Islamic	24	57.1		into consideration when planning
	Studies				

# 4.5.1 Population

The approximate population in the project area is 559,169 based on the 2006 National census with annual growth rate of 3.5%. The inhabitants are predominantly Hausas and Kanuri's, while majority of them are Muslims with an average household size of eight (8) persons and living under nuclear and extended families; hence monogamy and polygamy family systems are being practiced.

# 4.5.2 Community Administration

Traditional and native systems of administration still prevail in the area under the jurisdiction of the Local Government Councils, being the third tier of government. Community leaders (Bulamas) exercise authorities in their domain which help in settling family disputes and communal conflicts. The Bulama's are directly answerable to the ward heads (Lawans), who also report to the District heads.

### 4.5.3 Land Use

The entire area falls under Gujba LGA, which was one of the worst affected by the activities of Boko Haram insurgency. The major communities along the Gujba-Ngalda road, within 40kms span from Gujba are Gujba, Wagir, Nyakire, Bukkiyel and Mutai and the people are predominantly farmers. Along the proposed road are some small villages such as Taashan Deffo, mostly inhabited by herdsmen of Fulani extraction who practiced trans-humans and seasonal migration. The entire LGA and the neigbouring Gulani were under the control of Boko Haram Terrorists (BHT) from November 2014 up to March 2015, when the area was liberated by the Nigerian troops. Nevertheless, in the rural areas where the project is located, land use is basically agricultural and residential with a small commercial and cultural mix; which would consequently imply that land acquisition concerns would have more impact on farmland, economic crops & residential properties.

#### 4.5.4 Land Tenure

Agriculture is the mainstay of the economy in the area due to the soil fertility, which is suitable for guinea corn and beans production. Men and women engage in rain fed subsistence and commercial farming to meet their staple food needs and for commercial purposes. They supply markets within and outside the state and the northeast region with their farm products. Land tenure system is based on family lineage; hence farmlands are owned by families. In addition to farming, family members rear animals, particularly cattle, camels and small ruminants (Socioeconomic features of project area is shown in Figure 14), while women engage in petty trading such as ground nut oil extraction, sewing and local food and beverages production as means of livelihood.

# 4.5.5 Transportation

Transportation means of people in the project area are mostly lorries and, except in few cases where tricycles are utilized. The use of motorcycle has been banned in the area since 2013 by the government security forces as a means of curtailing the activities of Boko Haram insurgents, while due to the muddy nature of the soil in the area; this terrain makes it difficult for people to ride bicycles, especially during the rainy season. These issues have further compounded the poor transportation situation, especially for vulnerable people going about their usual social and economic pursuits such as farming, schooling, accessing health facilities and markets etc.



Figure 12: Socioeconomic features of project area

# 4.5.5.1 Issues affecting Transportation

The major problems affecting transportation in the project areas include erosion, flooding of roads by nearby rivers and adjacent flood plains, sand piles, vegetation encroachment, potholes, and gullies. One-on-one interviews with community members revealed that even though the road is important as a route to connect Gujba to Ngalda with average vehicular traffic at 1552/day (from 9am – 4pm) from the traffic survey conducted as shown in Table 12, the bad state of the road has continued to make travel slow, unsafe and hinder access to the communities.

Description	Gujba - Ngalda			Daily	Percentage
	Day 1	Day 2	Day 3	Average	(%)
Heavy truck	28	65	110	68	4.3
Medium	76	88	111	92	5.9
truck					

Table 12: Socioeconomic characteristics of project area

Small truck	93	134	150	126	8.1
Large bus	2	29	95	42	2.7
Mini bus	177	154	129	153	9.9
Car	646	621	573	613	39.5
Tricycle	189	313	175	226	14.6
Bicycle	231	231	142	201	13.0
Push cart	16	30	48	31	2.0
Total	1458	1434	1,533	1552	100

Source: Traffic Survey, 2019

### 4.5.6 Infrastructure

The assessment conducted revealed that there are no structures within the impact corridor of the project area that would be physically displaced /demolished and neither are there any project affected persons that would be economically displaced by loss of access to business or livelihood as existing road alignment will be maintained in built up areas.

There are eight (8) educational institutions in the area: five (5) primary schools, two (2) junior secondary schools and one (1) senior science secondary school. The only senior science secondary school is situated in Gujba town. This few number educational institutions can be attributed to the general response to education caused by poor school enrolment, retention and completion as children from poor background, coupled with the bad nature of the road could not attain secondary level of education. Most of the inhabitants have only completed primary school and some have attended Qur'anic schools, while only few were able to complete secondary education and in exceptional cases tertiary school.

In addition, the project area has five (5) primary health care centres (PHCs) at Gujba, Wagir, Nyakire, Bukkiyel and Mutai where ante-natal and Routine immunizations services are being provided for women and children as well as other basic health care services for the other population. Cases that require serious medical attention are referred to either general hospital, Buni Yadi or Damaturu, both within the radius of 65kms.

#### 4.6 Gender and Gender-Based Violence Information

Nigeria ranks 118 out of 134 countries on the Gender Equality Index.<sup>3</sup> Women's disadvantaged position and lack of decision-making power in

<sup>&</sup>lt;sup>3</sup> British Council Nigeria. <u>Gender in Nigeria report 2012</u>; UNDP Human Development Report 2016. See: <u>http://hdr.undp.org/en/content/gender-inequality-index-gii.</u>

the social, economic and political spheres are reflected in policies, laws and resource allocation that thwart progress towards gender equality in the country. More than 70 percent of women live below the poverty line, and maternal mortality ratio is among the highest in the world at 576 per 100,000.<sup>4</sup> More than half of people living with HIV (3.2 million) are women (55 percent).<sup>5</sup> Girl enrolment in school lags behind boys, and represents one third to one quarter of classroom participants depending the state; and two-thirds of the 10.5 million out-of-school children, are girls.<sup>6</sup>

The wide diversity and distinct socio-economic, cultural and political contexts across Nigerian geopolitical regions and states results in different gender related vulnerabilities. While gender inequitable norms prevail throughout the country, these vary by region and interact with other structural, community and individual factors exposing women, girls and boys to some forms of GBV more than others. The socioeconomic status of women and girls in the northern zones lags behind those in the south: only 3 percent of girls in the North complete secondary school, over two-thirds aged 15-19 years are unable to read compared to less than 10 percent in the South, and 76 percent are married by age 18 in the northwest.<sup>7</sup> Child marriage, acceptance of wife beating, restricted movement of women and girls are more pronounced in the North, and the prevalence of sexual violence, conflict related GBV and SEA is higher than in the South. In the South FGM, IPV, physical violence by any perpetrator, trafficking and harmful widowhood practices are more prevalent.

The term 'gender-based violence' reflects the underlying and systemic gender inequality which is a key driver of violence. Gender inequality exists in Nigerian households and communities, as in every society in the world; it results in women and girls experiencing limited choices, as well as restricted access to resources and opportunities compared to men and boys. The unequal distribution of power between men and women, along with engrained norms and rigid expectations on gender roles are the core drivers of GBV. GBV cuts across culture, level of education and income, religion, ethnicity, and other demographic indicators.

Nigeria's national government has taken steps to penalize and address GBV and SEA, although a clear leadership with the leverage to garner multi sectoral support to address this complex problem seems absent. The institutional champion of women's and children's rights and GBV issues within the government is the Federal Ministry of Women Affairs and Social Development (FMWASD). But it has limited influence on

<sup>&</sup>lt;sup>4</sup> The 2013 Nigeria Demographic and Health Survey (NDHS). See: <u>https://dhsprogram.com/pubs/pdf/PR41/PR41.pdf</u>. <sup>5</sup> UNAIDS 2017 Data. See: <u>http://www.unaids.org/sites/default/files/media\_asset/20170720\_Data\_book\_2017\_en.pdf</u>.

<sup>&</sup>lt;sup>6</sup> NDHS 2013.

<sup>&</sup>lt;sup>7</sup> NDHS 2013; British Council Nigeria, 2012.

sectoral ministries who need to enforce policy, insufficient budgetary resources<sup>8</sup> and insufficient institutional capacity to enact its mandate.

The regulatory framework to address GBV, SEA and VAC is uneven because the Nigerian legal system is plural, and different legal systems co-exist, namely, the statutory law, Sharia law in the northern regions, and customary law in rural areas. The simultaneous application of this three-tier system creates differentiated degrees of protection to women's and children's rights<sup>9</sup> which varies in every state and its enforcement is weak. There is a lack of clear mandates regarding which institutions oversee child protection and the design and implementation of violence prevention strategies and provision of services. Insufficient budget allocation both at national and state levels, coupled with inadequately trained and staffed structures to provide social welfare, justice, education and health services that are women, child and survivor centered. While efforts to provide GBV survivors with basic response services is concentrated in the NE by international non-governmental organizations or the UN system, there are very limited government or non-governmental services in the rest of the country, those that exist are for the most part unregulated, uncoordinated and unpredictable.<sup>10</sup> This is aggravated by a generalized lack of trust of citizens, particularly women, in the criminal justice system to enforce the existing laws. Moreover, lack of awareness of laws and knowledge of rights, amidst a context dominated by social norms that legitimate the perpetration of abuse, stigma and underreporting, results in the consequent impunity of perpetrators, possible re-victimization of survivors and the reproduction of the cycle of violence.

Two key national laws address GBV, the <u>Child Rights Act</u> (CRA, 2003), and the <u>Violence Against Persons Prohibition Act</u> (VAPP, 2015) which have been passed by the Federal Capital Territory (FCT) but not by many of the 36 states, making them inapplicable in those that haven't adopted them. While CRA has been passed in 24 states, VAPP has been passed in 4 states in addition to the FCT. Where laws are domesticated, implementation remains weak as institutional capacities are weak (social welfare, police, family courts). In practice, the legal and judicial systems provide women and children with little protection against violence, and timely and adequate support services are scarce and often ill equipped to respond to survivors' needs.

# 4.6.1 Gender and Gender-Based Violence Information in Yobe State

There is a Gender Based Violence (GBV) working group in Yobe state co-chaired by the State ministry of women Affairs and social

<sup>&</sup>lt;sup>8</sup> <u>UN Women data from 2011.</u>

<sup>&</sup>lt;sup>9</sup> UN CEDAW 2017.

<sup>&</sup>lt;sup>10</sup> UNICEF 2018.

development (MWASD) and the United Nations Funds for Population Activities (UNFPA). The forum, which comprises of state and non-State stakeholders such as United Nations (UN) agencies, International Non-Governmental Organizations (INGOs) and civil societies monitors trend and coordinate responses to violence against women and children (VAWC). However, there is little or no information as to the functionality, credibility and capacity of these entities to provide the needed responses to GBV, especially at the community level. Most stakeholders do not have the capacity to provide services. FIDA, the Ministry of Health (MOH), Ministry of Justice (MOJ) and MWASD are not exceptions. Key agencies supporting these actors in service provision are UNFPA, UNHCRC and to some extent UNICEF when it comes to child protection. However, some of the biggest challenges in the state are lack of reliable data on service availability, human resources, ineffective management of primary health facilities and inability to link with secondary healthcare centres.

The Sexual Assault Referral Centre (SARC) was commissioned in September 2016 to deal with cases of rape and other sexual assault in the state. However, SARC staff do not yet seem linked to other Violence Against Women Group (VAWG) stakeholders in the state and there seems to have been no work done on creating awareness among communities, including women's groups, about its existence and how to access it to date. Outside Damaturu, women and girls have serious barriers in accessing healthcare due to inequality exacerbated by power imbalance in favour of men.

The main stakeholders doing psychosocial work in Yobe are UNFPA, UNICEF and MOWASD and local Non-Governmental Organizations (NGOs) who serve as partners to UN agencies. The UNFPA assesses the level of services as not up to Inter Agency Standing Committee (IASC) standards. Another key gap when it comes to psychosocial care is the lack of support given to the counselors. Many counselors come from the communities concerned and may have been experiencing low levels of trauma themselves, which can be further compounded by secondary trauma. The only support they receive is that which they provide to each other which risks recycling trauma within the same group.

There is also a need to conduct mapping of GBV service availability in the state to identify the service providers. The mapping should also assess the availability and quality of their services, institutional capacities as well as human resources availability to deliver the services. This is in line with <u>World Bank good practice note in</u> <u>addressing Gender Based Violence (2018)</u> aimed at strengthening response for project exacerbated GBV

# CHAPTER FIVE: DESCRIPTION OF ENVIRONMENTAL AND SOCIAL IMPACTS

## 5.1 Background

This chapter identifies the potential environmental and social benefits and related negative impacts likely to be associated with the proposed Yobe MCRP intervention sub-project.

### 5.2 **Project Area of Influence**

The immediate geographical area of influence of work is the area identified for the sub-project. The larger geographical area of influence covers Yobe State.

### 5.2.1 Physical Environmental & Social Media Influence

The physical environmental media to be potentially influenced by the activities of the proposed project are land (landscape), air quality, groundwater and any adjacent drain to any of the project sites. The landscape features include soil, flora (especially vegetation) and fauna at the proposed project site, which will be impacted by the project activities. Any adjacent drain to any of the project sites will be the recipient of runoff water from the project site. Any percolation of fuels through the soil may impact on groundwater resources. The air quality may also be impacted by dust and gaseous emissions from construction activities.

Also to be considered, the social media to be influenced by this project includes activities such as acquisition of land, physical or economic displacement and mobilization of workforce with accompanying challenges such as labour influx, Increase in spread of Communicable diseases, STDs such as HIV/AIDS and other STIs GBV, impact on the connectivity network within the community as soon as roads are rehabilitated.

It is essential to note that as people migrate, their risk of exposure to crime increases. By increasing mobility and access often in hitherto remote areas can inadvertently facilitate increase in crime and human trafficking. The construction phase of the projects can inadvertently, increase human trafficking risks. As labourers arrive, the demand for commercial sex workers may increase thus placing pressure on the surrounding communities. Local people many of whom may be faced with temporary or permanent displacement, with concomitant breakdown in social networks and social capital are at increased risk of exploitation.

# 5.3 **Project Activities of Environmental and Social Concern**

Activities of potential environmental and social impacts identified with the proposed project are outlined under four (4-No.) phases of the project activities; namely preconstruction; construction; operations/maintenance and decommissioning phases as shown in Table 13.

Project Phases	Activities
Preconstruction Phase Activities	Preconstruction phase activities include among others: Siting of workers camp, Mobilization of workforce and signing of the code of conduct Training of workforce on OHS Establishment of health camps Provision of first aid equipment Procurement of PPEs Removal of trees and vegetation Assessment of existing project location, selection of beneficiary institutions, field studies and environmental screening; Preparation of environmental and social screening reports; Environmental and Social Management plan and preparation and implementation of the Resettlement Action Plan; Statutory permitting activities from Yobe WMA/
Construction Phase Activities	Construction phase activities include among others: Earthworks Rehabilitation work; Mobilization of equipment, materials and personnel to site Identification of storage area for construction material; Transportation and handling of materials and equipment; Civil & Construction Works Construction of waste bin bays (where applicable); and Disposal of construction waste/rubble and waste in general. Installation of safety signage

Operations ar	nd Operations and maintenance phase activities			
Maintenance	include:			
Phase Activities	Housekeeping;			
	Waste management (collection and disposal);			
	Maintenance and repair works; and			
	Materials management and storage (including			
	personal protective equipment, etc.).			
Decommissionir	Removal of construction equipment;			
Phase	Disposal of construction spoil and waste in			
	general;			
	Dismantling of temporary work camp of the			
	contractor; and			
	Waste management			
	Compensatory tree planting where necessary			

# 5.4 Identification of Potential Positive Impacts

In the course of the safeguards studies carried out for this road, both positive and negative dimensions of project-attributable impacts were identified. A detailed impact analysis is useful for the purpose of optimizing project benefits and reducing harmful impacts of interventions. Provided in Tables 14 are the positive impacts associated with this road sub-project.

No.	Impact		Key receptor(s)	Evaluation
1	Improved		Community	The proposed project when
	access	to	leadership and users	completed will deliver these
	transport		of transport	benefits:
	infrastructure	in	infrastructure	Better road access
	communities			Improved transportation services
				for people in communities
				increased community access inter
				groups and inter communal
				relations.
				Reduce travel time for motorist
				travelling from Gombe to Damaturu
				and Maiduguri who will bypass
				Potiskum axis.
2.	Improved		Children of school	Pupils of secondary school age can
	access	to	age	now be able to attend and return
	education			from school due to reduced travel
				Guiba where the only secondary
				school in the area is situated.
3.	Improved		Farmers in	Livelihoods restoration by
	access	to	neighboring	increasing access to farmlands for
	farmlands	&	communities	agricultural productivity as well as

# Table 14: Evaluation of potential positive impacts.

No.	Impact	Key receptor(s)	Evaluation
	markets		nearby markets for commercial activities.
4.	Increase access to health services	Community members	Improved access for general population including pregnant women, children and people with disability in emergency situations
5.	Employment generation	Community members	The proposed rehabilitation/construction sub- project activities will create employment opportunities for skilled and unskilled labour during the construction and operational phases. Also, there are indirect employment opportunities such as food vendors, petty traders and suppliers of raw materials for construction. During the operational phase, job opportunities will be created for maintenance workers and suppliers, waste management companies, etc.
6.	Improvement in local and national economy	Neighboring communities, LGA and national economy	The creation of direct and indirect job opportunities during the construction and operational phases of the project will boost the local and national economy
7.	Stakeholders' engagement	State Government, LGAs	Improvement of public goodwill and satisfaction towards governance in Yobe State.
8.	Improvement in management of resources	Neighboring communities, State Government, MDAs	Provision of a lead way to drive the State Government towards ensuring improved infrastructure
9.	Optimal utilization of Ngalda/Garin Chindo irrigation scheme	farmers/communities	The rehabilitation of Gujba Ngalda road will in the area lead to the optimal utilization of Ngalda/Garin Chindo irrigation scheme which will in-turn boost the economy and increase sources of income to the people
10.	Capacity building and strengthening of institutions	State Government, MDAs	Capacity building through: Strengthening of facility rehabilitation works and supervision systems of personnel involved in sub-project activities, including improvement in institutional responsibilities for construction and maintenance. Transfer of skills

#### 5.5 Evaluation of Potential Adverse Impacts Associated with the Proposed Project activities

The World Bank's safeguard policies emphasizes preference for preventive measures over mitigation or compensatory measures, whenever feasible (Para 2, OP 4.01). Specifically, the mitigation hierarchy embraces a 4-step process, outlined as follows:

Step I: Anticipate and avoid risks and impacts;

Step II: Where avoidance is not possible, minimize risks and impacts; Step III: Once risks and impacts have been minimized, mitigate; and Step IV: Where residual risks or impacts remain, compensate for or offset, as appropriate.

The potential negative environmental impacts include mainly impacts on air quality, soil quality, noise levels, water quality, security and Occupational health and safety (OHS), while social impacts include travel disruptions, risks of labour influx, child labour, sexual exploitation and abuse, GBV and conflict. These are identified with appropriate mitigation measures proffered in the next chapter of this report.

# CHAPTER SIX: ENVIRONMENTAL IMPACT MITIGATION AND MONITORING PLAN

# 6.1 Background

The project is envisaged to be hugely beneficial to the participating communities and the state at large. The scale of the subproject is such that severe negative impacts are not anticipated. The negative environmental and social impacts will be localized in spatial extent, short in duration and can be reduced or minimized through compliance with the implementation of the appropriate mitigation measures contained in Table 15.
## Table 15: Environmental and Social Management and Monitoring Plan

No	Project Activity	Potential Impact	Proposed Mitigation Measures/ Actions	Resp onsi bility for mitig ation	Cost (NGN )	Param eters to be Measu red	Method of Measureme nt	Perfor mance Indicat or	Freque ncy & Locatio n of Monito ring	Respons ibility for Monitori ng	Cost of Monito ring (NGN)
I. Pr	e-Construction	Phase									
<b>A.</b> E	nvironmental	<b>.</b>		<u> </u>	1						
1a.	Mobilization of construction equipment, drilling equipment, machinery, heavy duty vehicles and construction of workers' camp	Deteriorat ion of local air quality due to the emission of dusts & gases	Maintain equipment & machinery to manufacturers' specifications by regular servicing to reduce carbon emissions. Use water to wet active areas for dust suppression. Conduct regular visual inspection of dust pollution and ensure appropriate intervention if dust levels are high. Train drivers/ workers on proper operation of vehicles and equipment to include fuel efficiency and anti-idling. Ensure no burning of waste on sites Use of tarpaulins to cover trucks transporting earth	Contr actor	400,0	Air quality parame ters (CO, NO <sub>2</sub> , SO <sub>2</sub> , CO <sub>2</sub> , SPM) Mainte nance records Driver' s trainin g records	In-situ measuremen t. Visual observation of records & interviews	FMEnv permissi ble limit	Weekly in the surroun ding commu nities	Environ mental & Social Safeguar d Officers, Yobe State Ministry of Environ ment (YSME)	100,000

			materials or spoil on public roads Ensure rehabilitation of disturbed areas once completed Resources/Community representatives Provide and enforce the usage of appropriate PPE			of approp riate PPE					
1b.	Siting of boreholes	Contamin ation	*Choice of suitable borehole location is to be jointly agreed with PCU and communities Pits should not be located too close to latrine facilities	Contr actor	No additio nal cost	Distanc e from latrines to borehol es	Water quality tests	FMEnv permissi ble limit	Weekly site activitie s	Social Safeguar d officers of PCU	No additional costs
2.	Mobilization of construction equipment, machinery, heavy duty vehicles and violation of workers' camp	Noise and vibration disturban ces from operation of heavy- duty vehicles Traffic congestio n and risk of road traffic	Select and use vehicles/equipment with lower sound power levels. Install suitable mufflers on engine exhausts and compressor components. Enforce appropriate speed limit to reduce vehicle noise levels. Restrict noise-generating activities strictly to normal working hours (i.e. 9am – 5pm). Respond promptly to noise complaints. Provide and enforce the	Contr actor	100,0 00	Noise level Usage of approp riate PPE	<i>In situ</i> measureme nt	Noise level at sensitiv e receptor s not to exceed FMEnv recomm ended level (90 dBA) for an 8 hour period	Weekly at Constru ction site and nearby commu nities	Environ mental & Social Safeguar d Officers, Yobe State Ministry of Environ ment (YSME)	50,000

	Green House gas Emissions	usage of hearing protection devices (ear plugs/muffs) for workers. Install appropriate safety signage and/or use signalers at strategic locations. Inform local communities in advance of road diversions & major activities likely to affect traffic. Enforce road safety standards traffic rules				
		Have in place a traffic Management Plan (TMP) *Maintain equipment &				
Use of Asphalt plant crusher		machinery to manufacturers'				
		specifications by regular				
		emissions.				
		*Train drivers/ workers on				
		vehicles and equipment to				
		include fuel efficiency and				
		*Ensure no burning of				

			wa	aste or any material on								
			sit	es.								
			*E	insure asphalt plant								
			op	erators are trained for								
				e of equipment								
З	Site clearing	Occupatio	•	Develop and implement	Contr		Clearly	Visual	Availahl	Wookly	Environ	
5.	for staging	nal	•	a project specific	actor	600.0	defined	observation		at	montal &	50 000
	aroa	accidonte		Occupational Hoalth	actor	000,0	bounda	and	numbor	construc	Social	50,000
	area	accidents		and Safety Plan		00		anu	and	tion	Social	
		injurios to					nes of	Biodivorcity	divorcit		Jaieguai	
		injuries to		(UHSP). UHSP (U			protect	Biodiversity		area	u Officers	
		workers					eu	Survey	y OI		Unicers	
		and risk		to: Deskibition of device and			areas		plant			
	Mahiliaatian of	to	-	Prohibition of drug and					species			
	Modilisation of	communit		alconol use by workers			- · ·		within			
	arilling	y nealth		while on the job.			Eviden		baseline			
	machine,	and	-	Provision of adequate			ce or		conditio			
	construction	safety		first aid, first aiders,			re-		ns			
	machinery,			PPE, signage (English			vegetat				Yobe	
	Plant &			and Hausa languages).			ion				State	
	Equipment		-	Restriction of							Ministry	
				unauthorized access to			Eviden				of	
		Security		all areas of high risk			ce of		Implem		Environ	
		breaches		activities			Erosion		ent		ment	
		from	-	Provision of specific			control		Traffic		(YSME)	
		insurgenc		personnel training on			measur		manage			
		У		worksite OHS			es		ment			
				management			drainag		plan			
			-	Ensure that staging			е					
				areas for contractor								
				equipment are								
				adequately delineated								
				and cordoned off with								

	reflective tanes and				
	harriore				
	- Any uncovered work				
	pits should have				
	appropriate signage				
	and protection around				
	them				
	- Workers should get a				
	daily induction/toolbox				
	before going on the				
	site and a refresher of				
	what happened on site				
	a day before				
	- Adoquato				
	Signage Off				
	construction sites				
	should be installed to				
	alert				
	community/drivers/ped	1,500,			
	estrians	000			
	- lighting and/or				
	reflective tapes and				
	signage integrated in				
	all worksites for safety				
	at night				
	- Ensure security				
	management plan is in				
	place (Annex 12) and				
	that employees refer to				
	it at all times				
	- appropriate security				
	monsures in place to				
	measures in place to				

			prevent harassment or kidnapping of workers								
4.	Mobilisation of personnel	Increase demand on	Establish worker's camp and provide all basic amenities (water	Contr actor	300,0 00	Availab ility of ameniti	Visual inspection	Public percepti on	Monthly at project	Environ mental Safeguar	80,000
		existing communit	<ul> <li>sanitation etc.).</li> <li>Prohibit workers from unauthorized accoss to</li> </ul>			es in worker			site and surroun	ds Officer	

		and sanitation infrastruct ure		community infrastructure						commu nities	Yobe State MCRP Yobe LGA	
5.	Site clearing for staging area & Workers camp Mobilisation of Machinery, Plant & Equipment	Loss of vegetatio n, removal of trees and shrubs and habitat destructio n	•	Restrict removal of vegetation and trees to the area of need only. Protect all vegetation not required to be removed against damage; Undertake quick re vegetation of exposed soils with indigenous plant species once construction is completed. Ensure construction of effective drainage system and use erosion protection structures such as riprap, gabions etc.	Contr actor	250,0 00	Clearly defined bounda ries of protect ed areas Eviden ce of re- vegetat ion Eviden ce of Erosion control measur es drainag e	Visual observation; and Biodiversity survey	Availabl e number and diversit y of plant species within baseline conditio ns	Weekly at construc tion area	Environ mental Safeguar ds Officer Yobe State MCRP	90,000
6.	Site clearing for staging area	Landscap e disruption and visual	•	Ensure staging area or burrow pit site considered is in a place jointly agreed between	Contr actor	300,0 00	Clearly defined bounda ries of	Visual observation; and	Availabl e number and	Monthly at construc tion	Environ mental Safeguar ds &	

		intrusion		PCU and community			protect		diversit	area	Social	
			•	Restrict removal of			ed		y of		Safeguar	
	Mobilisation of			vegetation and trees to			areas	Biodiversity	plant		ds	
	Machinery,			the area of need only.				survey	species		Officer	
	Plant		•	Protect all vegetation				,	within			
				not required to be					baseline		Yobe	
				removed against			Eviden		conditio		State	
	Burrow pit			damage.			ce of		ns		MCRP	
	sourcina		•	Wherever possible.			re-		-		_	
	s s an sning			avoid the removal of			vegetat		Site			
				existing mature trees.			ion		restorati			
				which form important					on and			
				visual focal points.					zero no			
			•	Ensure rehabilitation of					of			
				disturbed areas once					material			
				completed to restore					s &			
				the visual and					equipm			
				landscape integrity of					ent on			
				the area.					site			
			•	Remove all temporary					after			
				structures, waste.					construc			
				equipment and vehicles					tion			
				from site immediately					cioni			
				after construction								
B. S	ocial		1					I				I
7.	Siting of	<ul> <li>Unautho</li> </ul>	•	Pay full compensation	Contr		No of	Implementat	Record	Weekly	Social	
	workers camp	rized		for land acquired if	actor	500,0	arievan	ion of RAP	of	site	Safequar	100,000
		moveme		land is privately		00	ces/		arievanc	activitie	d officers	
		nts of		owned, leasehold or			Dispute		es	s	of PCU	
		construc		other legally binding			S		resolved	-		
		tion		rental payment			reporte				Grievanc	
		workers,	•	Explore all available			d,				е	

	construc	options while selecting	signed	Redress
	tion	worker's camp with the	code of	Committ
	equipme	objective of avoiding or	conduc	ee
Land	nt,	minimizing negative	t by	
acquisition for	machine	impacts on	contrac	
camp	ry and	communities and	ts and	
	heavy	maintaining	his	
	duty	constructive	worker	
	vehicles	relationships between	S	
	(during	local communities and		
	and	worker's camp		
	after	Enforce a 'closed' camp		
	working	policy unless otherwise		
	hours)	agreed and approved.		
	could	Workers shall comply		
	result in	with the agreed camp		
	trespass	closure hours.		
	ing,	Contractor shall		
	<ul> <li>Conflict</li> </ul>	implement suitable		
	arising	measures to maintain		
	from	the closed camp policy,		
	land	which may include		
	acquisiti	perimeter security		
	on	fences, security		
	<ul> <li>Damage</li> </ul>	controls and		
	to local	guardhouses,		
	land and	monitoring transfer of		
	property	goods into and out of		
	and	camps for contraband		
	create	and stolen goods.		
	amongst	*Contractor shall have a		
	local	Project Security		

	resident	Management Plan and				
	s a	should refer to it always.				
	sense of	*Contractor, as				
	their	appropriate, shall provide				
	privacy	adequate recreation				
	being	facilities for workers to				
	invaded.	reduce incentive for				
	<ul> <li>Resident</li> </ul>	leaving camps during				
	s may	leisure time.				
	feel	*Contractor shall limit				
	vulnerab	workers interaction with				
	le and	the community when				
	there	outside the camp e.g., by				
	may be	organizing transport				
	increasi	directly to and from the				
	ng	worksite.				
	incident	If community members or				
	s of	local businesses express				
	crime	grievances in relation to				
	and or	camp related				
	violence	activities/operations, the				
	and	Project shall respond to				
	threats	the grievance in				
	to the	accordance with the				
	safety of	grievance procedure				
	commun	outlined in the GRM and				
	ity	the Community Grievance				
	member	Procedure contained in the				
	s.	Stakeholder Engagement				
	<ul> <li>Disparit</li> </ul>	Plan (SEP).				
	y of pay,					
	increase					

	in						
	disposab						
	le						
	income						
	and						
	notontial						
	potential						
	avaliabili						
	ty or						
	illegal						
	substan						
	ces,						
	illicit or						
	culturall						
	V						
	inapprop						
	riate						
	lifestyle						
	choices						
	leading						
	to						
	incroace						
	lincrease						
	u 						
	tension						
	between						
	local						
	commun						
	ities and						
	the						
	workers						
	at						
	camps.						
		1	1				

8.	Preparation of Staging areas	Increased security risks due to storage of materials and equipmen t on site	<ul> <li>Deploy competent security personnel to secure project site.</li> <li>Provide adequate training of security personnel.</li> <li>Disclose site security arrangements to the Police and host communities.</li> </ul>	Contr actor	200,0 00	No of securit y person nel engage d	Records and Interviews	Zero security incident s	Monthly at Constru ction site and surroun ding commu nities	Environ mental & Social Safeguar d officers of PCU Local Vigilante Police	50,000
9.	Labour influx from employment on project	Threat to communit y culture, safety and security due to presence of workers, Gender Based Violence risks	Ensure community have priority opportunity to employment for skilled and semi-skilled work Promote equal opportunities for employment for all (both male & female) Develop an induction program including a code of conduct for all workers. The code of conduct will address the following aspect: Respect for local residents; No hunting or unauthorized taking of products or livestock; Zero tolerance of illegal activities such as child sexual exploitation and underage sex, prostitution,	Contr actor	350,0 00	Worker s manual , employ ment codes etc. Level of awarene ss of local culture by migrant workers. Grieva nce Redres s	Visual observation and interviews	Commu nity percepti on and level of satisfact ion.	Monthly at Constru ction site and surroun ding commu nities	Social Safeguar ds Officer – PCU Yobe LGA Police	75,000

	harassment of women,		System			
	gender based violence.		Ratio			
	purchase or use of illegal		of			
	druas. fiahtina:		migran			
	Disciplinary measures and		t to			
	sanctions (e.g. dismissal)		local			
	for infringement of the		worker			
	code of conduct and/or		s			
	company rules:		5			
	Commitment / policy to		Presen			
	cooperate with law		ce of			
	enforcement agencies		securit			
	investigating perpetrators		v			
	of crimes including gender-		y nerson			
	based violence		nel			
	Provide cultural		inci			
	sensitization training to					
	improve awareness of					
	workers to local cultures					
	traditions and lifestyles					
	Prohibit child and forced					
	labour					
	<ul> <li>Ensure contractor staff</li> </ul>					
	are informed of legal					
	consequences of child					
	labour to discourage					
	practice					
	<ul> <li>Ensure non-compliance</li> </ul>					
	Employment process to					
	include procedures for					
	include procedures for					

				Im ba Me •	engagem showing of birth a plement sed Griev echanism Limit th migrant engaging Engage security	nent wher verified are manda commu vance Rec ne numbe workers local wor comp personnel.	e ID date tory nity- dress er of by kers. etent								
II. C	onstruction F	h	ase												
A. Er	ivironmental Is	รรม	ies					1	1	1	1	r		1	
10.	Use c Workers Camp	f	Generatio n of sanitary waste from worker's camp	•	Ensure sanitary site for enforce u Ensure u SWMA a vendor evacuatio	provision facilities workers usage. usage of pproved v for v on & dispo	of on and Yobe vaste vaste sal.	Contr actor	250,0 00	Presen ce of functio nal sanitar y facilitie s on site Waste vendor license s and waste evacua tion docum entatio n	Visual Observation Interview	National Environ mental Protecti on (Manag ement of Solid and Hazardo us Wastes) Regulati ons 1991.	Weekly at Project Site	Environ mental & Social Safeguar d Officers YOBE SWMA	75,000

11.	Use of haulage trucks for sand & materials supply	Public safety, road accidents leading to injuries and fatalities	•	Train drivers on defensive driving Conveyance of materials to site shall be by appropriate transportation means to prevent damage or accidents Provide road signs and flag persons to warn of dangerous conditions of conveying materials such as the water trucks	Contr actor PCU Safeg uards Team	No additio nal cost	Availab ility of up to date drainag e maps of metrop olis/ project area	Visual Observation	Complai nts on disrupti ons	Weekly at project site	Environ mental & Social Safeguar d Officers Drainage dept. of Yobe Ministry of Environ ment	No addition al cost
12.	Use of drilling equipment, Earthworks, Groundwork s & Excavation, road rehabilitatio n activities Sourcing of materials (also from burrow pits)	Public safety, road accidents leading to injuries and fatalities affecting host communit y populatio n, which could lead to conflict/ unrest	•	Develop and implement a project specific Occupational Health and Safety Plan (OHSP). OHSP Ensure QA/QC control is established on inspection of materials, which are to be of best quality to prevent defective outcomes on construction sites Use tarpaulins to cover sand and other loose material when transported by trucks Ensure burrow pits are used for extraction of	Engin eerin g Cons ultant /Mini stry of Work s & Trans port Envir onme ntal Safeg uards	80,00 0	Availab ility of an Occupa tional Health and Safety Plan (OHSP) Availab ility of QA/QC plan for the works	Procurement planning procedures		Daily at project site	Environ mental & Social Safeguar d Officers	40,000

	Use of generators for power supply	and stoppage of activities.	<ul> <li>material only for project purposes and not commercial</li> <li>Ensure generators are operated by dedicated trained personnel</li> <li>Carry out regular servicing of generator to reduce release of harmful emissions</li> </ul>	Speci alist							
13.	Construction of lined and unlined drains	Aggravate d soil erosion, rain fall runoff and road breakages	Stabilize road sections that are prone to rainfall run off, erosion and road breakages prior to drain construction	Contr actor s	150,0 00	Compli ance to engine ering designs for drains	Visual observation Meeting minutes, and agreements	Reduced vulnera bility to erosion and road breakag es Complia nce to provisio ns of minutes and agreem ents	Project roads	Twice Monthly	
14.	Groundwork s and earthworks works	Soil impacts and sediment transport	<ul> <li>Vegetation (grasses) shall be cleared only when contractor is fully mobilised for construction.</li> <li>Vegetation clearance</li> </ul>	Contr actor /	No additio nal cost	Develo ped site Reclam ation Plan	Visual observation	Material s sourced from licenced quarries	Quarterl y at material borrow sites and	Environ mental & Social Safeguar d Officers	

		Risk of exacerbat ing erosion concerns Land degradati on and increased susceptibi lity to erosion due to sourcing of constructi on materials	•	(where necessary) and excavations shall be limited to the demarcated construction site. Backfill with excavated soil material where appropriate. Ensure that heaped sand delivered for concrete mixing/construction works is covered with tarpaulin to prevent wind and water transport of soil particles.	Engin eerin g Cons ultant		Spoil manag ement			Project site	Yobe State Ministry of Environ ment (YSME)	
15.	Groundwork & levelling, Drilling; Transportati on of materials and equipment;	Air quality deteriorati on	•	Deliver equipment necessary for construction and other materials when community is less likely to be impacted by dust from moving machinery, such as in the evenings or on weekends. Impose a speed limit	Contr actor	See I.A.1	Air quality parame ters (CO, NO <sub>2</sub> , SO <sub>2</sub> , CO <sub>2</sub> , SPM) Mainte nance	In-situ measuremen t. Visual observation of records & interviews	FMEnv permissi ble limit	Weekly in the surroun ding commu nities	Environ mental & Social Safeguar d Officers, Yobe State	See I.A.1

	Earthworks			for all vehicles and construction equipment shall be less than 30km/h within the transmission pipelines premises and less than			records Driver' s trainin g records				Ministry of Environ ment (YSME)	
			•	Sokm/n Within communities. Haulage trucks carrying sand shall be covered with tarpaulin. Develop proper excavation procedures for workplace			Usage of approp					
			•	Hydraulic concrete mixing machines shall be used as much as possible and regularly service all construction equipment and machinery. Fit all heavy equipment			PPE					
				and machinery with air pollution control devices, which are operating correctly.								
16.	Transportati on of materials and equipment	Vibration and noise nuisance	•	Hydraulic concrete mixing machines shall be used as much as possible and regularly service all construction	Contr actor	See I.A.2.	Noise level Usage of approp	Noise measureme nt	Noise level at sensitiv e receptor s not to	Weekly at Constru ction site and nearby	Environ mental & Social Safeguar d Officers	See I.A.2.

			•	equipment and machinery. Minimize noise from construction equipment by using vehicle silencers, fitting jackhammers with noise-reducing mufflers Maintain maximum sound levels not exceeding 80 decibels (dba) when measured at a distance of 10m or more from vehicles, plants and machinery. Train the operators on proper use and maintenance of tools, proper positioning of machinery on site Maintain noise levels below 80 dB			riate PPE		exceed FMEnv recomm ended level (90 dBA) for an 8 hour period	commu nities	Yobe State Ministry of Environ ment (YSME) Engineeri ng Consulta nt	
17.	All road construction & rehabilitatio n phase activities	Visual intrusion Dust	•	Ensure good housekeeping at the construction site. Ensure an acceptable post-construction site as per provisions in the contract. Remove all construction equipment from the site after	Contr actor	No additio nal cost	Docum ent housek eeping proced ures & plans for site	Visual observation	Quality Control/ Quality Assuran ce Standar ds	Daily on Site	Environ mental & Social Safeguar d Officers,	

18.	Movement of	Soil	•	Consult with State PCU on the designated areas for stockpiling of soil, gravel, and other construction materials; Excavate the foundations at the same time as the access roads (if needed) are built so that dug material is used immediately, avoiding the need to stockpile on site; Keep exposed soil and stockpiles damp by spraying with water when necessary during dry weather; Use tarpaulins to cover sand and other loose material when transported by trucks; and Fit all heavy equipment and machinery with air pollution control devices, which are operating correctly. Develop and implement	Contr		Emerge	Visual	FMEnv	Monthly	Ministry of Environ ment (YSME)	
	plant &	contamin		a site-specific Waste	actor	150,0	ncy	observation	Soil	at	mental &	50,000

	equipment to and from staging area to site	ation	•	ManagementPlan(WMP)Prepare and implementanEmergencyResponsePlanrespond to incident ofcnillage		00	Respon se Plan for spillage develo ped	Laboratory testing	Quality Standar ds	Project Site	Social Safeguar d Officers,	
			•	Ensure fuel storage tanks are installed in a bonded area and checked daily. Ensure regular maintenance of vehicles to avoid leaks of oil.			Soil quality parame ters				Yobe State Ministry of Environ ment (YSME)	
			•	dumping of fuel waste Ensure local communities are sensitized on need to avoid tampering with waste bins							Yobe State Environ mental Protectio n Agency (YOBE SWMA)	
19.	Use of plant and equipment with internal combustion engines	Release of Green House Gas emissions (drivers of global warming)	•	Maintain equipment & machinery to manufacturers' specifications by regular servicing to reduce carbon emissions. Ensure that the	Contr actor	200,0 00	Mainte nance records Trainin g records	Visual Observation Interview	FMEnv permissi ble limit for air emissio n	Weekly at Project Site	Yobe State Ministry of Environ ment (YSME)	80,000

			•	mitigation measures in B3 are carried out. Train drivers/ workers on proper operation of vehicles and equipment to include fuel efficiency and anti- idling. Ensure no burning of waste or any material on sites.			Eviden ce of waste burning				Yobe State Ministry of Environ ment	
20.	Use of workers camp	Sanitation issues and public health impacts	•	Provide bins on site for temporary storage of domestic waste such as lubricant containers, drinking water sachets and carrier bags/packaging materials. Dispose all construction and domestic waste at the approved dumpsites and in the approved manner. Ensure all trenches or excavations made during the construction works do not collect stagnant water, which could breed mosquitoes. Ensure access to toilets	Contr actor / Engin eerin g Cons ultant Envir onme ntal Safeg uards Speci alist	300,0 00	Presen ce of functio nal sanitar y facilitie s on site Waste vendor license s Waste evacua tion docum entatio	Visual Observation Interview	National Environ mental Protecti on (Manag ement of Solid and Hazardo us Wastes) Regulati ons 1991.	Weekly at Project Site	Yobe State Ministry of Environ ment (YSME) Yobe State Environ mental Protectio n Agency (YOBE SWMA)	

			•	for construction crew or provide temporary toilets (mobile toilets) for use where there are no existing ones. Ensure mobile toilets/sanitary provisions are provided to reflect gender types. Ensure regular toolbox meetings are held among contractor			n					
				workers to offer awareness on transmission of contagious or communicable diseases.								
21.	Operation of Machinery & Equipment Movement of materials	Occupatio nal accidents and injuries to workers and risk to communit	•	Develop and implement a project specific Occupational Health and Safety Plan (OHSP). OHSP to include but not limited to: Prohibition of drug and alcohol use by workers	Contr actor	220,0 00	OHSP develo ped No of trained first Aiders	Visual observation	Complia nce with Factory Act, 1990 Complia nce with	Monthly at Constru ction Site	Environ mental & Social Safeguar ds Officer	100,000
	Earthworks	y health and safety	-	while on the job. Provision of adequate first aid, first aiders, PPE, signage (English and Hausa languages).			Usage of approp riate PPE		ISO 14001 Occupat ional Health			

	- Use only trained			& Safety		
	personnel for welding		Usage	Standar		
	activities		of	ds		
	- Restriction of		signag			
	unauthorized access to		e and			
	all areas of high risk		demarc			
	activities		ations			
	- Provision of specific					
	personnel training on					
	worksite OHS					
	management					
	- Ensure that staging					
	areas for contractor					
	equipment are					
	adequately delineated					
	and cordoned off with					
	reflective tapes and					
	harriors					
	- Any uncovered work					
	- Ally uncovered work					
	appropriate signage					
	and protection around					
	tnem					
	- workers snould get a					
	daily induction/toolbox					
	before going on the					
	site and a refresher of					
	what happened on site					
	a day before					
	- Adequate safety					
	signage on					
	construction sites					

			•	should be installed to alert community/drivers/ped estrians Lighting and/or reflective tapes and signage integrated in all worksites for safety at night appropriate security measures in place to prevent harassment or kidnapping of workers								
22.	Construction of culverts, drainage basins/culve rts Construction	Occupatio nal accidents and injuries to workers and risk to communit y health and safety <b>Erosion</b> Risk of erosion and flood as a	•	Ensure location is properly cordoned off before construction activities are carried out Create awareness in neighbouring communities to ensure road users are aware of road intervention work As much as possible, ensure community minimises movement around the site and should be informed before this type of work is carried out Use appropriate	Contr actor	300,0 00	OHS Proced ures develo ped No of trained first Aiders Usage of approp riate PPE Usage	Visual observation	Complia nce with Factory Act, 1990 Complia nce with ISO 14001 Occupat ional Health & Safety Standar ds	Monthly at Constru ction Site	Environ mental & Social Safeguar ds Officer/ Engineeri ng Consulta nt	60,000

		result of a lack of proper drainage	•	signage along road to show work in progress Use of flagmen to divert traffic where required			of signag e and demarc ations					
23.	Rehabilitatio n and construction of box and pipe culverts.	Disruption in current flow of streams and rivers	•	Construct temporary diversions or re- channel streams and rivers temporarily Sensitise communities along road of work	Contr actor ; Super vision Cons ultant	150,0 00	Water Polluta nts	Water quality tests	Routine testing procedu res are being conduct ed	Daily	PCU ESS Unit; Yobe State Ministry of Env.	
24.	Construction /borehole drilling work activities	Generatio n of constructi on waste including spoils, debris and concrete	•	Develop and implement a site-specific Waste Management Plan (WMP) to include the following: Ensure segregation of waste to facilitate reuse and recycling opportunities. Ensure hazardous wastes are stored in labeled closed containers with secondary containment with 110% of storage containers. Ensure no burning of waste on site. Ensure usage of YOBE	Contr actor	200,0	Contra ctor's WMP Eviden ce of waste segreg ation Waste storage facility Waste vendor license s and waste	Visual Observation Interview	National Environ mental Protecti on (Manag ement of Solid and Hazardo us Wastes) Regulati on 1991.	Weekly at Project Site	Environ mental & Social Safeguar ds Officer YOBE SWMA	50,000

			SWMA approved waste			evacua					
			vendor for waste			tion					
			evacuation, processing			docum					
			& disposal.			entatio					
			·			n					
B. Soc	cial Issues		-			•	·		•		
25.	Construction and rehabilitatio n of road around markets, schools, community structures, etc.	Possible destructio n of road side market shops, schools, petty trading shops and houses existing on the project roads or on the ROW Grievance s	Early notification and sensitization of PAPs Limit demolition to temporary structures and utility lines on the ROW • Implement GRM Regular community consultations to ensure updates on school calendar, which would be aligned with work schedule to prevent closures or disruptions	Contr actor ; PCU ESS Unit; GRC	400,0 00 No additio nal cost	Contra ctors' Compli ance	Visual Observation	Complia nce with proffere d mitigati on measur es.	Monthly	PCU ESS Unit; Supervisi on Consulta nt	
		school									
		5511001						1			

		calendar									
26.	Road rehabilitatio n, borehole drilling, groundworks & construction activities	Increase in spread of Communi cable diseases, STDs such as HIV/AIDS and other STIs	•	Ensure access into construction site is restricted Free testing kits Provision of condoms Vaccinating workers against common and locally prevalent diseases; Monitoring of local population health data, in particular for transmissible diseases. Implementation of HIV/AIDS education program; Information campaigns on STDs among the workers and local community in collaboration WITH relevant HIV/AIDS management organizations in Yobe State.	Contr actor / Engin eerin g Cons ultant ; Yobe State Minist ry of Healt h	Eviden ce of inclusio n in the bid advert and contrac tor Record s of training and awaren ess conduc ted and evidenc e of GBV track protoco l prepar	Records inspection	Docume	Check and evaluate during bid evaluati on Once annually	Social Safeguar ds Officer - PCU Supervisi on consulta nt and GBV Specialist	780,000

							ed					
27.	Road rehabilitatio n, borehole drilling, groundworks & construction activities	Risk of GBV/SEA and VAC as a result of Labour Influx	•	Commitment / policy to cooperate with law enforcement agencies investigating perpetrators of gender- based violence; Provision of opportunities for workers to regularly return to their families; Provision of opportunities for workers to take advantage of entertainment opportunities away from rural host communities. Capacity building for local law enforcement and the Yobe State ministry of Women Affairs and child development to act on GBV complaints; Information and awareness raising campaigns for community members, specifically women and airls:	Contr actor	300,0 00	Eviden ce of inclusio n in the bid advert and contrac t Record s of training and awaren ess conduc ted and evidenc e of GBV track protoco	Records inspection	Docume ntation	Check and evaluate during bid evaluati on Once annually	Social Safeguar ds Officer - PCU Supervisi on consulta nt and GBV Specialist	80,000

	•	Provision of					
		information to the		prepar			
		project corridor about		ed			
		the contractor's policies		64			
		and Worker Code of					
		Conduct (where					
	-	Enforcement of laws on					
	•						
		sexual violence and					
		numan traincking.					
	•	Include in the bid					
		document and also in					
		the contract the need					
		for contractor to draft					
		and sign the following:					
	•	Company's code of					
		conduct for prevention					
		of GBV and VAC;					
	٠	Manager's code of					
		conduct for prevention					
		of GBV and VAC					
	٠	Individual's code of					
		conduct for prevention					
		of GBV and VAC					
	٠	Community and					
		workers' training and					
		community					
		sensitization on					
		GBV/SEA/VAC;					
	•	Developing a specific					
		internal "Reporting and					
		Response Protocol and					

				GBV sensitive GRM" to guide relevant stakeholders in case of GBV/SEA/VAC incidents								
<b>C. O</b>	perational Phas	se										
28.	Operation of workers camp prior to demobilisation of facilities	Generatio n of sanitary waste from worker's camp	•	Ensure provision of sanitary facilities on site for workers and enforce usage. Ensure usage of YOBE SEPA approved waste vendor for waste evacuation & disposal.	Contr actor	250,0 00	Presen ce of functio nal sanitar y facilitie s on site Waste vendor license s and waste evacua tion docum entatio n	Visual Observation Interview	National Environ mental Protecti on (Manag ement of Solid and Hazardo us Wastes) Regulati ons 1991.	Weekly at Project Site	Environ mental & Social Safeguar ds Officer - PCU Supervisi on consulta nt and GBV Specialist YOBE SWMA	50,000
29.	Commissionin g of borehole & road tests	Generatio n of constructi on waste and debris	•	Develop and implement a site-specific Waste Management Plan (WMP) to include the following: Ensure segregation of	YOBE MOW R/ Contr actor	Part of Mainte nance cost	WMP for mainte nance activiti es.	Visual observation	Manage ment of Solid and Hazardo us	Daily during mainten ance works at project	YSME YOBE SWMA	Part of operatio n cost

			<ul> <li>waste to facilitate reuse and recycling opportunities.</li> <li>Ensure hazardous wastes are stored in labelled closed containers with secondary containment</li> <li>Ensure no burning of waste on site.</li> <li>Ensure usage of Yobe SWMA approved waste vendor for waste evacuation, processing &amp; disposal.</li> <li>Site visit to site at the completion of project to ensure no waste is left behind.</li> </ul>			Waste vendor licence s Waste docum entatio n		Wastes Regulati ons of 1991.	site		
Soc	ial Issues										
30	Creation of borrow pits	Public health from formation of stagnant pools for mosquito larvae breeding	*Ensure current system can handle improved drainage (prevent runoff erosion/ reservoir overflow) to prevent water stagnation. *Coordinate construction phases with dry season • *Develop and implement plan to deal with impacts	Contr actor	No additio nal costs	Eviden ce of Occurr ence Report ed inciden ce of floodin g/	Complaints received, resolution documented	PCU Safegua rd Speciali st	Quarter ly At the beginni ng of the Mainten ance -	PIU Engineeri ng Consulta nt	No addition al cost

						reduce d drainag e capacit y during constru ction					
31.	Interactions between Contractors and community	Child labor and school drop out	<ul> <li>Ensuring that children and minors are not employed directly or indirectly on the project by having in place an auditable &amp; verifiable employment process mandating provision of</li> </ul>	Contr actor	200,0 00	Plan in place & Execut ed Recruit ment Reports of contrac tor	Complaints	Child Rights Act 2003	Monthly	Yobe Social Safeguar ds Officer	50,000
			<ul> <li>Identification to demonstrate date of birth (DoB)</li> <li>Enforcement of legislation on child labor</li> </ul>								

			•	Ensure period meetings wi vulnerable groups ensure n marginalized	lic th to ot								
D. D	ecommissionin	g											
I. Er	nvironmental Is	sues	1										
32.	Demobilisation of facilities, plant & equipment	Risks of occupatio nal accidents and injuries to workers.	-	Develop & implement project specif Occupational Heal and Safety Pla (OHSP) to include b not limited to: Prohibition of drug ar alcohol use by worke while on the job. Provision of adequa first aid, first aider PPE, signage (Englis and Hausa languages) Restriction unauthorized access all areas of high-ris activities. Provision of specif personnel training of worksite OF management Ensure that stagin areas for contract	a fic fic than ut nd ers te s, sh. of to sk fic on S ng or 2	Contr actor	Part of Mainte nance cost	OHSP develo ped No of trained first Aiders Usage of approp riate PPE Usage of signag e and demarc	Visual observation	Complia nce with Factory Act, 1990	Monthly at Constru ction Site	ESMWR	

			<ul> <li>adequately delineated and cordoned off with reflective tapes and barriers</li> <li>Workers should get a daily induction/toolbox before going on the site and a refresher of what happened on site a day before</li> <li>Adequate safety signage on construction sites should be installed to alert community/drivers/ped estrians</li> <li>lighting and/or reflective tapes and signage integrated in all worksites for safety at night</li> <li>appropriate security measures in place to prevent harassment or</li> </ul>			ations					
			kidnapping of workers								
33.	Reconnection of surface pipeline network	Water contamin ation	All surface pipelines disconnected prior to the expansion work to be properly reconnected before handover of project.	YOBE MOW / Contr actor	Part of operat ional cost	Regular inspecti ons of pipelin es	Visual observation	Complia nce with Factory Act, 1990	Monthly at Constru ction Site	Yobe State Ministry of Water Resource s	Part of operatio n cost

34.	Burrow pit decommissioni ng	Public health	*Level out hollow area of burrow to reduce ponding of water & stagnation *Revegetate area around the burrow pit to re- introduce natural habitat formation *Maintain drainage channels of burrow to reduce water collection in hollow *Use of brickets in stagnant pond formation areas to eliminate insect breeding *carry out burrow pit reclamation according to remediation plan (annex 16)	Contr actor / Engin eerin g Cons ultant	300,0 00	Plan in place & Execut ed	Complaints received, resolution documented	PCU Safegua rd Speciali st	Once during decom mission ing	PCU/Soci al Safeguar ds Specialist	40,000
35.	All decommissioni ng activities	Waste managem ent	<ul> <li>Re-vegetate areas around workers camp &amp; Maintenance equipment sites to restore the landscape.</li> <li>Ensure that any remaining waste streams created during</li> </ul>	Contr actor	500,0 00	Availab ility and proper use of PPEs - Availab	Transport for monitoring Records on frequency and location of waste disposal site	Commu nity road for mainten ance	Weekly	Contract or/ Engineeri ng Consulta nt PCU/Soci	50,000
Sub-Total Mitigation	8,350,000.00	Sub-Total Monit	toring	1,32	0,000.00						
----------------------	--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-------------------------------------------------------	-------------------------------------------------	------------------------------------	----------						
	Maintenance activities and waste generated during decommissioning activities are collected from the project sites and properly disposed before handing over the project.	ility and proper use of warnin g signs	of domestic and road maintenance waste	al Safeguar ds Specialist							

# 6.2 Additional Mitigation for Gender Based Violence (GBV)/ Sexual Exploitation and Abuse (SEA).

The specific measures to reduce and mitigate the risk of GBV/SEA in the project will include:

- a) GBV/SEA assessment of project.
- b) Mandatory signing of Code of Conduct on sexual harassment by Contractor's and their employees
- c) Appointment of NGO to monitor GBV/SEA in all projects/subprojects implemented by Yobe MCRP.
- d) Community and workers' sensitization on GBV/SEA
- e) Developing a specific internal "Reporting and Response Protocol and GBV sensitive GRM" to guide relevant stakeholders in case of GBV/SEA/VAC incidents,

f)

- g) Provision of referral units for survivors of GBV/SEA.
- h) Provision in contracts for dedicated payments to contractors for GBV/SEA prevention activities.
- i) Contractor and SPCU requirement to ensure a minimum target of female employment with incremental rewards for the attainment of this target.

The following actions are recommended for immediate implementation:

- Hiring a dedicated GBV/SEA specialist for the project.
- Preparation and Implementation of a GBV sensitive GRM for reporting cases of GBV
- Hiring NGOs at the state level to manage social risks associated with GBV/SEA in the project.
- Building and improving FPMU/SPCUs, local communities and other relevant stakeholders' capacities to address risks of GBV/SEA by developing and providing guidance, training, awareness and dissemination of relevant GBV/SEA materials to communities.
- Strengthening operational processes of Yobe state MCRP on GBV/SEA.
- Identifying development partners and cultivating pragmatic partnership on GBV/SEA prevention measures and referral services.
- Developing Code of Conduct for civil works contractor with prohibition against GBV/SEA.
- Strengthening consultations and making operational GBV/SEA specific grievance redress mechanism.
- Providing financial support for implementation of the GBV/SEA actions described here-in including training and awareness building for various stakeholders.
- Establishing the inter-ministerial committee to advance GBV/SEA actions described above.

Overall, GBV risks in the project area might include Intimate Partner Violence (IPV), public harassment including harassment, verbal insults, physical abuse, rape, harmful widowhood practices and women and child trafficking. Targeted support to women under the program could likely exacerbate these risks. Development and implementation of specific GBV risk prevention and mitigation strategies tailored to local contexts will be

critical. Guidelines for situation analysis of GBV and safe reporting guidelines in line with international best practices will be implemented. Further, all risks related to labour influx will have to be mitigated by participation of project beneficiaries/communities and involvement of project contractors and contractors' workers and consultant employees in identifying mitigation and implementing measures, including developing mitigation instruments such as 'Labour Influx Management Plan' (See Annex 15) or Camp Management Plan.

#### 6.3 Measures for Non-compliance to the ESMP in this ESIA

If the Contractor fails to perform any of these ESHS obligations or work under the Contract, the value of this work or obligation, as determined by the Project Manager, may be withheld until the work or obligation has been performed, and/or the cost of rectification or replacement, as determined by the Project Manager, may be withheld until rectification or replacement has been completed. In case of recurrence, the Resident Engineer (supervision) may decide other appropriate measure as contained in the contract including advising the client to call the Performance Security.

Failure to perform includes, but is not limited to the following:

- a) failure to comply with any ESHS obligations or work described in the Works' Requirements which may include: working outside site boundaries, excessive dust, failure to keep public roads in a safe usable condition, damage to offsite vegetation, pollution of water courses from oils or sedimentation, contamination of land e.g. from oils, human waste, damage to archeology or cultural heritage features, air pollution as a result of unauthorized and/or inefficient combustion. Specific monitoring plan is shown in Annex 13;
- b) failure to regularly review C-ESMP and/or update it in a timely manner to address emerging ESHS issues, or anticipated risks or impacts.
- c) failure to implement the C-ESMP e.g. failure to provide required training or sensitization;
- d) failing to have appropriate consents/permits prior to undertaking Works or related activities;
- e) failure to submit ESHS report/s (as described in Appendix C), or failure to submit such reports in a timely manner;
- f) failure to implement remediation as instructed by the Engineer within the specified timeframe (e.g. remediation addressing noncompliance/s).
- g) A written notification from the resident engineer 10 days after the agreed date for the submission of the monthly environmental reports if there is no written explanation submitted by the environmental officer of the contractor.
- h) Failure to submit a declaration of methods for the operations that request it, the Resident Engineer shall immediately suspend activities that are occurring without this approved document.

The employer shall be financially penalized if his workers at the workplace do not have their personal protective equipment (gloves, jackets, boots, etc.).

The contractors be penalized by a written note if they do not comply with the methodology approved for the work. In case of recurrence, the Resident

Engineer may decide other appropriate measure as contained in the contract including advising the client to call the Performance Security

### 6.3 Institutional Arrangements

The successful implementation of the ESMP contained in the ESIA depends on the commitment and capacity of various institutions and stakeholders to implement the ESMP effectively. Thus, the arrangement as well as the roles and responsibilities of the institutions and persons that will be involved in the implementation, monitoring and review of the ESMP are presented in Table 16 below.

S/ N	Category	Roles & Responsibilities
1	Federal	Approve disclosure of ESIA/ESMP in country
	Ministry of	Environmental monitoring to ensure country standards is complied
	Environment	with
2	Yobe State Ministry of	Environmental monitoring and compliance overseer at the State level Site assessment and monitoring of ESIA/ESMP implementation.
2	Environment	Encuring approval & disclosure of Environmental and Social
5	Safaguarda	consuling approval & disclosure of Litvitonmental and Social
	Saleguarus	Saleguards instruments to the public
	Unit	Facilitate M&E implementation and monitoring functions;
		Responsible for coordination to ensure that parties responsible
_		for implementation carry out their functions as and when due
4	PCU	Ensuring approval of fund for Environmental and Social safeguards
		unit and M&E implementation and monitoring functions;
		Ensure that the ESTA/ESMP is disclosed to the public Responsible for coordination to ansure that parties to implementation
		carry out their responsibilities as and when due
		Ensure that World Bank safeguards policies and country standards are
		adhered to by contractor and workers through supervision and funding
		of mitigation measures/FSMP
5	Environment	Environmental Safeguards Officer
	al & Social	Carry out supervision functions during construction to ensure that
	Safeguard	contractor and workers adhere to mitigation measures in the
	Units of the	ESIA/ESMP;
	PCU	Collate environmental baseline data on relevant environmental characteristics for monitoring and auditing
		Ensure that project activities are implemented in accordance with
		good practices and guidelines set out in the site specific ESIA/ESMP;
		Identify and liaise with all stakeholders involved in environment
		related issues in the project; and be responsible for the overall
		monitoring of mitigation measures and the impacts of the project
		during implementation.
		Social Safeguards
		Coordinate and ensures the implementation of the social aspects of
		the ESIA/ESMP
		Identify and liaise with all stakeholders involved in social related
		issues in the project;
	1	Conduct impact evaluation and beneficiary's assessment; and
		Establish portnorships Q lision with susseinsticute Community Descriptions
		Establish partnerships & liaise with organizations, Community Based
6	Contractor	Establish partnerships & liaise with organizations, Community Based Organizations (CBOs), Civil Society Organizations (CSOs).

 Table 16: Institutional Arrangement for ESMP Implementation

		Implement ESMP during project implementation
		Develop C-ESMP
		Ensuring staff good behavior/ practices including the use of PPEs and
		zero gender violence
		Compliance to BOQ specification in procurement of material and
		construction
		Hire Safeguards personnel implement ESIA/ESMP during project
		implementation
		Mitigate environmental and social Impacts
		Implementation of code of conduct for all staff
		Develop contractor ESMP (C-ESMP)
		Preparation of work plans for environmental and social management
		in line with the ESMP
		Ensure any changes during construction process that may have a
		significant environmental and social impact are communicated to ESO
		In time and managed accordingly.
		Maintain records of environmental incidents as well as corrective and
		preventive actions taken
		Supervision of implementation of all the measures and preparation of
		required Monitoring report
		Contractor should ensure that the safety officer conducts a Job Hazard
		Analysis (JHA) prior to the commencement of work to identify the
		Indzarus associated with the job activities
		Ensure all contractors and workers sign the code of Conduct (CoC)
		Browide adequate basic amonities and DREs to workers, and ensure
		that workers at work wear the PPEs
		Prenare and maintain records and all required reporting data as
		stipulated by the ESIA/ESMP for submission to the Supervising
		Consultant
7	Supervising	Consultant Supervise the implementation of the FSMP by the Contractors:
7	Supervising Consultant	Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation
7	Supervising Consultant	Consultant Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation Plans (CESMP) to ensure compliance with the ESMP
7	Supervising Consultant	Consultant Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation Plans (CESMP) to ensure compliance with the ESMP Review site-specific environmental enhancement/mitigation designs
7	Supervising Consultant	Consultant Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation Plans (CESMP) to ensure compliance with the ESMP Review site-specific environmental enhancement/mitigation designs worked out by the Contractor.
7	Supervising Consultant	Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation Plans (CESMP) to ensure compliance with the ESMP Review site-specific environmental enhancement/mitigation designs worked out by the Contractor. Develop of good practice construction guidelines to assist the
7	Supervising Consultant	Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation Plans (CESMP) to ensure compliance with the ESMP Review site-specific environmental enhancement/mitigation designs worked out by the Contractor. Develop of good practice construction guidelines to assist the contractors in implementing ESMPs.
7	Supervising Consultant	SuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSupervise
7	Supervising Consultant	Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation Plans (CESMP) to ensure compliance with the ESMP Review site-specific environmental enhancement/mitigation designs worked out by the Contractor. Develop of good practice construction guidelines to assist the contractors in implementing ESMPs. Prepare and submit regular environmental monitoring and implementation progress reports.
7	Supervising Consultant	SuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSupervise
7	Supervising Consultant	SuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSuperviseSupervise
7	Supervising Consultant	Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation Plans (CESMP) to ensure compliance with the ESMP Review site-specific environmental enhancement/mitigation designs worked out by the Contractor. Develop of good practice construction guidelines to assist the contractors in implementing ESMPs. Prepare and submit regular environmental monitoring and implementation progress reports. Continuous interaction with the Engineer/ESSU regarding the implementation of the environmental/social provisions in the ESIA/ESMP
7	Supervising Consultant	Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation Plans (CESMP) to ensure compliance with the ESMP Review site-specific environmental enhancement/mitigation designs worked out by the Contractor. Develop of good practice construction guidelines to assist the contractors in implementing ESMPs. Prepare and submit regular environmental monitoring and implementation progress reports. Continuous interaction with the Engineer/ESSU regarding the implementation of the environmental/social provisions in the ESIA/ESMP Provides an independent oversight ensuring contractor adhere strictly
7	Supervising Consultant	Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation Plans (CESMP) to ensure compliance with the ESMP Review site-specific environmental enhancement/mitigation designs worked out by the Contractor. Develop of good practice construction guidelines to assist the contractors in implementing ESMPs. Prepare and submit regular environmental monitoring and implementation progress reports. Continuous interaction with the Engineer/ESSU regarding the implementation of the environmental/social provisions in the ESIA/ESMP Provides an independent oversight ensuring contractor adhere strictly to the engineering specifications and provide frequent reports on
7	Supervising Consultant	Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation Plans (CESMP) to ensure compliance with the ESMP Review site-specific environmental enhancement/mitigation designs worked out by the Contractor. Develop of good practice construction guidelines to assist the contractors in implementing ESMPs. Prepare and submit regular environmental monitoring and implementation progress reports. Continuous interaction with the Engineer/ESSU regarding the implementation of the environmental/social provisions in the ESIA/ESMP Provides an independent oversight ensuring contractor adhere strictly to the engineering specifications and provide frequent reports on contractor/ Clients compliance
7	Supervising Consultant	Supervise by the LSIA/LSIAP, for submission to the Supervising Consultant Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation Plans (CESMP) to ensure compliance with the ESMP Review site-specific environmental enhancement/mitigation designs worked out by the Contractor. Develop of good practice construction guidelines to assist the contractors in implementing ESMPs. Prepare and submit regular environmental monitoring and implementation progress reports. Continuous interaction with the Engineer/ESSU regarding the implementation of the environmental/social provisions in the ESIA/ESMP Provides an independent oversight ensuring contractor adhere strictly to the engineering specifications and provide frequent reports on contractor/ Clients compliance Preparation and implementation of the Environmental and Social
7	Supervising Consultant	Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation Plans (CESMP) to ensure compliance with the ESMP Review site-specific environmental enhancement/mitigation designs worked out by the Contractor. Develop of good practice construction guidelines to assist the contractors in implementing ESMPs. Prepare and submit regular environmental monitoring and implementation progress reports. Continuous interaction with the Engineer/ESSU regarding the implementation of the environmental/social provisions in the ESIA/ESMP Provides an independent oversight ensuring contractor adhere strictly to the engineering specifications and provide frequent reports on contractor/ Clients compliance Preparation and implementation of the Environmental and Social Monitoring Plan during construction
7	Supervising Consultant	Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation Plans (CESMP) to ensure compliance with the ESMP Review site-specific environmental enhancement/mitigation designs worked out by the Contractor. Develop of good practice construction guidelines to assist the contractors in implementing ESMPs. Prepare and submit regular environmental monitoring and implementation progress reports. Continuous interaction with the Engineer/ESSU regarding the implementation of the environmental/social provisions in the ESIA/ESMP Provides an independent oversight ensuring contractor adhere strictly to the engineering specifications and provide frequent reports on contractor/ Clients compliance Preparation and implementation of the Environmental and Social Monitoring Plan during construction Supervision of contractor performance of implementation of the
7	Supervising Consultant	Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation Plans (CESMP) to ensure compliance with the ESMP Review site-specific environmental enhancement/mitigation designs worked out by the Contractor. Develop of good practice construction guidelines to assist the contractors in implementing ESMPs. Prepare and submit regular environmental monitoring and implementation progress reports. Continuous interaction with the Engineer/ESSU regarding the implementation of the environmental/social provisions in the ESIA/ESMP Provides an independent oversight ensuring contractor adhere strictly to the engineering specifications and provide frequent reports on contractor/ Clients compliance Preparation and implementation of the Environmental and Social Monitoring Plan during construction Supervision of contractor performance of implementation of the Construction and Work Camp Management Plan
7	Supervising Consultant	Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation Plans (CESMP) to ensure compliance with the ESMP Review site-specific environmental enhancement/mitigation designs worked out by the Contractor. Develop of good practice construction guidelines to assist the contractors in implementing ESMPs. Prepare and submit regular environmental monitoring and implementation progress reports. Continuous interaction with the Engineer/ESSU regarding the implementation of the environmental/social provisions in the ESIA/ESMP Provides an independent oversight ensuring contractor adhere strictly to the engineering specifications and provide frequent reports on contractor/ Clients compliance Preparation and implementation of the Environmental and Social Monitoring Plan during construction Supervision of contractor performance of implementation of the Construction and Work Camp Management Plan Hire Safeguards personnel implement EISA/ESMP
7	Supervising Consultant	Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation Plans (CESMP) to ensure compliance with the ESMP Review site-specific environmental enhancement/mitigation designs worked out by the Contractor. Develop of good practice construction guidelines to assist the contractors in implementing ESMPs. Prepare and submit regular environmental monitoring and implementation progress reports. Continuous interaction with the Engineer/ESSU regarding the implementation of the environmental/social provisions in the ESIA/ESMP Provides an independent oversight ensuring contractor adhere strictly to the engineering specifications and provide frequent reports on contractor/ Clients compliance Preparation and implementation of the Environmental and Social Monitoring Plan during construction Supervision of contractor performance of implementation of the Construction and Work Camp Management Plan Hire Safeguards personnel implement EISA/ESMP
7	Supervising Consultant	Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation Plans (CESMP) to ensure compliance with the ESMP Review site-specific environmental enhancement/mitigation designs worked out by the Contractor. Develop of good practice construction guidelines to assist the contractors in implementing ESMPs. Prepare and submit regular environmental monitoring and implementation progress reports. Continuous interaction with the Engineer/ESSU regarding the implementation of the environmental/social provisions in the ESIA/ESMP Provides an independent oversight ensuring contractor adhere strictly to the engineering specifications and provide frequent reports on contractor/ Clients compliance Preparation and implementation of the Environmental and Social Monitoring Plan during construction Supervision of contractor performance of implementation of the Construction and Work Camp Management Plan Hire Safeguards personnel implement EISA/ESMP Thorough supervision of the mitigation of the environmental and Social impacts such as labour influx and GBV Depenting and implement progress with the EISA/ESMP
7	Supervising Consultant	Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation Plans (CESMP) to ensure compliance with the ESMP Review site-specific environmental enhancement/mitigation designs worked out by the Contractor. Develop of good practice construction guidelines to assist the contractors in implementing ESMPs. Prepare and submit regular environmental monitoring and implementation progress reports. Continuous interaction with the Engineer/ESSU regarding the implementation of the environmental/social provisions in the ESIA/ESMP Provides an independent oversight ensuring contractor adhere strictly to the engineering specifications and provide frequent reports on contractor/ Clients compliance Preparation and implementation of the Environmental and Social Monitoring Plan during construction Supervision of contractor performance of implementation of the Construction and Work Camp Management Plan Hire Safeguards personnel implement EISA/ESMP Thorough supervision of the mitigation of the environmental and Social impacts such as labour influx and GBV Reporting any incidents or non-compliance with the EISA/ESMP to the PCU
7	Supervising Consultant	Supervise the implementation of the ESMP by the Contractors; Review the Contractors Environmental and Social Implementation Plans (CESMP) to ensure compliance with the ESMP Review site-specific environmental enhancement/mitigation designs worked out by the Contractor. Develop of good practice construction guidelines to assist the contractors in implementing ESMPs. Prepare and submit regular environmental monitoring and implementation progress reports. Continuous interaction with the Engineer/ESSU regarding the implementation of the environmental/social provisions in the ESIA/ESMP Provides an independent oversight ensuring contractor adhere strictly to the engineering specifications and provide frequent reports on contractor/ Clients compliance Preparation and implementation of the Environmental and Social Monitoring Plan during construction Supervision of contractor performance of implementation of the Construction and Work Camp Management Plan Hire Safeguards personnel implement EISA/ESMP Thorough supervision of the mitigation of the environmental and Social impacts such as labour influx and GBV Reporting any incidents or non-compliance with the EISA/ESMP to the PCU

		Making recommendations to the PCU regarding ESMP performance as part of an overall commitment to continuous improvement Supervise contractor performance of implementation of the Construction Campsite/Staging area Camp Management Plan/CESMP Prepare monthly safeguards report including recommendations to the PCU regarding ESMP performance as part of an overall commitment to continuous improvement
8	Yobe State Environment al Protection Agency	Inspection of project premises in order to ensure strict compliance with sanitation and waste management standards in the state. Collaboration with other MDAs at the State and Federal level, NGOs and Donor Agencies in environmental protection and management especially in areas of waste recycling etc.
9	Yobe LGAs (Gujba LGA)	Provision of oversight function across project within its jurisdiction for ESMP compliance. Monitoring of activities related to public health, sanitation, waste management amongst others.
10	Affected Community and Public	Promote environmental awareness. Review environmental and social performance report made available by PCU. Provide comments, advice and/or complaints on issues of nonconformity. Attend public meetings organized by the PCU to disseminate information and receive feedback. Identify issues that could derail the project and support project mitigation measures and awareness campaigns.
11	CDA	Ensure community participation by mobilizing, sensitizing community members;
12	NGOs/CSOs	Assisting in their respective ways to ensure effective response actions, conducting scientific researches alongside government groups to evolve and devise sustainable environmental strategies and techniques.
13	World Bank	Overall supervision and provision of technical support and guidance. Disclosure of ESIA/ESMP at World Bank external site Supervision mission to monitor PCU's implementation and performance of ESMP

The Yobe MCRP, and any institution participating in the implementation, will not issue a Request for Proposal (RFP) of any activity without the construction phase's Environmental and Social Management Plan (ESMP) inserted in, and will not authorize the works to commence before the contractor's ESMP (C-ESMP) has been approved and integrated into the overall planning of the works.

#### 6.4 Contractual Measures

Most of the mitigation measures are the obligation of the Contractor during the pre-construction and construction phases of the project. Consequently, the potential contractor will have to prepare their proposals taking into account the measures in Table 17 as well as the detailed general environmental management conditions during civil works.

#### Table 17: Contractual Measures

Action	Remarks
The measures as described in this	The non-inclusion of these measures in
ESIA shall be included in the tender	the proposal will lead to a

documents with appropriate flexibility to adjust these measures to site circumstances, and that the potential contractor will have to prepare their proposals taking into account these	disqualification of the proponent; The contract with the successful bidder should contain these environmental and social management measures as firm conditions to be complied with.
measures.	
Specifically, the measures should be translated into a suite of environmental specification that are written in the same language style and format as the rest of the contract document	This approach will ensure that the environmental and social controls integrate seamlessly into the tender document and are presented in a familiar form to the Contractor
Cost of mitigation measures be added to the cost of the contractual document	The contactor must take into account and put the cost for the environmental and social requirements specified in the ESMP.

# 6.5 Capacity Building for Implementation of ESMP and Permit Conditions

An initial assessment indicates that the capacity of the PCU for implementing this ESIA will require strengthening, especially in the area of implementing the World Bank's environmental safeguards policies, and the application & management, therefore requiring strengthening in order to close these gaps.

Consequently, a training Workshop will be organized to guide the implementation of the ESIA and topical areas of discussion would include the Permit Schedule, World Bank's Safeguards Policy triggered and environmental management. The training on the EISA implementations will include the Code of conduct for contractor and his/her labour force, public health and safety issues, occupational health, Grievance Redress Mechanism for the project, ESIA monitoring and reporting. The capacity building will also involve sensitization of workers on issues such as zero tolerance on child labour, sexual exploitation and abuse, labour influx, Gender Based Violence, HIV/AIDS and their mitigation measures.

The capacity building plan proposed to achieve this is provided in Table 18.

Activity	Target	Timeline/	Proposed	Cost		
-	Group/Particip	Duration	Facilitator	NGN		
	ants					
*Training Workshop on preparation of ESIA, Permit Schedule *World Bank	*Engineering Consultant -Resident Engineer, Clerk of Works	Prior to resumptio n/ commence ment of constructio n works.	Environmen tal Safeguards Specialist/ Consultant	350,000		
Safeguards Policy triggered and environmental management. *Road rehabilitation safeguard requirements	*Project Coordinator, Works Engineer, Planning Officer, Finance Officer Safeguard Officers *Contractor,	(1/2 day)				
*Sensitization of workers on zero tolerance for child labour, sexual exploitation and abuse, HIV/AIDS, labour influx, Gender Based Violence, and their mitigation measures.	contractor workers, Manager, Foreman, Engineers	Prior to resumptio n/ commence ment of constructio n works. (1/2 day)	Social Safeguards Specialist/ Consultant	300,000		
*Induction on occupational and public health and safety (OHS) requirements of the works and environmental management *Training on code of conduct understanding	All construction/ contractor workers	Prior to commence ment of constructio n works. (1/2 day)	Lead Contractor/ Engineering Consultant/ HSE-OHS Consultant	200,000		
*Risk assessment on road construction	All construction/ contractor workers	Prior to commence ment of constructio		300,000		

# Table 18: Capacity building plan for implementation of the ESMP &permit conditions

Activity	Target Group/Particip ants	Timeline/ Duration	Proposed Facilitator	Cost NGN
work projects		n works.		
*Conducting		(1/2 day)		
Health and				
Safety				
Assessments				
*Developing				
and				
implementing				
mitigation				
measures				
Total			1,1	50,000.00

#### **Description of cost breakdown**

Description	Cost (NGN)				
Professional fee for 2 Consultants for 2 days	400,000.00				
Rent/Hiring of facility (for 2 day training)	200,000.00				
Meals for participants - tea break	150,000.00				
Meals for participants (2 days)	200,000.00				
Workshop Materials	200,000.00				
Total	N1,150,000.00				

#### 6.6 Implementation Schedule

The activities related to environmental management and monitoring must be integrated in the overall construction schedule. The project implementation phase is estimated for 17 months for road construction & rehabilitation activities. The implementation schedule is presented in Table 18.

# Table 19: Implementation Schedule

S/ N	S/ Activity Description N		Pre (Mc	Preconstruction Construction (Month) (Month)								Operations Phase							
			1	2	3	4	5	6	7	8	9	10	11	12	14	15	16	17	
1	Clearance and Formal Disclosure of ESIA	PCU																	
2	Inclusion of E&S Requirements in bid documents	PCU																	
3	Allocating Budget for ESMP	PCU																	
4	Appointing Support Staff for ESIA	PCU																	
5	Review & Approval of Contractor's E&S Plans	PCU																	
6	Finalization of Engineering Designs	PCU/ Consult ant																	
7	Mobilization to site	Contract or																	
8	Site Clearing	Contract or																	
9	Construction Phase	Contract or																	
10	Implementation of Mitigation	PCU/ Contract or																	
11	Supervising ESMP Implementation	PCU																	
12	Monitoring & Reporting on ESMP Implementation	PCU/MD As																	
13	Environmental and Social Training	E&S Consult ant																	
14	Environmental and Social Auditing	PCU/SM E /Consult ant																	

#### 6.7 Estimated Budget for ESMP Implementation

The total cost for implementing the environmental and social management actions contained in this ESIA is Sixteen Thousand, Two Hundred and Sixty Five Thousand, Seven Hundred Naira Only (#16,265,700.00), and a Dollar equivalent of Fifty Three Thousand, One Hundred and Fifty Six Dollars Only (\$53,156.00). This is as shown in Table 20 of this report.

		Total <sup>*</sup>	<
#	Item	Local <del>N</del>	US\$
1	Mitigation (Including the cost of PPEs)	9,185,000	30,015
2	Capacity Building (including training on Code-of- conduct)	1,150,000	3,758
3	GBV, STIs and HIV Mitigation	750,000	2,451
4	Grievance Redress Mechanism	750,000	2,451
5	Consultations	500,000.00	1,634
6	Monitoring (including the cost of hand-held monitoring instruments)	1,452,000	4,314
7	Disclosure	1,000,000	3,268
	Sub-Total	14,787,000	48,324
8	Contingency (10% of sub Total)	1,478,700	4,832
	Grand Total	16,265,700	53,156

#### Table 20: ESMP Budget

Currency Unit = Nigerian Naira US\$1 = N306

#### 5.8 ESIA Disclosures

After the ESIA review and clearance by the World Bank, the information in Table 21 describes the process of disclosure.

#### Table 21: Breakdown of Disclosure process

s/n	Action	Remarks							
1	Disclosure on 2 state	The PCU will disclose the ESIA as required by							
	newspapers	the Nigeria EIA public notice and review							
		procedures							
2	Disclosure on 2 national	The PCU will disclose the ESIA as required by							
	newspapers	the Nigeria EIA public notice and review							
		procedures							
3	Disclosure at the Yobe	The PCU will disclose the ESIA as required by							
	State Ministry of	the Nigeria EIA public notice and review							
	Environment	procedures							
4	Disclosure at the Yobe	The PCU will disclose the ESIA as required by							
	Ministry of Works &	the Nigeria EIA public notice and review							
	Transport office	procedures							

5	Disclosure at relevant Yobe LGAs (Gujba LGA)	The purpose will be to inform stakeholders about the project activities; E&S impacts anticipated and proposed E&S mitigation measures.
6	Disclosure at the World Bank external website	The ESIA will be disclosed according to the World Bank Operational Policy on Disclosure on the external website.

# CHAPTER SEVEN: GRIEVANCE REDRESS MECHANISM<sup>11</sup>

#### 7.1 Introduction

Grievance redressed mechanism is an important aspect in projects and the redress of grievance is important to avoid unnecessary legal delays and cost overruns of the project and to ensure social accountability, inclusion, sustainability and transparency in the implementation activities, the Yobe State MCRP shall establish a mechanism to receive and act on complains and grievances by beneficiaries, stakeholders or project affected parties arising from activities being conducted by the Project, in the State.

Grievance Mechanisms are increasingly important for development projects where ongoing risks or adverse impacts are anticipated. For the proposed subprojects, grievances are likely to arise due to the following:

- i) Delay in civil works;
- ii) Conflict between construction workers and community members;
- iii) Unmanaged expectations;
- iv) Lack of information about the project
- v) Occupational Health and Safety Issues
- vi) Exposure to environmental hazards
- vii)

To manage these social and environmental risks and others, which cannot be foreseen now with a view to ensuring successful project development and implementation, experience has revealed that open dialogue and collaborative grievance resolution represent the best practice. The grievance mechanisms shall at a minimum be targeted at the following:

- i) Provide a way to reduce risk for projects,
- ii) Provide an effective avenue for expressing concerns and achieving remedies for communities;
- iii) Promote a mutually constructive relationship;
- iv) Prevent and address community concerns, and
- v) Assist larger processes that create positive social change.
- vi) Offer GBV sensitive channels to provide referral pathways for victims

#### 7.2 Grievance Redress Process

At the time that the 40km Gujba-Ngalda road construction is approved for implementation and contracts signed, communities will have been informed of the process for expressing dissatisfaction and to seek redress. The grievance procedure will be simple and administered as far as possible at the local levels to facilitate access, flexibility and ensure transparency. All the grievances will be channeled via the Grievance redress committee for each sub project at the sector level.

<sup>&</sup>lt;sup>11</sup> A GRM has been developed for the entire MCRP, however this GRM will be for the implementation of 40km Gujba-Ngalda road construction sub-project in Yobe state and will take bearing from the MCRP GRM.

There is no ideal model or one-size-fits-all approach to grievance resolution. The best solutions to conflicts are generally achieved through localized mechanisms that take account of the specific issues, cultural context, local customs and project conditions and scale. In its simplest form, grievance mechanisms can be broken down into the following primary components:

(i)Receive and register a complaint
(ii)Screen and assess the complaint
(iii)Formulate a response (within a specified time frame)
(iv) Select a resolution approach
(v)Implement the approach
(vi)Settle the issues
(vii)Track and evaluate results
(viii)Appeals process
(ix)Monitoring and reporting to project management to detect systemic problems;
(x) Learn from the experience and communicate back to all parties involved.

This GRM process framework is as shown in Table 22.

### 7.3 Grievance Redress Committee

A Grievance Redress Committee shall be constituted within the PCU to receive, and ensure satisfactory resolution of grievances. The main functions of the Committee are spelt out below:

- Receive grievances from member of the public;
- Evaluate grievances from affected persons concerning the application to them of the Entitlement Policy;
- Recommend to the Social Officer of the PCU as the case may be, solutions to such grievances from affected persons;
- Communicate the decisions to the Claimants';
- Hear appeals from persons, households or groups who, not being affected persons, believe that they are qualified to be recognized as affected persons, to recommend to the PCU whether such persons should be recognized as affected persons, and to communicate the decision of the PCU in that regard to the Claimants;
- Ensure that all notices, forms, and other documentation required by aggrieved persons are made available in Local language understood by people
- Promote establishment of GBV sensitive channels which provide survivor centered referral pathways
- Make provision for complainants to submit claims without fear of retribution.

Step	Category	Activities
1	<i>Reception and registration</i>	<ul> <li>Aggrieved person files complaints or grievances regarding any aspect of the project verbally, through phone call, sms, in writing or through a representative in English or local language.</li> <li>The Aggrieved person first instance of complaint is the ward level through the chairman or secretary of the GRC. If the site community GRC cannot resolve the complaint, then the matter is escalated to the project office (Yobe-MCRP). If still unresolved, then a notification to the Yobe State Citizen's Mediation Centre.</li> </ul>
		<ul> <li>All complaints are to be recorded by the implementing agency with the name of the complainant, address and location information, the nature of the grievance and the resolution desired.</li> <li>All grievances reported must be acknowledged within 48 hours of receipt by an official authorized to receive grievances</li> </ul>
2	Resolution	All grievances referred to the appropriate party for resolution

### 

•	Resolution	made	within	10	days	after
	receipt of g	rievance	e.			
•	If additiona	l inform	nation is	nee	ded, p	roject
					1 1 1 1 1	

- management can authorize additional 5 days for resolution which shall be communicated to the aggrieved person.
- Results of grievances disclosed to the aggrieved person in writing with an explanation of the basis of the decision.
   The Social Safeguards Specialist with
- The Social Safeguards Specialist with the support of other YOBE-MCRP PCU staff will coordinate the resolution of the grievances.

pursued through the legal system.

Appeals
 Aggrieved person dissatisfied with the resolution proffered to their grievances may file an appeal to the next level (LGA) in the GRM referral hierarchy.
 There will be no further redress available outside the resettlement project. In such cases, grievances would need to be

4	Monitoring	• During project implementation and for at least 3 months following the conclusion of the project, the Social Safeguards officer will prepare monthly reports regarding the number and nature of grievances filed and make it available to project management.
---	------------	-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

#### 7.4 Expectation when Grievances arise

When local people present a grievance, they generally expect to receive one or more of the following: acknowledgement of their problem, an honest response to questions/issues brought forward, an apology, adequate resolution, modification of the conduct that caused the grievance and some other fair remedies. Levels of grievance are:

a. Reception & Registration of Grievance at the first level (Community GRC)

- b. Registration of Grievance at the Second level (LGA)
- c. Registration of Grievance at the Third level (State)

Upon exhaustion of efforts by the GRC, LGA and State levels, aggrieved persons would be advised to seek full legal redress in a court of competent jurisdiction. This option shall as much as possible be avoided, and only resorted to as a last option and worst-case scenario.

The overall process of grievance shall take the following way:

- During consultation process, prior to construction, stakeholders are given copies of grievance procedures as a guide on how to register their grievances;
- The process of grievance redress will start with registration of the grievances to be addressed for reference, and to enable progress updates of the cases.
- The response time will depend on the issue to be addressed but it should be addressed with efficiency. Nevertheless, Grievance form will be filled by person affected by the project with the Grievance Redress Committee, which will act on it within 10 working days on receipt. If no understanding or amicable solution is reached, or the affected person does not receive a response from the local Grievance Redress Committee within 15 working days, the affected person can appeal to a designated office in the PCU, which should act on the complaint/grievance within 15 working days of its filing.
- All reasonable moves shall be made to settle any arising grievance amicably. If affected person is not satisfied with the decision received, he/she can, as a last resort, appeal to a court of competent jurisdiction. Affected persons will be exempted from all administrative and legal fees incurred pursuant to grievance redress procedures.
- The appeals process will use a local mechanism, which includes peers and local leaders of the affected people. These will ensure equity across cases; they eliminate nuisance claims and satisfy legitimate claimants at low cost.

For MCRP, it is recognized that the formal legal mechanisms for grievance redress tend to be a lengthy and acrimonious procedures, thus an informal grievance redress mechanism through the PCU Safeguard Units will be established. This unit will work with a committee comprising administrative head of local governments; community/village chiefs, NGOs/CBOs and other relevant Government organs that will be set-up to address complaints.

The grievance redress mechanism is designed with the objective of solving disputes at the earliest possible time, which will be in the interest of all parties concerned and therefore implicitly discourages referring such matters to the law courts for resolution that will otherwise take a considerably longer time. For this reason, handling grievances will begin with the State Project Coordination Unit and involve Local Government. A grievance log will be established by the project and copies of the records kept with all the relevant authorities. A review of grievances will be conducted at least every three months during implementation in order to detect and correct systemic problems.

The PCU will establish an informal forum for the presentation and consideration of individual appeals after the administrative route has been exhausted. The informal forum will include local government, and other concerned responsible parties, as deemed appropriate. The existence, location, purpose and composition of this forum will be publicized, so that persons who may be affected by the project activities are knowledgeable about the availability of this forum for resolving any grievance. If a grievance cannot be resolved in these informal venues, the complainant may take recourse to the administrative and legal systems for satisfaction. Figure 15 shows GRM flow chart.

#### 7.5 Grievance Log

The Project Liaison officer will ensure that each complaint has an individual reference number, and is appropriately tracked and recorded actions are completed. The log also contains a record of the person responsible for an individual complaint, and records dates for the following events:

- Date the complaint was reported.
- Date the Grievance Log was uploaded onto the project database.
- Date the information on proposed corrective action sent to complaint.
- The date the complaint was closed out.
- Date response was sent to complainant.
- Monitoring Complaints

As the coordinating agency for resolving grievances, a complaint desk to collate petitions, complaints, etc. from aggrieved parties shall be opened at the Yobe-MCRP office manned by the Yobe-MCRP social safeguard officer. The social safeguards officer shall refer all the issues to the Yobe-MCRP social safeguards team who ensures appropriate channel of resolution of such grievances are reached with a view to resolving the issues.

# 7.6 Financing the Grievance Redress Mechanism and Cost of Remediation

Yobe State government through the PCU shall be responsible for the funding of logistics for the GRC as well as the eventual compensation or remediation that aggrieved party may be entitled to. The PCU will also be responsible for the cost of the judicial process for cases that result to court for adjudication.



Figure 13: Flow Chart for GRM

### CHAPTER EIGHT: STAKEHOLDER CONSULTATIONS

#### 8.1 Introduction

Stakeholder participation during project planning, design and implementation is widely recognized as an integral part of environmental and social management for projects. It is a two-way flow of information and dialogue between project proponents and stakeholders, which are specifically aimed at developing ideas that can help shape project design, resolve conflicts at an early stage, assist in implementing solutions and monitor ongoing activities.

#### 8.2 Objectives of Consultation

The main objective of the consultations with stakeholders is to discuss the proposed project's environmental and social implications and to identify alternatives for consideration. Specifically, the consultations seek to achieve the following objectives:

- To provide some information about the proposed project;
- To provide opportunities for stakeholders to discuss their concerns and offer recommendations;
- To gain insight on the role of each stakeholder in the implementation of the environmental and social safeguards as well as structures in place for the management of the proposed facilities;
- To provide and discuss with stakeholders the alternatives considered to reduce anticipated impacts;
- To identify and verify significance of environmental, social and health impacts; and
- To inform the process of developing appropriate mitigation and management options.

#### 8.3 Stakeholder Consultation Strategy and Plan

Stakeholder consultation is a process and would continue through the ESIA study stages to its implementation. Table 23 summarizes the proposed approach for stakeholder engagement.

Table 23: Stakeholders Engagement Strategy

No.	Activity	Identified Stakeholders	Focus of Consultation/	Timelines/	Forms of	Facilitator
1	Preparation of ESIA	FPMU State Project Coordinating Unit Federal Ministry of Environment State Ministry of Environment Community and Community Based Organizations FMF World Bank	Large scale forum Key stakeholders interviews Mapping of community interests and concerns Communities need to know what the project is all about.	Throughout the ESIA study period	Focus Group Discussion/workshops Phone calls One on one interview Distribution of pamphlets Public meetings Newspapers/magazines	Yobe MCRP
2	Site preparation prior to construction work on road	PCU Contractor Supervising Engineers Consultant FME	Information Disclosure at Federal Ministry of Environment, State Ministry of Environment and Local Government level.	Two weeks prior to construction	Through Radio and Newspapers	Yobe MCRP Federal Ministry of Environmen t
3	Start of construction of road	PCU Contractors Supervising Engineers Consultant Suppliers Businessmen NGOs/vulnerable groups Communities	Affected Communities Government Officials World Bank	Throughout the construction period	Phone calls Newspapers Radios Pamphlets One on One	Yobe MCRP FMF WORLD BANK
4	End of construction/r ehabilitation	PCU Government Officials Affected Communities	Government Officials Affected Communities	Decommissio ning phase	Phone calls Televisions Radios	Governmen t Officials Yobe MCRP

No.	Activity	Identified Stakeholders	Focus of Consultation/	Timelines/	Forms of	Facilitator
			Engagement	Frequency	communication	
	of road Decommission ing of construction equipment &	World Bank			Newspapers Emails Pamphlets	
5	Commissionin g and handing over of road infrastructure	Government Officials PCU Beneficiary Communities Wagir, Nyakire, Bukkiyel & Mutai	Government Officials Benefitting Communities	Prior to operation of the facility	Newspapers Television Radio	Yobe MCRP
6	Operation and maintenance of Gujba- Ngalda road	Beneficiary Communities Wagir, Nyakire, Bukkiyel & Mutai	Beneficiary Communities Wagir, Nyakire, Bukkiyel & Mutai	During operation and maintenance period	One on one Workshops/FGD Television Radio	Yobe MCRP
		Yobe MCRP	Beneficiary Communities Wagir, Nyakire, Bukkiyel & Mutai	3 times a week	Visits	Yobe MCRP
		Yobe MCRP Government Officials Other Communities	Beneficiary Communities Wagir, Nyakire, Bukkiyel & Mutai	Fortnightly	Visits	
			Beneficiary Communities Wagir, Nyakire, Bukkiyel & Mutai	3 times a week	Visits	
			Beneficiary communities Wagir, Nyakire, Bukkiyel & Mutai	3 times a week	Visits	
		NGOs/CBOs	Beneficiary Communities Wagir, Nyakire, Bukkiyel & Mutai	Once a term	Visits	
		World Bank	Beneficiary communities	Once a term	Visits	Yobe MCRP

No.	Activity	Identified Stakeholders	Focus	of	Consultation	/	Timelines/	Forms	of	Facilitator
			Engage	ement			Frequency	communication		
			Wagir,	Nyakir	e, Bukkiyel	&				
			Mutai							

#### 8.4 Stakeholders Consulted

Key stakeholders to the MCRP intervention sub-project were identified for consultations and these included stakeholders from the Yobe MCRP Project Implementation Unit of the Federal Ministry of Environment (FMEnv), Yobe State Ministry of Environment, Yobe State Ministry of Works & Infrastructure, Yobe State Waste Management Agency (YSWMA), village heads, local community leaders and women groups in communities. The vulnerable groups in the project areas were identified and these include:

- Children
- Old men and women
- Physically challenged individuals

#### 8.5 Outcome of Stakeholder Consultations carried out during ESIA Preparation

Site visits were carried out to undertake physical assessment of the 40km Gujba-Ngalda road from January 22<sup>nd</sup> – 26<sup>th</sup> 2020 and meetings were held with other stakeholders such as consultations with different sector ministries such as the Ministries of Works, Water Resources, Transportation and the Federal Ministry of Environment, Yobe State Ministry of Environment, Yobe State Environmental Protection Agency and other relevant stakeholders in the project area. Pictures of consultation meetings are shown in Figure 16.





Figure 14: Pictures from Stakeholder Consultations

Key stakeholders to the MCRP intervention sub-project were identified for consultations and these included stakeholders in the communities visited such as Wagir, Nyakire, Bukkiyel & Mutai communities. Furthermore, stakeholders from the Yobe MCRP Project Coordination Unit, Federal Ministry of Environment (FMEnv), Yobe State Ministry of Environment, MCRP sector ministries such as the representatives of the Yobe State Ministry of Works & Infrastructure, village heads, local community leaders, youths and women groups in communities, were also consulted. Issues raised and how they were resolved is contained in Table 24.

S/n	Issues raised during	How they were addressed		
	consultations			
Issues raised in social gatherings	Disruption of movement during construction phase since this is the only road linking communities in the area	Alternative route will be created for motorists and pedestrians during construction phase to ease movement of people, goods and services		
	Project to take cognizance of existing ponds and earth dams used for livestock farming in the area.	As the road is already in existence and will only be rehabilitated project activities will not affect any pond or earth dam.		
	MCRP to consider extending the project up to Ngalda instead of taking only 40kms	The project financial approval will allow for only 40kms at this time. However, this will be considered in subsequent years when funding may become available.		
	Expansion of existing culvert at the entrance Wagir	Component 2 manager responded that the design consultant has made the observation and recommendation for the expansion has been captured in the design		
Issues	At a dedicated session with	Contractors will be trained on GBV		
during	concerns about gender-	code of conduct against engaging in		
meetings	based violence (GBV).	sexual exploitation and abuse as well		
with	violence against women	as violence against women. Project has		
Women	and children and sexual	established GRM with GBV sensitive		

#### Table 24: Concerns raised and how they were addressed

	exploitation and abuse likely to be exacerbated by the project activities.	channels to offer referral pathways for survivors. The MCRP project safeguard team will closely monitor activities of contractors and their staff during implementation phase to ensure compliance. The team advice the community members, particularly parents to monitor their children (girl child) and continue to warn them to be careful with those who will lure them into such activities.
	Women have raised concern about job opportunities to be created by the project during construction phase, especially for their children who are staying idle without job.	Labour influx management plan will be developed as part of the ESIA for contractor's compliance to ensure community members are considered in the recruitment of staff on the project.
Issues raised during meetings with Youths	The youths have expressed concern about employment opportunities during the project implementation.	Contractors will be trained on how to manage labour influx. Part of the strategy for managing labour influx is to look inward for various skills within the communities, unless such are not available before resorting to external source. Therefore, the project will provide job opportunities to the youth, especially those who are prepared to work on road construction projects.
Issues raised during meetings with elderly persons	Community elders advocated for construction of additional road from Gujba to Goniri to connect more communities in the area,	The team responded that even though Gujba – Gonir has been prioritized by the State and it is entirely a new project while MCRP is focusing on rehabilitation of existing infrastructure
	to Ngalda (95kms) to cover more communities in the area	available. The community members were advised to advocate with the State government, north east development commission for the execution of the project
	Contractors to exercise caution during construction to ensure safety of animals, children, women, aged and other vulnerable people who will be routinely moving around to pursue their daily needs	Iraffic management plan will be developed as part of the ESIA. Dangerous and hazardous areas will be cordoned during construction phase to safeguard human beings and animal

#### CHAPTER NINE: RECOMMENDATIONS AND CONCLUSION

#### 9.0 Conclusion & Recommendations

This chapter presents recommendations to be undertaken by the PCU to enhance the achievement of these environmental and social safeguards, while also providing a conclusion to this ESIA report.

#### 9.1 Recommendations

This rehabilitation of 40km Gujba-Ngalda road intervention sub-project with the associated activities outlined in this ESIA will have highly beneficial impacts by improving critical service delivery infrastructure within the communities, through which the livelihood opportunities can be enhanced and social cohesion, strengthened.

Although, the rehabilitation, construction & civil works that will be implemented will lead to some limited adverse environmental and social impacts which will largely be localized in spatial extent, short term and occurring within less sensitive environmental areas. These will be managed through the application of the appropriate mitigation measures stated in the ESIA matrix table, which would be included in the contractor's agreement, good practices, adequate supervision and enforcement during project implementation. Consequently, there is therefore no major environmental or social issue to impede the implementation of the proposed project. Nevertheless, some additional recommendations that will enhance the overall sustainability of the project are:

- priority should be given to local workers to stimulate local socioeconomic activities, improve livelihood and poverty reduction in the affected communities.
- ensure opinion of persons in affected communities is given priority in appropriation of mitigation measures.
- all bare and exposed soils should be re-vegetated with native vegetation immediately to prevent erosion,
- maintenance works should be carried out in an environmentally sustainable and socially responsible and inclusive manner;
- the Safeguard Unit of PCU should ensure active monitoring to ensure the contractor adhere strictly to the requirements of this ESIA especially in the application of mitigation measures
- the PCU should ensure that the relevant sections of the ESIA should be made available to contractors.

#### 9.2 Conclusion

The ESIA has provided in detail the mitigation measures for identified potential adverse impact s and risks associated with the various phases of

the project, and a monitoring program to ensure compliance. In concluding, with adequate application of mitigation measures the impacts will be avoided, reduced or mitigated, and in very few cases they may be offset

#### References

- MCRP Project Appraisal Document (PAD).
- MCRP Project Implementation Manual
- World Bank policies, World Bank website: www.worldbank.org
- FEPA (1991): *National Environmental Protection (effluent Limitation) Regulations*. Federal Environmental Protection Agency, Nigeria.
- Igbokwe, et al. (2008): Mapping and Monitoring the Impact of Gully Erosion in South-Eastern Nigeria with Satellite Remote Sensing and Spatial Information Science. In: *Intl. Archives of Photog. Remote Sensing and Spatial Information Sciences.* vol. 37, Part B, pp. 865-71, Beijing. China.
- Nwokocha CO (2017) The Challenges Facing the Effective Implementation of Drought and Desertification Policy in North-East Geopolitical Zone of Nigeria. Arts Social Sci J 8: 289. doi:10.4172/2151-6200.1000289
- Olaniyan, C. I. O. (1975): *An introduction to West Africa Animal Ecology*. 2nd ed. Heinemann Educational Books Ltd. London and Ibadan.
- Rural Access and Mobility Project 2, (2012), Environmental and Social Management Framework
- Rural Access and Mobility Project 2, (2012), Revised Environmental and Social Impact Assessment (ESIA) report
- Rural Access and Mobility Project 2, (2012), Resettlement Policy Framework (RPF)

## Annex 1: Questionnaire MULTI-SECTORAL CRISIS RECOVERY PROJECT (MCRP)

Questionnaire for the Preparation of Safeguard Instruments (ESIA & ESMP) for Yobe - MCRP

This questionnaire which is expected to take about 20 minutes to complete is aimed at eliciting your view/opinion on the social and environmental implications of the Yobe MCRP project activities in your community. Your input would assist in the preparation of an Environmental and Social Management Plan (ESMP) that would enable the PCU to manage the various project activities in a manner that guarantees socio-environmental sustainability of the project.

My name is
DATE: Community: LGA: Please simply tick (x) or write in brief detail where appropriate SECTION A: BIO-DATA Name:
PhoneNumber: Address(optional):
Age (years): < 8-30 350 50-70 above 70
Sex: Mal emale What is your religion: Christian Muslim Pagan traditionalist Others
Marital Status:le Married Separated/Divorcee
No. of children: Non 1-3 46 Above 8 Level of education: () No formal educ. () Govt. Secondary () Secondary () Tertiary () others (specify)
What do you do for a living (your Govt. secondary occupation/nature of business)?

( ) Self-employed ( ) fisherman ( ) hunter ( ) public sector ( ) Others (specify).....

11. How long have you been resident in this community? () Since birth () above 15 years () 10 - 15 years () 5 - 10 years () below 5 years 12. What are the transportation means to this community? () Car/bus () motorcycle () bicycle () lorry () others 13. Please give your weekly() or monthly () earnings Below N500 ( ) N500 - N1000 ( ) N1000 - N5000 ( ) N5000 -N7000 ( ) N7000 - N10,000 above 10,000 ( ) SECTION B 11. What is your general opinion of this project? ..... 12. How do you think the project will affect the community? How will it affect the individual families? ..... Pls explain the benefits or negative impacts of this project in the community? ..... How do you seek redress when there is a grievance among people in this community? Do you have any concerns about labour influx into the community when the project commences? ..... How far or how close is the nearest market? ..... Please describe the leadership structure in this community ...... Please describe the health care facilities in this village. Where is the nearest hospital located? 19. Have you had any instances of gender based violence in your community? If yes, please explain.....

# Annex 2: Occupational Health & Safety (OHS) Plan

No	Project	Potential	Proposed Mitigation	Resp	Cost (NGN)
	Activity	Impact	Measures/	onsi	
			Actions	bility	
				for	
				mitig	
				ation	
I. Pr	e-Construction Pl	nase			
1.	Site clearing	Occupatio	Develop and implement a	Contr	80,000
	for staging	nal	project specific	actor	
	area	accidents	Occupational Health and		
		and	Safety Plan (OHSP). OHSP		
		injuries to	to include but not limited		
	Mobilization of	workers	to:		
	Machinery,	and risk	Prohibition of drug and		
	Plant &	to	alconol use by workers		
	Equipment		While on the job.		
		y nealth	provision of adequate first		
		anu	diu, IIISt diuers, PPL,		
		Salety	Hausa Janguagos)		
			Restriction of unauthorized		
			access to all areas of high		
			risk activities		
			Provision of specific		
			personnel training on		
			worksite OHS		
			management		
			Ensure that staging areas		
			for contractor equipment		
			are adequately delineated		
			and cordoned off with		
			reflective tapes and		
			barriers		
			Any uncovered work pits		
			should have appropriate		
			signage and protection		
			around them		
			workers should get a daily		
			induction/toolbox before		
			going 40n the site and a		
			rerresner or what		

	operturbing		happened on site a day before Adequate safety signage on construction sites should be installed to alert community/drivers/pedestr ians lighting and/or reflective tapes and signage integrated in all worksites for safety at night appropriate security measures in place to prevent harassment or kidnapping of workers		
<u> </u>		<b>D</b> 1 11	<b>T</b> · · · · · · · · · · · · · · · · · · ·		N1
2.	Use of haulage trucks for sand & materials supply	Public safety, road accidents leading to injuries and fatalities	Train drivers on defensive driving Conveyance of materials to site shall be by appropriate transportation means to prevent damage or accidents Provide road signs and flag persons to warn of dangerous conditions of conveying materials such as the water trucks	Contr actor PCU Safeg uards Team	No additional cost
3.	Use of plant, Machinery & Equipment Movement of materials Construction work such as:	Occupatio nal accidents and injuries to workers and risk to communit y health and safety	Develop and implement a project specific Occupational Health and Safety Plan (OHSP). OHSP to include but not limited to: Prohibition of drug and alcohol use by workers while on the job. Provision of adequate first aid, first aiders, PPE, signage (English and Ibo languages). Use only trained personnel for welding & metal bending activities Restriction of unauthorized access to all areas of high risk activities Provision of specific personnel training on worksite OHS management Ensure that staging areas for contractor equipment	Contr actor	200,000

-						
			are adequately delineated			
			and cordoned off with			
			reflective tapes and			
			barriers			
			Any uncovered work nits			
			should have appropriate			
			should have appropriate			
			signage and protection			
			around them			
			Workers should get a daily			
			induction/toolbox before			
			going on the site and a			
			refresher of what			
			happened on site a day			
			before			
			Adequate safety signage			
			on construction sites			
			should be installed to alert			
			should be installed to dielt			
			community/arivers/pedestr			
			lans			
			lighting and/or reflective			
			tapes and signage			
			integrated in all worksites			
			for safety at night			
			appropriate security			
			measures in place to			
			provent baracsment or			
			kidpapping of workers			
			Ensure demonstion areas			
			and areas for roof			
			removals are properly			
			cordoned off to prevent			
			accidents and incidents			
III. Demobilization						
4.	Demobilization	Risks of	Develop & implement a	Contr	Part of	
	of office and	occupatio	project specific	actor	Maintenance	
	camp	nal	Occupational Health and		cost	
	facilities plant	accidents	Safety Plan (OHSP) to		0000	
	& oquinmont	accidents	include but not limited to:			
	a equipment		Drahihitian of drug and			
		injuries to	Prohibition of drug and			
		workers.	alconol use by workers			
			while on the job.			
			Provision of adequate first			
			aid, first aiders, PPE,			
			signage (English and			
			Hausa languages).			
			Restriction of unauthorized			
			access to all areas of high-			
			risk activities			
			Drovicion of chaster			
			Provision of specific		200.000	
			personnei training on		200,000	
			worksite OHS			
			management			
1			Ensure that stading areas			

	for contractor equipment	
	and cordoned off with	
	reflective tapes and	
	barriers	
	Workers should get a daily	
	induction/toolbox before	
	going on the site and a	
	refresher of what	
	happened on site a day	
	Defore	
	Adequate safety signage	
	should be installed to alert	
	community/drivers/pedestr	
	ians	
	lighting and/or reflective	
	tapes and signage	
	integrated in all worksites	
	for safety at night	
	appropriate security	
	nrevent harassment or	
	kidnapping of workers	
Sub-Total Mitigation (OHS)	1,080,000.00	

# Annex 3: Sample Company Code of Conduct Company's Code of Conduct

Preventing Gender Based Violence and Violence Against Children

The company is committed to creating and maintaining an environment in which gender based violence (GBV) and violence against children (VAC) have no place, and where they will not be tolerated by any employee, associate, or representative of the company. Therefore, in order to ensure that all those engaged in the project are aware of this commitment, and in order to prevent, be aware of, and respond to any allegations of GBV and VAC, the company commits to the following core principles and minimum standards of behavior that will apply to all company employees, associates, and representatives including sub-contractors, without exception:

The company—and therefore all employees, associates, and representatives commit to treating women, children (persons under the age of 18), and men with respect regardless of race, color, language, religion, political or other opinion, national, ethnic or social origin, property, disability, birth or other status. Acts of GBV and VAC are in violation of this commitment.

Demeaning, threatening, harassing, abusive, culturally inappropriate, or sexually provocative language and behavior are prohibited among all company employees, associates, and its representatives.

Acts of GBV or VAC constitute gross misconduct and are therefore grounds for sanctions, which may include penalties and/or termination of employment. All forms of GBV and VAC, including grooming are unacceptable, regardless of whether they take place on the work site, the work site surroundings, at worker's camps or at worker's homes.

In addition to company sanctions, legal prosecution of those who commit acts of GBV or VAC will be pursued if appropriate.

Sexual contact or activity with children under 18—including through digital media—is prohibited. Mistaken belief regarding the age of a child is not a defense. Consent from the child is also not a defense or excuse.

Sexual favors—for instance, making promises or favorable treatment dependent on sexual acts—or other forms of humiliating, degrading or exploitative behavior are prohibited.

Unless there is full consent12 by all parties involved in the sexual act, sexual interactions between the company's employees (at any level) and members of the communities surrounding the work place are prohibited. This includes relationships involving the withholding/promise of actual provision of benefit

<sup>12</sup> Consent is defined as the informed choice underlying an individual's free and voluntary intention, acceptance or agreement to do something. No consent can be found when such acceptance or agreement is obtained through the use of threats, force or other forms of coercion, abduction, fraud, deception, or misrepresentation. In accordance with the United Nations Convention on the Rights of the Child, the World Bank considers that consent cannot be given by children under the age of 18, even in the event that national legislation of the country into which the Code of Conduct is introduced has a lower age. Mistaken belief regarding the age of the child and consent from the child is not a defense.

(monetary or non-monetary) to community members in exchange for sex—such sexual activity is considered "non-consensual" within the scope of this Code.

All employees, including volunteers and sub-contractors are highly encouraged to report suspected or actual acts of GBV and/or VAC by a fellow worker, whether in the same company or not. Reports must be made in accordance with GBV and VAC Allegation Procedures.

Managers are required to report suspected or actual acts of GBV and/or VAC as they have a responsibility to uphold company commitments and hold their direct reports responsible.

To ensure that the above principles are implemented effectively the company commits to ensuring that:

All managers sign the 'Manager's Code of Conduct' detailing their responsibilities for implementing the company's commitments and enforcing the responsibilities in the 'Individual Code of Conduct'.

All employees sign the project's 'Individual Code of Conduct' confirming their agreement not to engage in activities resulting in GBV or VAC.

Displaying the Company and Individual Codes of Conduct prominently and in clear view at workers' camps, offices, and in in public areas of the work space. Examples of areas include waiting, rest and lobby areas of sites, canteen areas, health clinics.

Ensure that posted and distributed copies of the Company and Individual Codes of Conduct are translated into the appropriate language of use in the work site areas as well as for any international staff in their native language.

An appropriate person is nominated as the company's 'Focal Point' for addressing GBV and VAC issues, including representing the company on the GBV and VAC Compliance Team (GCCT) which is comprised of representatives from the client, contractor(s), the supervision consultant, and local service provider(s).

Ensuring that an effective Action Plan is developed in consultation with the GCCT which includes as a minimum:

GBV and VAC Allegation Procedure to report GBV and VAC issues through the project Grievance Redress Mechanism (GRM);

Accountability Measures to protect confidentiality of all involved; and,

Response Protocol applicable to GBV and VAC survivors and perpetrators.

That the company effectively implements the Action Plan, providing feedback to the GCCT for improvements and updates as appropriate.

All employees attend an induction training course prior to commencing work on site to ensure they are familiar with the company's commitments and the project's GBV and VAC Codes of Conduct.

All employees attend a mandatory training course once a month for the duration of the contract starting from the first induction training prior to commencement of work to reinforce the understanding of the project's GBV and VAC Code of Conduct.
I do hereby acknowledge that I have read the foregoing Company Code of Conduct, and on behalf of the company agree to comply with the standards contained therein. I understand my role and responsibilities to prevent and respond to GBV and VAC. I understand that any action inconsistent with this Company Code of Conduct or failure to take action mandated by this Company Code of Conduct may result in disciplinary action.

Signature:		 	
Printed Nam	ne:		 
Title:		 	

Date:

### Manager's Code of Conduct

Preventing Gender Based Violence and Violence Against Children

Managers at all levels have particular responsibilities to uphold the company's commitment to preventing and addressing GBV and VAC. This means that managers have an acute responsibility to create and maintain an environment that prevents GBV and VAC. Managers need to support and promote the implementation of the Company Code of Conduct. To that end, managers must adhere this Manager's Code of Conduct and also sign the Individual Code of Conduct. This commits them to supporting and developing systems that facilitate the implementation of the Action Plan and maintain a GBV-free and VAC-free environment at the workplace and in the local community. These responsibilities include but are not limited to:

Implementation

To ensure maximum effectiveness of the Company and Individual Codes of Conduct:

Prominently displaying the Company and Individual Codes of Conduct in clear view at workers' camps, offices, and in in public areas of the work space. Examples of areas include waiting, rest and lobby areas of sites, canteen areas, health clinics.

Ensuring all posted and distributed copies of the Company and Individual Codes of Conduct are translated into the appropriate language of use in the work site areas as well as for any international staff in their native language.

Verbally and in writing explain the Company and Individual Codes of Conduct to all staff.

Ensure that:

All direct reports sign the 'Individual Code of Conduct', including acknowledgment that they have read and agree with the Code of Conduct.

Staff lists and signed copies of the Individual Code of Conduct are provided to the GCCT and the client.

Participate in training and ensure that staff also participate as outlined below.

Staff are familiar with the Grievance Redress Mechanism (GRM) and that they can use it to anonymously report concerns of GBV or VAC incidents.

Staff are encouraged to report suspected or actual GBV or VAC through the GRM by raising awareness about GBV and VAC issues, emphasizing the staff's responsibility to the Company and the country hosting their employment, and emphasizing the respect for confidentiality.

In compliance with applicable laws and to the best of your abilities, prevent perpetrators of sexual exploitation and abuse from being hired, re-hired or deployed. Use background and criminal reference checks for all employees.

Ensure that when engaging in partnership, sub-contractor or similar agreements, these agreements:

Incorporate the GBV and VAC Codes of Conduct as an attachment.

Include the appropriate language requiring such contracting entities and individuals, and their employees and volunteers, to comply with the Individual Codes of Conduct.

expressly state that the failure of those entities or individuals, as appropriate, to take preventive measures against GBV and VAC, to investigate allegations thereof, or to take corrective actions when GBV or VAC has occurred, shall constitute grounds for sanctions and penalties in accordance with the Individual Codes of Conduct.

Provide support and resources to the GCCT to create and disseminate internal sensitization initiatives through the awareness-raising strategy under the Action Plan.

Ensure that any GBV or VAC issue warranting police action is reported to the client and the World Bank immediately.

Training

All managers are required to attend an induction manager training course prior to commencing work on site to ensure that they are familiar with their roles and responsibilities in upholding the GBV and VAC Codes of Conduct. This training will be separate from the induction training course required of all employees and will provide managers with the necessary understanding and technical support needed to begin to develop the Action Plan for addressing GBV and VAC issues.

Ensure that time is provided during work hours and that staff attend the mandatory project facilitated induction training on GBV and VAC required of all employees prior to commencing work on site.

Ensure that staff attend the monthly mandatory refresher training course required of all employees to combat increased risk of GBV and VAC during civil works.

Managers are required to attend and assist with the project facilitated monthly training courses for all employees. Managers will be required to introduce the trainings and announce the self-evaluations.

Collect satisfaction surveys to evaluate training experiences and provide advice on improving the effectiveness of training.

Response

Managers will be required to provide input to the GBV and VAC Allegation Procedures and Response Protocol developed by the GCCT as part of the final cleared Action Plan.

Once adopted by the Company, managers will uphold the Accountability Measures set forth in the Action Plan to maintain the confidentiality of all employees who report or (allegedly) perpetrate incidences of GBV and VAC (unless a breach of confidentiality is required to protect persons or property from serious harm or where required by law).

If a manager develops concerns or suspicions regarding any form of GBV or VAC by one of his/her direct reports, or by an employee working for another contractor on the same work site, s/he is required to report the case using the GRM.

Once a sanction has been determined, the relevant manager(s) is/are expected to be personally responsible for ensuring that the measure is effectively enforced, within a maximum timeframe of 14 days from the date on which the decision to sanction was made.

Managers failing to report or comply with such provision can in turn be subject to disciplinary measures, to be determined and enacted by the company's CEO, Managing Director or equivalent highest-ranking manager. Those measures may include:

Informal warning.

Formal warning.

Additional Training.

Loss of up to one week's salary.

Suspension of employment (without payment of salary), for a minimum period of 1 month up to a maximum of 6 months.

Termination of employment.

Ultimately, failure to effectively respond to GBV and VAC cases on the work site by the company's managers or CEO may provide grounds for legal actions by authorities.

I do hereby acknowledge that I have read the foregoing Manager's Code of Conduct, do agree to comply with the standards contained therein and understand my roles and responsibilities to prevent and respond to GBV and VAC. I understand that any action inconsistent with this Manager's Code of Conduct or failure to take action mandated by this Manager's Code of Conduct may result in disciplinary action.

Signature:	
Printed Name:	 
Title:	
Date:	 

### Individual Code of Conduct

Preventing Gender Based Violence and Violence Against Children

I, \_\_\_\_\_\_, acknowledge that preventing gender based violence (GBV) and violence against children (VAC) is important. The company considers that GBV or VAC activities constitute acts of gross misconduct and are therefore grounds for sanctions, penalties or potential termination of employment. All forms of GBV or VAC are unacceptable be it on the work site, the work site surroundings, or at worker's camps. Prosecution of those who commit GBV or VAC may be pursued if appropriate.

I agree that while working on the project I will:

Consent to police background check.

Treat women, children (persons under the age of 18), and men with respect regardless of race, color, language, religion, political or other opinion, national, ethnic or social origin, property, disability, birth or other status.

Not use language or behavior towards women, children or men that is inappropriate, harassing, abusive, sexually provocative, demeaning or culturally inappropriate.

Not participate in sexual contact or activity with children—including grooming, or contact through digital media. Mistaken belief regarding the age of a child is not a defense. Consent from the child is also not a defense or excuse.

Not engage in sexual favors—for instance, making promises or favorable treatment dependent on sexual acts—or other forms of humiliating, degrading or exploitative behavior.

Unless there is the full consent13 by all parties involved, I will not have sexual interactions with members of the surrounding communities. This includes relationships involving the withholding or promise of actual provision of benefit (monetary or non-monetary) to community members in exchange for sex—such sexual activity is considered "non-consensual" within the scope of this Code.

Attend and actively partake in training courses related to HIV/AIDS, GBV and VAC as requested by my employer.

Consider reporting through the GRM or to my manager any suspected or actual GBV or VAC by a fellow worker, whether employed by my company or not, or any breaches of this Code of Conduct.

With regard to children under the age of 18:

Wherever possible, ensure that another adult is present when working in the proximity of children.

Not invite unaccompanied children unrelated to my family into my home, unless they are at immediate risk of injury or in physical danger.

Not sleep close to unsupervised children unless absolutely necessary, in which case I must obtain my supervisor's permission, and ensure that another adult is present if possible.

Use any computers, mobile phones, or video and digital cameras appropriately, and never to exploit or harass children or to access child pornography through any medium (see also "Use of children's images for work related purposes" below).

Refrain from physical punishment or discipline of children.

Refrain from hiring children for domestic or other labor which is inappropriate given their age or developmental stage, which interferes with their time available for education and recreational activities, or which places them at significant risk of injury.

<sup>13</sup> Consent is defined as the informed choice underlying an individual's free and voluntary intention, acceptance or agreement to do something. No consent can be found when such acceptance or agreement is obtained through the use of threats, force or other forms of coercion, abduction, fraud, deception, or misrepresentation. In accordance with the United Nations Convention on the Rights of the Child, the World Bank considers that consent cannot be given by children under the age of 18, even in the event that national legislation of the country into which the Code of Conduct is introduced has a lower age. Mistaken belief regarding the age of the child and consent from the child is not a defense.

Comply with all relevant local legislation, including labor laws in relation to child labor.

Use of children's images for work related purposes

When photographing or filming a child for work related purposes, I must:

Before photographing or filming a child, assess and endeavor to comply with local traditions or restrictions for reproducing personal images.

Before photographing or filming a child, obtain informed consent from the child and a parent or guardian of the child. As part of this I must explain how the photograph or film will be used.

Ensure photographs, films, videos and DVDs present children in a dignified and respectful manner and not in a vulnerable or submissive manner. Children should be adequately clothed and not in poses that could be seen as sexually suggestive.

Ensure images are honest representations of the context and the facts.

Ensure file labels do not reveal identifying information about a child when sending images electronically.

### Sanctions

I understand that if I breach this Individual Code of Conduct, my employer will take disciplinary action which could include:

Informal warning. Formal warning. Additional Training. Loss of up to one week's salary. Suspension of employment (without payment of salary), for a minimum period of 1 month up to a maximum of 6 months. Termination of employment. Report to the police if warranted.

I understand that it is my responsibility to avoid actions or behaviors that could be construed as GBV or VAC or breach this Individual Code of Conduct. I do hereby acknowledge that I have read the foregoing Individual Code of Conduct, do agree to comply with the standards contained therein and understand my roles and responsibilities to prevent and respond to GBV and VAC. I understand that any action inconsistent with this Individual Code of Conduct or failure to take action mandated by this Individual Code of Conduct may result in disciplinary action and may affect my ongoing employment.

Signature: \_\_\_\_\_

Printed Nam	ne:	 	 
Title:		 	 _

Date:

### Annex 4: General Environmental Management Conditions for Maintenance/Maintenance Contracts

General

1. In addition to these general conditions, the Contractor shall comply with any specific Environmental Management Plan (EMP) for the works he is responsible for. The Contractor shall inform himself about such an EMP, and prepare his work strategy and plan to fully take into account relevant provisions of that EMP. If the Contractor fails to implement the approved EMP after written instruction by the Supervising Engineer (SE) to fulfil his obligation within the requested time, the Owner reserves the right to arrange through the SE for execution of the missing action by a third party on account of the Contractor.

2. Notwithstanding the Contractor's obligation under the above clause, the Contractor shall implement all measures necessary to avoid undesirable adverse environmental and social impacts wherever possible, restore work sites to acceptable standards, and abide by any environmental performance requirements specified in an EMP. In general these measures shall include but not be limited to:

(a) Minimize the effect of dust on the surrounding environment resulting from earth mixing sites, asphalt mixing sites, dispersing coal ashes, vibrating equipment, temporary access roads, etc. to ensure safety, health and the protection of workers and communities living in the vicinity dust producing activities.

(b) Ensure that noise levels emanating from machinery, vehicles and noisy maintenance activities (e.g. excavation, blasting) are kept at a minimum for the safety, health and protection of workers within the vicinity of high noise levels and nearby communities.

(c) Ensure that existing water flow regimes in rivers, streams and other natural or irrigation channels is maintained and/or re-established where they are disrupted due to works being carried out.

(d) Prevent bitumen, oils, lubricants and waste water used or produced during the execution of works from entering into rivers, streams, irrigation channels and other natural water bodies/reservoirs, and also ensure that stagnant water in uncovered borrow pits is treated in the best way to avoid creating possible breeding grounds for mosquitoes.

(e) Prevent and minimize the impacts of quarrying, earth borrowing, piling and building of temporary maintenance camps and access roads on the biophysical environment including protected areas and arable lands; local communities and their settlements. In as much as possible restore/rehabilitate all sites to acceptable standards.

(f) Upon discovery of ancient heritage, relics or anything that might or believed to be of archaeological or historical importance during the execution of works, immediately report such findings to the SE so that the appropriate authorities may be expeditiously contacted for fulfilment of the measures aimed at protecting such historical or archaeological resources.

(g) Discourage maintenance workers from engaging in the exploitation of natural resources such as hunting, fishing, collection of forest products or any other activity that might have a negative impact on the social and economic welfare of the local communities.

(h) Implement soil erosion control measures in order to avoid surface run off and prevents siltation, etc.

(i) Ensure that garbage, sanitation and drinking water facilities are provided in maintenance workers camps.

(j) Ensure that, in as much as possible, local materials are used to avoid importation of foreign material and long distance transportation.

(k) Ensure public safety, and meet traffic safety requirements for the operation of work to avoid accidents.

3. The Contractor shall indicate the period within which he/she shall maintain status on site after completion of civil works to ensure that significant adverse impacts arising from such works have been appropriately addressed.

4. The Contractor shall adhere to the proposed activity implementation schedule and the monitoring plan / strategy to ensure effective feedback of monitoring information to project management so that impact management can be implemented properly, and if necessary, adapt to changing and unforeseen conditions.

5. Besides the regular inspection of the sites by the SE for adherence to the contract conditions and specifications, the Owner may appoint an Inspector to oversee the compliance with these environmental conditions and any proposed mitigation measures. State environmental authorities may carry out similar inspection duties. In all cases, as directed by the SE, the Contractor shall comply with directives from such inspectors to implement measures required to ensure the adequacy rehabilitation measures carried out on the bio-physical environment and compensation for socio-economic disruption resulting from implementation of any works.

Worksite/Campsite Waste Management

6. All vessels (drums, containers, bags, etc.) containing oil/fuel/surfacing materials and other hazardous chemicals shall be bonded in order to contain spillage. All waste containers, litter and any other waste generated during the Maintenance shall be collected and disposed at designated disposal sites in line with applicable government waste management regulations.

7. All drainage and effluent from storage areas, workshops and camp sites shall be captured and treated before being discharged into the drainage system in line with applicable government water pollution control regulations.

8. Used oil from maintenance shall be collected and disposed of appropriately at designated sites or be re-used or sold for re-use locally.

9. Entry of runoff to the site shall be restricted by constructing diversion channels or holding structures such as banks, drains, dams, etc. to reduce the potential of soil erosion and water pollution.

10. Maintenance/maintenance waste shall not be left in stockpiles along the road, but removed and reused or disposed of on a daily basis.

11. If disposal sites for clean spoil are necessary, they shall be located in areas, approved by the SE, of low land use value and where they will not result in material being easily washed into drainage channels. Whenever possible, spoil materials should be placed in low-lying areas and should be compacted and planted with species indigenous to the locality.

Material Excavation and Deposit

12. The Contractor shall obtain appropriate licenses/permits from relevant authorities to operate quarries or borrow areas.

13. The location of quarries and borrow areas shall be subject to approval by relevant local and national authorities, including traditional authorities if the land on which the quarry or borrow areas fall in traditional land.

14. New extraction sites:

a) Shall not be located in the vicinity of settlement areas, cultural sites, wetlands or any other valued ecosystem component, or on on high or steep ground or in areas of high scenic value, and shall not be located less than 1km from such areas.

b) Shall not be located adjacent to stream channels wherever possible to avoid siltation of river channels. Where they are located near water sources, borrow pits and perimeter drains shall surround quarry sites.

c) Shall not be located in archaeological areas. Excavations in the vicinity of such areas shall proceed with great care and shall be done in the presence of government authorities having a mandate for their protection.

d) Shall not be located in forest reserves. However, where there are no other alternatives, permission shall be obtained from the appropriate authorities and an environmental impact study shall be conducted.

e) Shall be easily rehabilitated. Areas with minimal vegetation cover such as flat and bare ground, or areas covered with grass only or covered with shrubs less than 1.5m in height, are preferred.

f) Shall have clearly demarcated and marked boundaries to minimize vegetation clearing.

15. Vegetation clearing shall be restricted to the area required for safe operation of Maintenance work. Vegetation clearing shall not be done more than two months in advance of operations.

16. Stockpile areas shall be located in areas where trees can act as buffers to prevent dust pollution. Perimeter drains shall be built around stockpile areas. Sediment and other pollutant traps shall be located at drainage exits from workings.

17. The Contractor shall deposit any excess material in accordance with the principles of the general conditions, and any applicable EMP, in areas approved by local authorities and/or the SE.

18. Areas for depositing hazardous materials such as contaminated liquid and solid materials shall be approved by the SE and appropriate local and/or national authorities before the commencement of work. Use of existing, approved sites shall be preferred over the establishment of new sites.

Rehabilitation and Soil Erosion Prevention

19. To the extent practicable, the Contractor shall rehabilitate the site progressively so that the rate of rehabilitation is similar to the rate of maintenance.

20. Always remove and retain topsoil for subsequent rehabilitation. Soils shall not be stripped when they are wet as this can lead to soil compaction and loss of structure.

21. Topsoil shall not be stored in large heaps. Low mounds of no more than 1 to 2m high are recommended.

22. Re-vegetate stockpiles to protect the soil from erosion, discourage weeds and maintain an active population of beneficial soil microbes.

23. Locate stockpiles where they will not be disturbed by future maintenance/Maintenance activities.

24. To the extent practicable, reinstate natural drainage patterns where they have been altered or impaired.

25. Remove toxic materials and dispose of them in designated sites. Backfill excavated areas with soils or overburden that is free of foreign material that could pollute groundwater and soil.

26. Identify potentially toxic overburden and screen with suitable material to prevent mobilization of toxins.

27. Ensure reshaped land is formed so as to be inherently stable, adequately drained and suitable for the desired long-term land use, and allow natural regeneration of vegetation.

28. Minimize the long-term visual impact by creating landforms that are compatible with the adjacent landscape.

29. Minimize erosion by wind and water both during and after the process of reinstatement.

30. Compacted surfaces shall be deep ripped to relieve compaction unless subsurface conditions dictate otherwise.

31. Re-vegetate with plant species that will control erosion, provide vegetative diversity and, through succession, contribute to a resilient ecosystem. The choice of plant species for rehabilitation shall be done in consultation with local research institutions, forest department and the local people.

Water Resources Management

32. The Contractor shall at all costs avoid conflicting with water demands of local communities.

33. Abstraction of both surface and underground water shall only be done with the consultation of the local community and after obtaining a permit from the relevant Water Authority.34. Abstraction of water from wetlands shall be avoided. Where necessary, authority has to be obtained from relevant authorities.

35. Temporary damming of streams and rivers shall be done in such a way avoids disrupting water supplies to communities downstream, and maintains the ecological balance of the river system.

36. No maintenance/Maintenance water containing spoils or site effluent, especially cement and oil, shall be allowed to flow into natural water drainage courses.

37. Wash water from washing out of equipment shall not be discharged into water courses or road drains.

38. Site spoils and temporary stockpiles shall be located away from the drainage system, and surface run off shall be directed away from stockpiles to prevent erosion.

Traffic Management

39. Location of access roads/detours shall be done in consultation with the local community especially in important or sensitive environments. Access roads shall not traverse wetland areas.

40. Upon the completion of civil works, all access roads shall be ripped and rehabilitated.

41. Access roads shall be sprinkled with water at least five times a day in settled areas, and three times in unsettled areas, to suppress dust emissions. Blasting

42. Blasting activities shall not take place less than 2km from settlement areas, cultural sites, or wetlands without the permission of the SE.

43. Blasting activities shall be done during working hours, and local communities shall be consulted on the proposed blasting times.

44. Noise levels reaching the communities from blasting activities shall not exceed 90 decibels.

Disposal of Unusable Elements

45. Unusable materials and Maintenance elements such as electro-mechanical equipment, pipes, accessories and demolished structures will be disposed of in a manner approved by the SE. The Contractor has to agree with the SE, which elements are to be surrendered to the Client's premises, which will be recycled or reused, and which will be disposed of at approved landfill sites.

46. As far as possible, abandoned pipelines shall remain in place. Where for any reason no alternative alignment for the new pipeline is possible, the old pipes shall be safely removed and stored at a safe place to be agreed upon with the SE and the local authorities concerned. 47. AC-pipes as well as broken parts thereof have to be treated as hazardous material and disposed of as specified above.

48. Unsuitable and demolished elements shall be dismantled to a size fitting on ordinary trucks for transport.

Health and Safety

49. In advance of the maintenance/Maintenance work, the Contractor shall mount an awareness and hygiene campaign. Workers and local residents shall be sensitized on health risks particularly of Cholera, tetanus and Hepatitis.

50. Adequate road signs to warn pedestrians and motorists of maintenance/Maintenance activities, diversions, etc. shall be provided at appropriate points.

51. Maintenance/Maintenance vehicles shall not exceed maximum speed limit of 40km per hour.

### Repair of Private Property

52. Should the Contractor, deliberately or accidentally, damage private property, he shall repair the property to the owner's satisfaction and at his own cost. For each repair, the Contractor shall obtain from the owner a certificate that the damage has been made good satisfactorily in order to indemnify the Client from subsequent claims.

53. In cases where compensation for inconveniences, damage of crops etc. are claimed by the owner, the Client has to be informed by the Contractor through the SE. This compensation is in general settled under the responsibility of the Client before signing the Contract. In unforeseeable cases, the respective administrative entities of the Client will take care of compensation.

Contractor's Environment, Health and Safety Management Plan (EHS-MP)

54. Within 6 weeks of signing the Contract, the Contractor shall prepare an EHS-MP to ensure the adequate management of the health, safety, environmental and social aspects of the works, including implementation of the requirements of these general conditions and any specific requirements of an EMP for the works. The Contractor's EHS-MP will serve two main purposes:

For the Contractor, for internal purposes, to ensure that all measures are in place for adequate EHS management, and as an operational manual for his staff.

For the Client, supported where necessary by a SE, to ensure that the Contractor is fully prepared for the adequate management of the EHS aspects of the project, and as a basis for monitoring of the Contractor's EHS performance.

55. The Contractor's EHS-MP shall provide at least:

a description of procedures and methods for complying with these general environmental management conditions, and any specific conditions specified in an EMP;

a description of specific mitigation measures that will be implemented in order to minimize adverse impacts;

a description of all planned monitoring activities (e.g. sediment discharges from borrow areas) and the reporting thereof; and

the internal organizational, management and reporting mechanisms put in place for such.

56. The Contractor's EHS-MP will be reviewed and approved by the Client before start of the works. This review should demonstrate if the Contractor's EHS-MP covers all of the identified impacts, and has defined appropriate measures to counteract any potential impacts.

EHS Reporting

57. The Contractor shall prepare bi-weekly progress reports to the SE on compliance with these general conditions, the project EMP if any, and his own EHS-MP. An example format for a Contractor EHS report is given below. It is expected that the Contractor's reports will include information on:

EHS management actions/measures taken, including approvals sought from local or national authorities;

Problems encountered in relation to EHS aspects (incidents, including delays, cost consequences, etc. as a result thereof);

Lack of compliance with contract requirements on the part of the Contractor;

Changes of assumptions, conditions, measures, designs and actual works in relation to EHS aspects; and

Observations, concerns raised and/or decisions taken with regard to EHS management during site meetings.

Training of Contractor's Personnel

58. The Contractor shall provide sufficient training to his own personnel to ensure that they are all aware of the relevant aspects of these general conditions, any project EMP, and his own EHS-MP, and are able to fulfil their expected roles and functions. Specific training should be provided to those employees that have particular responsibilities associated with the implementation of the EHS-MP. General topics should be:

EHS in general (working procedures);

Emergency procedures; and

Social and cultural aspects (raise awareness on social issues).

Cost of Compliance

59. It is expected that compliance with these conditions is already part of standard good workmanship and state of art as generally required under this Contract. The item "Compliance with Environmental Management Conditions" in the Bill of Quantities covers this cost. No other payments will be made to the Contractor for compliance with any request to avoid and/or mitigate an avoidable EHS impact.

# Annex 5: Project Traffic Management Plan (Sample)

### 1. Introduction

This Traffic Management Plan describes procedures and protocols for site access, traffic routing and management, and contractor company guidelines with respect to vehicle and employee transportation in delivering their obligations on this intervention project. Public, employee and contractor safety is the primary goal of this plan. It is vital that the Contractor recognizes that the traffic within the project area will be dynamic throughout the course of execution of this works and the safety of other road users is absolutely essential during this time.

### 2. General Site Access

In the interest of site security and public safety, access to operational areas or locations where heavy duty machinery would be operated in related to the execution of this contract will be restricted to authorized site personnel through the usage of signs and gates where appropriate. Facilities that potentially present danger to persons or wildlife such as the electrical substation, equipment staging area and workers camp will be fenced or barricaded as appropriate to prevent general access.

### 3. Traffic Management

All traffic on routes to and from the site will be radio controlled. Where this is not possible, signage will be installed at appropriate locations in order to warn the public along these routes.

In the event that temporary closure occurs, access to the sites will be further restricted through the use of fences and gates as appropriate. Access to work areas such as temporary excavated places, or confined spaces where work is ongoing will be securely blocked by means of a temporary but robust barrier or barricade. Buildings and ancillary facilities will be locked and secured. A number of additional general measures related to site access, road management and public safety and construction events notification are presented here:

Private employee off-road vehicles or private transport buses will be prohibited from entry into the site.

Signage will be posted near all construction sites.

Notifications will be provided for activities that would be carried out over the weekend or public holiday periods. These would be disseminated through existing social institutions such as the village or district heads of communities, Local Government Councilors and NGO's or CBO's

Speed limit maintained at 10 km/hr speed limit within or near the communities; Install reverse alarm fitted on all trucks, heavy duty equipment and off road vehicles Employ or engage the use of a minimum of two flagmen around excavated areas, one for traffic approach and one to direct traffic away from the sites In accordance with the Occupational Health and Safety Regulations for public roads, use of flashing devices/trafficators on all vehicles/machinery and equipment that will cross, travel on or may otherwise pose a risk to users of public roads.

### 4. Employee Transportation

To the extent possible employees will use buses provided by the contractor as transportation to and from the site, thereby reducing overall vehicle traffic. Project vehicles or will be utilized by staff, only when necessary.

### 5. Speed Limits

Speed limits will be enforced to and from the site and signage(s) shall be posted along the access and site roads (maximum 40 km/hr, reduced to 20 km/hr at blind corners and bridge crossings. Traffic along other access roads will be radio controlled for safety and speed control. Furthermore, employees and contractors will be educated on safety including traffic protocols and speed limits during mandatory orientation. Routine traffic inspections and/or speed indicator signs will be used to encourage safe and responsible driving.

### 6.Communications And Notification Protocols

It is anticipated that the intervention project will require only single-lane temporary closures. Signage warnings of construction activities on the roads will be placed at appropriate distances from the construction site, in consultation with SPIU, Ministry of Transports, department of Highways & Public Works. For significant work activity (those requiring more than one day to complete), written notification will be distributed to residents and the SPIU, Ministry of Transport, department of Highways & Public Works will be notified. A public notice would be posted at multiple locations in the metropolis to communicate to residents any new activities that may be occurring or scheduled. Contact information for the Contractors senior management will be included in this notice and any concerns regarding the intervention work/project or traffic management can be forwarded through this notification system.

### 7. Traffic Routing and Volumes

Alternative traffic routing shall be mapped out and provided in the event that there will be complete closure of the road due to this intervention work activity. Traffic officers and appropriate road diversion signage(s) shall be deployed to ensure diversions routes are properly identified and traffic is directed along the mapped route. The flagmen shall be properly kitted in their Personal Protective Equipment (PPE), such as reflector vests and safety boots, to ensure that safety on the job is given due priority.

### 8. Reporting

Records on traffic management and implementation of this plan should be kept and updated by the contractor as evidence of ongoing mitigation compliance, which will be submitted to SPIU as part of routine reports on progress of work.

# Annex 6: Contingency and Emergency Response Plan (Sample)

Introduction

An emergency is best described as a serious situation or unforeseen crisis that happens unexpectedly and requires or demands immediate/necessary action. This is often associated with danger. Therefore, this plan has been prepared to establish a process that has been adopted by our organization to respond to any emergency situation. This plan has the following fundamental objectives are:

To ensure that we can identify how to prepare for an emergency Provide a checklist of actions that would enable our team prepare to handle such emergencies

The objective

The aim of this plan is therefore to examine a series of steps in the process, which is designed to ensure that any situation that necessitated that the status of emergency be apportioned, be managed in a manner that would ameliorate this condition.

Thus, this plan provides guidelines on the best approach that would be engaged by employees of the Contractor company in emergency situations, which may be as a consequence of the following:

Medical (health) Safety Environmental Security Any other types of emergencies

Emergency Response Team (ERT)

An emergency response team will be constituted for the project. These will be the group of persons that would have the responsibility of managing this emergency plan in a manner that would ensure the goals of this plan are achieved. For this reason, the members of the ERT are:

Managing Director (or representative) HSEQ Officer Project Engineer Supervisor Support members (headmen from units – civil, mechanical, electrical etc.) Supervising Consultant representative SPIU representative

Emergency Response Centre (ERC)

Due to the temporary nature of the facilities that would be utilized as workers camp & site office, for intervention projects, the site office will also be converted into the Emergency Response Centre (ERC), in cases of emergency. Therefore, appropriate communication equipment shall be available in the office, to ensure that the channels of contact are available, at all times.

In the minimum our ERC will have: A computer system with internet facilities available A telephone A public address system

Activation of this Emergency Response Centre

The individual that receives the information that could potentially necessitate an emergency response should immediately convey the information to the Project Engineer.

Jointly, the project engineer and the Safety officer will review the situation/information, following which the managing director will be contacted (if not on site).

The managing director will hereafter take the decision of the gravity of the situation, following which it may be necessary to constitute an ERT and convert the site office into the ERC.

Core ERT and support members will be represented once the ERC is activated.

Checklist of Emergency Response Actions

These actions shall be implemented immediately the ERC is activated:

S/n	Actions
1.	Verify status of emergency and likely exposure of other personnel to risk, ensure ERT members are fully equipped in emergency response equipment
2.	Locate and account for all personnel on site (muster point) and if appropriate, implement the evacuation procedure, if necessary. Review decision on need to establish contact with family of personnel involved

	in emergency
3.	Establish and maintain close contact with relevant authorities related or connected to the resolving of this emergency. e.g. in case of medical emergency, a hospital, security emergencies will require a contact with government law enforcement agencies – police etc.
4.	Inform supervising consultant & SPIU representative as promptly as possible in order to establish interface link with Client
5.	Transmit any information update or changes in situation status to emergency focal group; the managing director and members of the ERT and determine if there is a need to shut down critical on going operational activities
6.	Depending on the type of emergency, any necessary follow up action should be determined and promptly acted upon, as may be required e.g. medical emergencies may require evacuation, environmental emergencies may require containment, safety emergencies may require prompt cordoning off of area etc.
7.	Internal Communication channel with other personnel should be kept open, by means of public address system or telecommunication (walkie talkies) and updates provided to forestall any likely re-occurrences, where possible
8.	Examine cross-cutting impact of emergency on liability issues and operational continuity. e.g. media involvement in security emergencies
9.	Undertake an assessment of risk to review other potential liabilities and deploy mitigation measures, where necessary. e.g. workmen compensation insurances in case of accident emergencies
10.	Review all cost implications of emergency response actions and make necessary budgetary provisions
11.	Provide the SPIU with updates immediately additional information is received.

Accident reporting

This accident report would be factual, free from hearsay, assumptions, gossips and / or preliminary conclusions. The report shall be duly signed by the Project engineer. The SPIU shall be briefed about the accident in writing within 24 Hours.

### Timing of investigation

The investigation should be carried out as soon as possible after the accident. The quality of evidence can deteriorate rapidly with time and delayed investigation are usually not as conclusive as those performed with dispatch. A prompt investigation is a good demonstration of management concern for safety. Scope of Investigation The scope of the investigation can be divided into four areas: Personnel Technique The Environment Organization

In each of these areas, actions of omission may be identified which could be a factor contributing to the accident or subsequent injury, damage or loss.

Establishment of the fact In establishing the fact(s) of an accident, we would consider the followings as necessary factors:

Background information that would be considered, the procedure for this type of operations command structure the person involved

Facts collection

Facts collection shall include but not limited to topography, weather, warning signs

/notices, condition of the equipment, housekeeping, before interview can be conducted.

### ACCIDENT REPORT AND INVESTIGATION (Standard report form)

Date: /AM/PM	Time:
Location:	Department:
Supervisor:	
Name of Victim:	
Nationality:	Address:
Marital Status:	Occupation:
Date of Birth:	Experience (years):

Equipment/tools being used when accident occurred:------

Conditions during accident: weather- dry, rain, clear, dusk, dark etc.

Unsafe acts, actions and conditions (Please describe):	

Report verification by:

Namo		
Name.	Date.	

# Annex 7: Waste Management Plan

No	Project Activity	Potential Impact	Proposed Mitigation Measures/ Actions	Respons ibility for mitigati on	Cost (NGN)
I. Pre-	Construction Pl	nase		1	
1.	Use of Workers Camp/Site Office	Generatio n of sanitary waste	Ensure provision of sanitary facilities on site for workers and enforce usage. Ensure usage of Yobe waste management agency approved waste vendor for waste evacuation & disposal.	Contract or	250,000
2.	Use of workers camp/site office	Sanitation issues and public health impacts	Provide bins on site for temporary storage of domestic waste such as lubricant containers, drinking water sachets and carrier bags/packaging materials. Dispose all construction and domestic waste at the approved dumpsites and in the approved manner. Ensure all trenches or excavations made during the construction works do not collect stagnant water, which could breed mosquitoes. Ensure access to toilets for construction crew or provide temporary toilets (mobile toilets) for use where there are no existing ones. Ensure mobile toilets/sanitary provisions are provided to reflect gender types. Ensure regular toolbox meetings are held among contractor workers to offer awareness on transmission	Contract or/ Engineeri ng Consulta nt Environ mental Safeguar ds Specialist	150,000

			of contagious or communicable diseases.		
3.	Building rehabilitatio n/constructi on work activities	Generatio n of constructi on waste including spoils, debris and concrete	Develop and implement a site-specific Waste Management Plan (WMP) to include the following: Ensure segregation of waste to facilitate reuse and recycling opportunities. Ensure no burning of waste on site. Ensure usage of YOBE SWAMA approved waste vendor for waste evacuation, processing & disposal.	Contract or	300,000
4.	Operation of workers camp/site office prior to demobilizati on of facilities	Generatio n of sanitary waste from worker's camp	Ensure provision of sanitary facilities on site for workers and enforce usage. Ensure usage of approved waste vendor for waste evacuation & disposal.	Contract or	180,000
5.	Commissioni ng of Michika General Hospital Road	Generatio n of constructi on waste and debris	Develop and implement a site-specific Waste Management Plan (WMP) to include the following: Ensure segregation of waste to facilitate reuse and recycling opportunities. Site visit at the completion of project to ensure no waste is left behind.	Contract or	Part of Maintenan ce cost
6.	All decommissio ning activities	Waste managem ent	<ul> <li>* Re-vegetate areas around workers camp &amp; Maintenance equipment sites to restore the landscape.</li> <li>* Ensure that any remaining waste streams created during Maintenance activities and waste generated during decommissioning activities are collected from the project sites and properly disposed before handing over the project.</li> </ul>	Contract or	150,000
Sub-Total Mitigation for Waste Mgt.		tion for		<u> </u>	1,030,000
	-				

## Annex 8: Cultural Heritage Management/Chance Find Procedure

### Identification and Assessment

For Cultural Heritage Management (CHM) under the Yobe MCRP, Inventory will always be a key management tool in the area of **identification and assessment**. The extent to which inventories are prepared will depend on criteria adopted by the PCU and in lines with requirements or guidelines by the WB.

The principal best practice in assessing cultural heritage issues around roads to be rehabilitated under the Yobe MCRP is to have a thematic and individual value assessment procedure in place, so as to justify long-term conservation of an asset. The aim of an identification and assessment process should be not only the identification of places, but also the establishment of a hierarchy of significant places under a thematic system.

### Best Practice Inputs

1. The MCRP should have a standard inventory form, also available as a Standard Operating Procedure (SOP).

2. Inventory should be updated as new information comes to light, or as new technology is introduced eg. GPS plotting of sites.

3. Inventory is thematically linked and has the primary aim of revealing a hierarchy of significant places under a variety of relevant themes.

4. Inventory work focuses on geographic areas or themes where there is little recorded inventory and a potential threat exists to unrecorded sites.

5. Each road project area has assessment criteria and an assessment process, both of which have been endorsed by the PCUs Safeguard Unit and WB.

6. The MCRP PCU should maintain a CHM database containing all information relating to history and management of CHM assets with cross-reference to other state inventories.

7. Assessment of significance of heritage places by an external CHM specialist should be a prerequisite for major capital expenditure on any CHM asset.

### Allocating Resources

Best Practice inputs/Indicators

1. There should be provision for access to a capital works budget for CHM catch up maintenance.

2. The Yobe MCRP PCU should plan for an ongoing core funding base for cyclical maintenance of CHM assets within each institution responsible for CHM and the reflection of this responsibility in the expected outputs.

3. Ensure risk management actions for CHM emergencies.

4. Prioritization of resource allocation to places on a thematic significance basis. This should be founded on an understanding of the history of land under management and broader state or national themes.

5. The proportion of CHM staff /institutional responsibilities to CHM assets managed should be similar to the proportion of staff to assets in other functional areas within the organization.

6. Identification of core competencies for CHM staff/institutional responsibilities and competency-based recruitment procedures including assessment of competencies by a CHM specialist.

7. The PCU should ensure that training in core CHM competencies are integrated into PCU training programs. (Including instruction in broad CHM principles and specific standard operating procedures)

8. Development of a suite of partnership tools to expand CHM management options eg. Local government management, community participation.

9. Regular analysis of CHM assets to ensure that each asset is managed by the MCRP PCU with the best expertise, resources, motivation and local presence to effectively conserve that place, and to present the place if it is appropriate to do so.

10. Comprehensive guidelines and programs to promote and support active community involvement in CHM.

11. All leases on CHM assets include provision for specific ongoing works funded by lessee.

12. Revenue generated from CHM should be retained for CHM without a corresponding drop in budget funding, in order to encourage sustainable management.

#### Protection

1. The MCRP should ensure that the process of acquiring places with a range of conservation or heritage values (natural, historic and indigenous) should take into account all the identified values and provide for their future management.

2. If the PCU considers acquisition is not an option, or is unnecessary, then other options including reserving, listing on a state heritage register, voluntary conservation agreement, covenanting, gazetting or referral to another relevant authority are pursued, with the co-operation of the owner.

3. The MCRP risk management strategy addresses the need for staff training and appropriate checks and balances to minimize the threat to CHM assets by in-house staff.

### Conservation

1. Conservation of places of cultural significance should be done according to a plan – a conservation management plan (CMP).

6. The breadth and detail of CMPs are commensurate with the needs of the place.

7. Shorter CMPs for individual sites, tailored to specific circumstances, should be prepared where; there is urgency to do the work, or the issues are simple and the vision statement for the place dictates action, or the plan forms part of a broader management plan.

8. Broad management plans or 'historic area plans' are prepared for larger land areas with predominantly historic values or places with multiple, geographically linked heritage assets. Work specifications or shorter CMPs are then prepared for each identified heritage asset in the area.

9. All CMPs are signed off by, at the minimum, by the PCUs Safeguard Unit (or their equivalent) to ensure organizational 'buy-in'.

10. Properly costed work specifications, together with plans, must be are prepared to relevant industry standards

11. Provision is made for a CHM specialist to inspect progress and ensure that work is proceeding according to the plan and that all work is supervised and conducted by skilled conservation practitioners or tradespeople.

12. Where sites have a multiplicity of values (e.g. natural and cultural as well as historic), then an overarching integrated management plan is prepared for that place. Cultural heritage is a component of such a plan.

### Monitoring

Physical monitoring of sites of cultural heritage will require synergized involvement attention by several relevant state and national agencies e.g. State Ministry for Culture and Tourism.

#### **Best Practice Inputs/Indicators**

The Yobe MCRP PCU should ensure:

- 1. The use of a formal asset management and monitoring system for CHM assets.
- 2. Annual reporting of agreed performance measures
- 3. Auditing of CHM to ensure management objectives are met
- 4. Integration of heritage places into organizational asset management systems.

5. A process existing for consistently reviewing plans, quality of planning and those who prepare them.

6. Establishment of a register of contract CHM specialists that is regularly reviewed on the basis of existing contractors' work, allows for the addition of new contractors and is open to public inspection.

7. Long term monitoring of the condition of cultural heritage places

8. Regular meetings of Yobe MCRP PCU Staff and CHM specialists as a means of monitoring progress towards best practice and assisting agencies to set higher levels of best practice.

9. Ongoing market research to measure effectiveness of presentation in interpreting specific places, raising awareness of cultural heritage conservation and encouraging appropriate growth in visitor numbers.

10. A CHM strategy/policy document which is published and subject to public consultation and scrutiny

11. Monitoring of visitor numbers at all actively managed places

## **Annex 9: Labour Influx Plan**

This plan identifies labour requirements and sets out the procedures for addressing labour conditions and risks associated with the proposed project, which is aimed at helping Yobe MCRP to determine the resources necessary to address project labor issues.

SUB- CATEGORY	WORKER IMPACTS\RISKS	PROJECT IMPACTS\RISKS	MITIGATION MEASURES	MONITORING	MONITORING FREQUENCY	RESPONS- IBILITY
Employment	Influx of many foreigners into project community	Competition on livelihood and job opportunity with locals	60 of unskilled labour shall be from the project community. Where possible qualified skilled workers on contract shall also be sourced within the community	Verify	Onset of Project and bi- weekly	ESO; SSO
Housekeeping.	The general appearance of the camp deteriorates making camp life unpleasant.	The overall camp experience is compromised which in turn leaves workers demoralised and unproductive.	Ensure that camp grounds and common areas are routinely cleaned and organised with appropriate signage in place, and that grounds are maintained (e.g., grassed areas are regularly mown). Establish easily accessible, designated smoking areas which are clearly highlighted and regularly cleaned.	Verify	Monthly	ESO; SSO
Recreation.	Workers spend most of their time in the camps and could become disenchanted and bored. They may want to leave the camps and go into the local towns and villages in search of recreation.	Tensions arise from the local communities as workers impact their activities in search of recreation. An increase in alcohol consumption and prostitution could result due to the influx of workers into local	Provide appropriate recreational facilities and activities. These should be discussed with the camp residents committee.	Assessment	Quarterly	ESO; SSO

		communities.				
Spiritual /Religion.	Workers will want access to places of worship for their chosen religion. They may leave the camps and go into the local towns and villages in search of an appropriate place of worship.	Tensions arise from the local communities as workers impact their activities.	Provide appropriate places of worship where residents express a need for this in accordance with cultural sensitivities, and assess transport arrangements on a case-by-case basis. Ensure that equipment and facilities are kept clean and well maintained.	Assessment	Quarterly	ESO; SSO
SUB- CATEGORY	WORKER IMPACTS\RISKS	PROJECT IMPACTS\RISKS	MITIGATION MEASURES	MONITORING	MONITORING FREQUENCY	RESPONS- IBILITY
Security.	Inconsistent and aggressive behaviour of security personnel towards workers can result in tensions and conflict in the workplace and a perception of human rights abuses.	Insufficient training and control of security personnel can lead to the inappropriate use of force, while protecting Project workers and assets, or inappropriate behaviour towards local populations, resulting in human rights claims.	<ul> <li>Ensure that camp security personnel meet at least the following requirements:</li> <li>Have not been implicated in past abuses</li> <li>Are trained in appropriate conduct towards workers and community members including:</li> <li>Exercising constraint and caution and understand how force may be used</li> <li>Respecting human rights</li> <li>Behaving consistently</li> <li>Knowing and abiding by applicable laws</li> </ul>	Assessment	Quarterly	ESO; SSO

			o Fostering good community relations through their interaction and behaviour towards the workforce and communities			
Community relations.	Communities are negatively impacted by camp activities: noise, waste, traffic, lighting and so forth. This may result in negative actions towards camp operations such as road closures and the prevention of workers or suppliers from entering the worksite.	Workers are stopped from going to work, which affects productivity.	Implement control measures to avoid and minimise the impacts of camp and living conditions on communities. Limit foreign worker interaction with communities and provide cultural sensitivity awareness training to facilitate appropriate interaction with communities.	Assessment	Quarterly	ESO; SSO

# Annex 10: List of Persons Met During Study

NAME	SFY			COMMUNITY
Aisha Usman	Female	Nil	Guiba	Wagir
Aisha Abdullahi	Female	07088442725	Guiba	Wagir
Aisha Muhammadu	Female	09072783371	Guiba	Wagir
Sakina Idriss	Female	09114745951	Guiba	Wagir
Gabai Mohammed	Male	Nil	Guiba	Wagir
Mohammed	Huic		Gujba	Wagii
Mahmud	Male	08026462507	Guiba	Wagir
Baba Hassan Goni				
Mele	Male	08087401039	Gujba	Gujba Town
Amina Mohammed	Female	08022273051	Gujba	Gujba Town
Babulama Zariye	Male	08081843464	Gujba	Gujba Town
Idrissa Mohammed	Male	08088814659	Gujba	Gujba Town
Dallatu Modu				
Carpenter	Male	08080129023	Gujba	Gujba Town
Fatima Ali Kwayam	Female	08088144350	Gujba	Gujba Town
Ibrahim Gana	Male	07085479122	Gujba	Gujba Town
Zara Ibrahim	Female	07016596346	Gujba	Gujba Town
Balkisu Hassan	Female	09071033620	Gujba	Gujba Town
Fatima Ibrahim				
Goni	Female	08022639440	Gujba	Gujba Town
Ali Lamido	Male	08082563211	Gujba	Gujba Town
Abdu Haruna	Male		Gujba	Tashan Deffo
Wada Alhassan	Male	07083846522	Gujba	Wagir
Usman Maifumi	Male		Gujba	Wagir
Ibrahim Abdu	Male		Gujba	Wagir
Umaru Abubakar	Male		Gujba	Wagir
Mala A. Bakura	Male	07012844392	Gujba	Bukkiyel
Jalige Buba	Male	08123786994	Gujba	Bukkiyel
Yahaya Maina Ilu	Male	08030432150	Gujba	Bukkiyel
Usman Hassan	Male	08024190179	Gujba	Bukkiyel
Jauro Fema	Male	08082645544	Gujba	Bukkiyel
Musa A. Dadi	Male	08129613773	Gujba	Bukkiyel
Biba Gado Ibrahim	Female	08125103951	Gujba	Bukkiyel
Dajji Adamu	Male	08121865774	Gujba	Bukkiyel
Aisha Umar	Female	07087628170	Gujba	Bukkiyel
Halima Babayo	Female	08126543473	Gujba	Bukkiyel
Mohammed S.				,
Modu	Male	08081046673	Gujba	Mutai

Bukar Wanzam	Male	07088364977	Gujba	Mutai
Ya Hadiza Bako	Female	09014790168	Gujba	Mutai
Hajja Mamman	Female	09071280676	Gujba	Mutai
Hajja Mangu	Female	07016507300	Gujba	Mutai
Yagana Maluri	Female	08027852218	Gujba	Mutai
Chiroma Mala	Male	09017499556	Gujba	Mutai
Barde Jalo	Male	08068990051	Gujba	Mutai
Muhammed				
Fannami	Male	08086862982	Gujba	Mutai
Mai Kadiri Fannami	Male	08088738038	Gujba	Mutai

### Annex 11: Camp Management Plan

Contractor Company (name of the Company) has developed this Camp Management Plan as part of its Environmental and Social Management Plan (ESMP) outlining a range of mitigation measures designed to avoid or reduce undesired camp management impacts during construction. This document establishes a basis and template for use by the Contractor(s) to develop their own plans outlining not only mitigation measures but to also incorporate the roles and responsibilities described in the ESMP.

The objectives of the Camp Management Plan are:

Avoid or reduce negative impacts on the community and maintain constructive relationships between local communities and workers' camps; and

Establish standards on worker welfare and living conditions at the camps that provide a healthy, safe and comfortable environment.

This Plan should be read in conjunction with other environmental and social management plans (ESMPs), if available including:

- Traffic Management Plan
- Security Plan
- Stakeholder Engagement Plan

### Legal Requirements and Grievances

The Contractor is required to operate within the parameters of the Nigeria Labour Law and the International Labour Organization guidelines. The World Bank Performance Standards are applicable to MCRP and its sub projects. Furthermore, the Grievance Redress Mechanism for the MCRP is required to be adhered to by the Contractor.

Contractor personnel shall conduct regular safety walks and an HSE committee will track performance against requirements stipulated in this plan. The Contractor will also have its grievance mechanism developed for the project.

Additionally, Contractor would be required to sign and acknowledge the Code of Conduct and agree to abide by its provisions.

### Management and Monitoring

Figure below presents a flow chart summarizing key management steps associated with implementation and review of this Plan, including steps to allow for continued improvement. Table 1 presents a summary of the potential impacts related to camp activities, together with mitigation and management measures to avoid or reduce these impacts, and the monitoring required to assess the performance of these measures.

The Contractor shall develop a Contractor Plan which shall, as a minimum, incorporate the camp management measures described in Table 1. The Contractor shall not be limited to these measures.

Monitoring to be undertaken as part of this Plan is described in Table 1.The Contractor is responsible for developing area or site-specific procedures for the

monitoring program (where necessary) based upon the final design details of the infrastructure



Table 1: Management and Monitoring									
Aspect	Potential impact	Mitigation & Management	Monitoring	Frequency	Responsibility				
Community Relations	Unauthorised movements of construction workers (during and after working hours) could result in trespassing, damage to local land and property and create amongst local residents a sense of their privacy being invaded. Residents may feel vulnerable and there may be increasing incidents of crime and or violence (GBV etc) and threats to the safety of community members. Disparity of pay, increase in disposable income and potential availability of illegal substances, illicit or culturally inappropriate lifestyle choices, leading to increased tension between local communities and the workers at camps.	<ol> <li>Contractor shall enforce a 'closed' camp policy unless otherwise agreed and approved by Company. Workers will comply with the agreed camp closure hours.</li> <li>Contractor shall implement suitable measures to maintain the closed camp policy which may include perimeter security fences, security controls and guard houses, monitoring transfer of goods into and out of camps for contraband and stolen goods. Contractor should refer to the Project Security Management Plan.</li> <li>Contractor, as appropriate, shall provide adequate recreation facilities for workers to reduce incentive for leaving camps during leisure time.</li> <li>Contractor shall limit workers interaction with the community when outside the camp e.g., by organizing transport directly to and from the worksite.</li> <li>If community members or local businesses express grievances in relation to camp related activities/operations, the Project shall respond to the grievance in accordance with the Grievance Redress Mechanism contained in the ESMF.</li> <li>FPMU/SPCU may request that camp related activities/operations be amended to address community grievances. Contractor shall comply with these requests.</li> <li>Workers shall abide by camp rules which include a disciplinary process to be developed by the contractor once appointed.</li> <li>The Project shall, be cognisant of the environment in which it works and shall, where practicable, respect local cultural events such as religious events, funerals and the like.</li> <li>The Project shall provide training to all workers on camp management including: a. A briefing on camp rules, including closed camp policy. behaviour between</li> </ol>	<ol> <li>Monitoring</li> <li>Verification</li> <li>Verification</li> <li>Verification</li> <li>Notification</li> <li>Verification</li> <li>Verification</li> <li>Verification</li> <li>Verification</li> </ol>	<ol> <li>On-going</li> <li>Every 3 months</li> <li>Every 6 months</li> <li>On-going</li> <li>On-going</li> <li>On-going</li> <li>Every 3 months</li> <li>On-going</li> <li>Every 3 months</li> </ol>	<ol> <li>Contractor</li> <li>Contractor</li> <li>Contractor</li> <li>Contractor</li> <li>Contractor</li> <li>Contractor</li> <li>and FPMU/SPCU</li> <li>Contractor and FPMU/SPCU</li> <li>Contractor and FPMU/SPCU</li> <li>Contractor and FPMU/SPCU</li> <li>Contractor and FPMU/SPCU</li> <li>Contractor</li> <li>FPMU/SPCU</li> <li>Soutractor</li> <li>FPMU/SPCU</li> </ol>				
			<ul> <li>fellow workers and the community;</li> <li>b. Procedures for dealing with camp related complaints, worker issues and community issues and</li> <li>c. Community relations orientation. The objective of this orientation will be to increase awareness about the local area and cultural sensitivities.</li> </ul>						
-------------------------------------------------------------------	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----------------------	---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----------------	----------------------------------------------	----------------	------------------------------------------------------------------	----------------	--------------------------------------------------
Health	Potential interaction between workers, persons engaged in illicit activities and the community increases the risk of spreading communicable diseases, particularly in more remote communities. Camp operations have the potential to develop favourable conditions for pests and disease, which could impact the health of workers and the community, as well as affect community livelihoods (e.g. rodent infestation affecting crops).	1. 2. 3. 4.	Contractor shall comply with the Minimum Health Requirements for Project Execution and the Community Health and Safety Management Plan which set out requirements and management measures on controlling communicable diseases within camps and to outside communities Contractor shall enforce the closed camp policy to limit interaction with community The Contractor shall develop a Pathogen and Pest Management Plan to prevent pathogens and pests from entering the camps and spreading outside the camps. Posters and informational sessions will be conducted to raise awareness among the workforce and communities locally around the worker camps.	Ver	ification	1. 2. 3.	Every three months On-going Every three months	Со	ntractor
Waste management, pollution and environmental impacts	Camp has the potential to have off site pollution impacts from waste disposal, emissions and spills. Camp operations may also cause environmental issues including deteriorating water quality, erosion, sedimentation, noise and air quality issues. These factors have the potential to affect the community if not adequately managed.	a) b) c)	Contractor shall exercise all reasonable due diligence to conduct its operations in a manner that will minimize pollution. Contractor shall comply with the Waste Management Plan and Hazardous Materials Management Plan which define requirements to contain, transport, handle and dispose of camp wastes and hazardous materials to avoid impacts to human health and the environment. Contractor shall also apply appropriate mitigation measures as contained in this ESMF.	1. 2. 3.	Verification Verification Notification	On	-going	Со	ntractor
Community resources	<ul> <li>Any infrastructure, services or resources used by camps (e.g. water abstraction) that result in reductions/ shortage/interruptions for the</li> </ul>	1.	Contractor shall utilise water sources for camp use in a manner that minimises impacts on local supply and use. Where necessary, water supply should be sought outside of the community source(s).	1. 2. 3.	Verification On-going Verification	1. 2.	Prior to establishin g the camps Every 3	1. 2. 3.	Contractor Contractor Contractor & SPCU

	<ul> <li>Iocal community will have a negative impact.</li> <li>There is potential for social envy and increased resentment from the community towards the Project and project team if camp facilities are perceived to be superior to those in the community. Services of note include camp health facilities, power supply, clean running water. Restricted ability to access these services may increase frustration at the level of the services available to them.</li> </ul>	<ol> <li>The Project shall routinely monitor quality and supply of water source used by camp through quarterly sampling exercises.</li> <li>Contractors shall be encouraged to extend Corporate Social Responsibility projects to host communities.</li> </ol>		months 3. Annual	
Procurement	Increased demand for food and	The Project shall not purchase products in the local	Verification	On-going	Contractor
and supply of	other provisions may deplete	community unless through formal contracts with			
goods	natural resources e.g. agriculture,	approved suppliers.			
	fisheries, etc. potentially causing				
	shortages of supply in the local				
	community, and/or increasing the				
	price of goods, affecting				
	affordability for local communities.				
Camp location	<ul> <li>Siting of camps may result in displacement of residents, loss of productive lands and the resources upon these lands. Camps may also restrict or impede access to areas for the local community.</li> <li>Construction camps may result in a noticeable increase in traffic, noise, air emissions and light intrusion which could negatively affect the amenity and lifestyle of nearby communities and pose a potential safety issue.</li> </ul>	<ol> <li>Potential camp locations will be selected in consultation with FPMU/SPCU and affected communities will be subsequently consulted. Necessary permits will be obtained from the relevant Local Authorities for the approved camp location.</li> <li>The Project shall refer to those Environmental &amp; Social Management Plan's (ESMP) that include mitigation/avoidance measures that relate to the local community, including:         <ul> <li>Noise and Vibration Management Plan;</li> <li>Air Emissions Management Plan.</li> </ul> </li> </ol>		<ol> <li>Prior to establishin g the camp</li> <li>On-going</li> </ol>	Contractor and/or Company
Labour Influx	There is a likelihood of influx of	Contractor shall enforce a `closed' camp policy.	Verification	On-going	Contractor and
	non local labour into areas around	This is intended to deter individuals setting up			FPMU/SPCU

	the construction camps. However, people from outside of the local area may migrate into existing settlements or develop new settlements in proximity to camps and the Project area. Labour Influx can result in disputes and sometimes violence between the new settlers and the resident community. Migrants moving into existing settlements may increase demand and inflate prices for housing, goods and services. Increased population and development of new and uncontrolled settlements increase pressure on infrastructure, services and resources. Major labour influx related risks include workers' sexual relations with minors and resulting pregnancies, presence of sex workers in the community, the spread of HIV/AIDS, sexual harassment of female employees, child labour and abuse, increased drop out rates from school, poor labour practice and lack of road safety.	<ul> <li>near camp.</li> <li>Contractor shall develop a Labour Influx Management Plan.</li> <li>Contractor is to coordinate with Local government to ensure that no illegal and unsafe settlements develop.</li> <li>Contractor shall eview and ensure adherence to labour influx management plan.</li> </ul>			
Worker welfare and living conditions	Construction workers living in camps may encounter stresses and discomforts that negatively impact their health and welfare. These stressors or discomforts may be caused by Poor living conditions (accommodation, ablution and sanitary, health, recreation catering and laundry).	Contractor shall comply with minimum standards for camp buildings, facilities and services in line with the Bank standard or as contained in the Project Invitation to Tender (ITT) requirements.	Verification	On-going	Contractor
	Cultural issues (nationality, religion, discrimination, GBV and harassment, etc.).	<ul> <li>Contractor shall ensure that applicable ESMF mitigation measures for specific issues are applied.</li> <li>Contractor may provide prayer rooms and other facilities, as necessary and to the extent</li> </ul>	Verification	On-going	Contractor

		<ul> <li>practicable, to satisfy the religious needs and customs of its workforce.</li> <li>Contractor's personnel shall not engage in any discrimination, GBV, SEA or harassing behaviour. Contractor shall establish an Equal Opportunity Policy to promote non-discrimination in accordance with Labour and Worker Conditions Management Plan.</li> <li>Contractor shall implement a worker grievance procedure to address grievances between workers.</li> </ul>			
	Mental health issues (morale, isolation, family attachments, boredom).	<ul> <li>Camps will be treated as closed camps. Camp rules in relation to alcohol consumption and drug prohibition will be complied with.</li> <li>Contractor shall provide recreational facilities where practicable.</li> <li>Contractor will provide counselling for all workers, with no discrimination by race, sex or religion.</li> </ul>	Verification	<ul> <li>On-going</li> <li>Every 6 months</li> </ul>	Contractor
	Personal security (crime, and emergencies).	<ul> <li>Camps will be controlled by security to avoid intrusions from outside community.</li> <li>Work Site Security Plan to be developed by Contractor shall include security measures to be provided at the camps which may include fencing, locks, alarms, pass card systems, badge and pass system, access points, safe transport of personnel as appropriate.</li> <li>Contractor shall develop an Emergency Response Plan that meets requirements set out in ITT package</li> </ul>	Verification	Prior to establishing camp	Contractor
	Environmental stress (climate, noise etc.).	<ul> <li>Contractor shall comply with Minimum Health requirements for Project Execution including the following: <ul> <li>Accommodation will be designed to suit climatic conditions;</li> <li>Accommodation and surroundings shall be constructed so that noise does not interfere with sleep to the extent that is reasonably practicable; and</li> <li>Health and hygiene inspections shall be carried out.</li> </ul></li></ul>	Verification	On-going	Contractor
Decommission ing	Decommissioning of camps has several potential impacts:	Contractor is to follow retrenchment procedure contained in Labour and Worker Conditions	Verification	On-going	Contractor and FPMU/SPCU

<ul> <li>Local employment and provision of local goods and services at camps will no longer be required;</li> <li>Locals employed and previously accommodated in camps will no longer have access to services and benefits available at camps (e.g. health services, recreation facilities); and</li> <li>Infrastructure which provides benefits to communities may no longer be maintained (e.g. roads, camp boreholes ) and may be decommissioned and removed.</li> </ul>	<ul> <li>Management Plan (if available)</li> <li>Where Community requests, some infrastructure and services may be retained as advised by the FPMU and the World Bank: <ul> <li>Disturbed areas will be reinstated;</li> <li>Where practicable, Contractor will return camp areas to former landforms;</li> <li>No facilities will be maintained in or near especially environmentally or socially sensitive areas; and</li> <li>Where there are negative consequences of induced access, the facility will also be decommissioned and the area reinstated.</li> </ul> </li> </ul>		
-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	--	--

# Annex 12: Security Management Plan (Sample)

The contractor shall pay necessary attention to ensuring security of life & property during the execution of this contract according to the scope of works. In ensuring that this role is carried out, the following will be given priority:

### **1.** Management Commitment and Responsibilities

Management is committed to ensuring that the following are in place:

- Providing up to date information regarding the security management mechanism, tools & updates in and around the work sites
- Ensure necessary early warning system is deployed to respond to security emergencies in the workplace by:
  - Development of a specific step-by-step approach to security response
  - Establish a security task force to respond to specific hazards, which is to be deployed in the case of security emergency
- Employing the appropriate personnel for the role of security personnel/advisor(s) and security staff
- Prioritize training of security personnel
- Enforcing disciplinary actions as needed to enforce security compliance
- Promoting interaction and assistance with regulatory and response agencies such as the Nigerian Police Force & Nigerian Military armed forces.

### 2. Threat Assessment and Analysis

A vital component of this Security Management Plan is the identification of internal and external threats. The mechanisms for identifying threats shall comprise but will not be limited to:

- Have in place and periodically update a threat matrix that will be submitted to management for review and approval.
- Undertake periodic drills that will include responses to:
  - A bomb threat
  - A violence in the workplace situation potential or actual
  - Domestic violence occurring within our facilities
  - General evacuation requirements due to a technical, human or natural threat
  - Others as may be determined by the General Manager or Security Management Committee

Threats will be qualified utilizing a threat matrix, or other tool that compares operations to threats, and their likelihood and severity. Where possible, mitigating actions and recommendations will be initiated.

# 3. The Role of the Security Focal Person or Manager

In the minimum, the contractor will have a security manager or focal staff that will be responsible for all security related issues in the workplace. The role of this security focal person includes:

- Lead role in threat assessments
- Program maintenance and updates
- Incident response and coordination
- Chair of the Security Program Committee
- Training Responsibilities
- Coordination with other Departments
- Coordination with agencies and response units

## 4. Employee security education and training

The company-training security program will ensure:

- Employee duties and responsibilities
- Event-specific responsibilities
- Threat or event reporting
- Back-to-work/check-in requirements
- Potential disciplinary actions
- Dealing with the media, regulatory agencies, or other entities outside the company

## 5. Management and Supervisor Education and Training

For Managers and Supervisors, our program focuses upon:

- Individual or Department duties
- Knowledge and deployment of response protocols
- Assuring employee and other constituent welfare
- Threat or event reporting
- Back-to-work/check-in requirements
- Potential disciplinary actions
- Dealing with the media, regulatory agencies, or other entities outside the company

## **Program Exercises and Drills**

The training and education activities that will be undertaken for the purposes of implementing this Security Management Plan shall be one of the following: case studies, table top exercises, or small and/or large scale exercises involving response pattern to adopt in the face of clear and present threats e.g. insurgent attacks

Impact Parameter	Time of Impact/Proje ct Phase	Impact Indicato r	FMEnv Limits	Sampling Location	Sampling Frequency	Sampling Method	Monitor ing Duratio n	Monitoring Personnel
Ambient Air Quality & particulate and gaseous emission	Site preparation, Construction/re habilitation & Operation of facility	TSP NO2 SO2 CO HC	600μg/m3 100 μg/m3 300 μg/m3 20 ppm	Receiving air - upwind & downwind of the site	Daily, during site preparation, construction; Once every three months during operation of facility	Air Sampler	Short- term Long- term	PCU-MCRP Contractor Yobe SMENv & FMEnv
Noise	Site preparation, Construction/re habilitation & Operation of facility	Noise Level	80 dBA (8-hr)	Work Site and 200m away	Daily (During site preparation, construction	Decibel Noise Meter	Short- term	PCU-MCRP Contractor Yobe SMENv & FMEnv
Water Quality (Surface)	Site preparation, Construction/re habilitation & Operation of facility	pH Tempera ture Oil & Grease Salinity COD BOD Turbidity TDS TSS	As specified in FMEnv Guidelines	Receiving water body/ drainage (upstream & Down-stream of discharge point).	Daily during Land preparation & construction & for 1- month at operation.	Water Sampler, Turbidi- meter and pH- meter	Short- term	PCU-MCRP Contractor Yobe SMENv & FMEnv

# Annex 13: Specific Environmental & Social Parameters Monitoring Plan

		Heavy Metals						
Soil	Site preparation, Construction/ Rehabilitation	Particle Size, Total Org C, Oil & Grease Heavy Metals, Nutrients	As specified in FMEnv Guidelines	Within and around construction area.	Once, before and after construction	Visual Inspection and Soil Sampler	Short- term	PCU-MCRP Contractor Yobe SMENv & FMEnv
Socio- economics	Construction/ rehabilitation stage	Absence of Contract or/comm unity conflict, increase/ decrease in economic activities	National/ World Bank guidelines & procedure s	Host communities	Monthly during construction	Socio- economic survey, observatio ns and interviews	Short term	PCU-MCRP Contractor Yobe SMENv & FMEnv
Health	Construction/ Rehabilitation & operation	Presence / absence of alien diseases	National health survey guidelines	Host communities	Monthly at construction and bi-annually at operation stages	Interview & medical examinati ons & records	Long term	PCU-MCRP, ESMoH, Yobe SMENv, & YOBE SWAMA
Land	Pre-	Complain	National/	Host	Weekly before	Complaint	Long	PCU-MCRP

acquisition Economic displacement	construction	ts of land take or economic displace ment (Grievan ce Log)	World Bank guidelines & procedure s	communities	construction	s received by PCU Grievance redress mechanis m	term	
Risk of Increase in spread of Communicabl e diseases, STDs such as HIV/AIDS and other STIs	Construction & Operation	Increase in reported cases	National/ World Bank guidelines & procedure s	Host communities	During and after construction works	Interview & medical examinati ons & records	Long term	PCU-MCRP Yobe State MoH
Risk of GBV/SEA and VAC as a result of Labour Influx	Construction & Operation	Presence / absence of reported cases	National/ World Bank guidelines & procedure s	Host communities	During and after construction works	Interview & medical examinati ons & records	Long term	PCU-MCRP Yobe State MoH
Reconnection of utilities such as existing power cables	Operation & Decommissioni ng	Visual inspectio ns and reported cases	National/ State, World Bank guidelines & procedure s	Host communities	During operation & decommissioning	Interview & records of inspection s	Long term	PCU-MCRP Yobe MoP

# **Annex 14: Certificate of Laboratory Reports**

# FEDERAL MINISTRY OF AGRICULTURE AND RURAL DEVELOPMENT

DEPARTMENT OF AGRIC LAND RESOURCES, GARKI, AREA 11 - ABUJA.

P.M.B No.:.... Tel: 09 - 2344315 Sec. Fax: 09 - 2344314 E-Mail Fmin Agric @ Linkserve Com.ng



Ref. No ALR/LAS/1/95 Date: 12-02-2020

CLIENT: SadaAfri-Tech International, 3B Evo Road GRA Port Harcourt, River State, Nigeria.

### SUBMISSION OF LABORATORY ANALYSIS RESULT

Ihereby submit the result of twelve (12) soil samples and twelve (12) water samples submitted to the laboratory on  $28^{th}$  January,2020 for analysis.

Attached, is a copy of the laboratory analysis results. Thank you for your patronage.

Yours faithfully

Danjel AutaDanjuma (MR) Field Officer, AL& CCMS, Kaduna. FEDERAL MINISTRY OF AGRICULTURE AND RURAL DEVELOPMENT

FEDERAL DEPT. OF AGRICULTURAL LAND AND CLIMATE CHANGE MANAGEMENT SERVICES

#### NATIONAL SOIL AND WATER LABORATORY,

KM 2 KADUNA- ABUJA EXPRESSWAY, GONIN- GORA, KADUNA

**CLIENT: SadaAfri-Tech International** 

DATE: 12/02/20

#### **Heavy Metals**

S/ N	PARAMETER	WGG02 Sub Soil	NGD05 Top Soil	NGA05 SubSoil	WGG02 Top Soil	TDG01 Top Soil	MUT03 Sub Soil	BUK04 SubSoil	BUK Top Soil	BUK04 Stream Sediment	MUT03 Top Soil	WGG02 Stream Sediment	TDG01 Sub Soil
1	Cadmium (mg/kg)	ND	ND	ND	ND	ND	ND	ND	ND	ND ·	ND	ND	ND
2	Lead (mg/kg)	53.5	ND	ND	6.20	ND	4.70	23.1	9.20	ND	ND	ND	50.70
3	Manganese (mg/kg)	231.5	274.3	73.3	153.0	68.40	247.4	348.9	131.8	21.1	25.7	24.3	156.0
4	Chromium (mg/kg)	4.0	7.2	15.9	ND	7.6	11.1	13.4	14.6	ND	ND	ND	14.0
5	Zinc (mg/kg)	100.7	161.6	43.0	1.3.6	45.7	1.3.6	117.0	155.8	38.2	46.2	36.4	99.4
6	Cobolt (mg/kg)	21.1	7.1	ND	7.0	12.8	9.0	3.3	ND	0.5	ND	0.7	11.9

Auta Daniel Danjuma Lab. Analyst.

#### FEDERAL MINISTRY OF AGRICULTURE AND RURAL DEVELOPMENT

### FEDERAL DEPT. OF AGRICULTURAL LAND AND CLIMATE CHANGE MANAGEMENT SERVICES

#### NATIONAL SOIL AND WATER LABORATORY,

#### KM 2 KADUNA- ABUJA EXPRESSWAY, GONIN- GORA, KADUNA

#### CLIENT:SadaAfri-Tech Internal

#### DATE: 12/02/20

#### Water Samples

S/ N	PARAMETER	WGG02 Ground water	BUK Down stream S.Water	BUK04 Ground Water	MUT 03 Ground Water	NGD 05 shallow Sediment	NGD 05 G.Water	WGG02 Up stream S. water	MUT 03 Pond sediment	TD GO1 G. Water	BUK 04 Up streamS. water	TDGO1 Shallow well sediment	WGG Down stream S. water
1	рН	7.20	7.15	7.10	7.60	7.05	7.35	7.35	7.10	7.00	7.10	7.25	7.10
2	TDS (ppm)	66	336	377	201	184	416	91	114	26	316	510	169
3	Nitrate (mg/l)	42	140	16	20	170	250	80	240	53	91	330	340
4	Chloride (mg/l)	28.36	121.95	65.23	34.03	45.38	124.78	34.03	51.05	31.20	52.47	134.71	39.70
5	Alkalinity(mg/l)	2.5	42.5	138	158	236	130	75	51	18	3159	5	55
6	Cadmium (mg/l)	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
7	Lead (mg/l)	ND	ND	ND	ND	ND	ND	ND	ND	0.077	0.276	ND	ND
8	Chromium (mg/l)	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
9	Manganese (mg/l)	0.148	0.195	3.152	0.202	0.940	0.423	0.411	0.480	0.324	2.078	1.664	0.220
10	Zinc (mg/l)	0.370	0.215	0.447	0.315	0.460	0.391	0.723	0.508	0.450	0.436	0.367	0.276
11	Cobolt (mg/l)	NB)	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Auta Daniel Danjuma Lab. Analyst.

#### FEDERAL MINISTRY OF AGRICULTURE AND RURAL DEVELOPMENT

#### FEDERAL DEPT. OF AGRICULTURAL LAND AND CLIMATE CHANGE MANAGEMENT SERVICES

#### NATIONAL SOIL AND WATER LABORATORY,

#### KM 2 KADUNA- ABUJA EXPRESSWAY, GONIN- GORA, KADUNA

#### CLIENT; SadaAfri-Tech International

Auta Daniel Danjuma (Lab. Analyst)

#### DATE: 10/2/2020

S/N	Soil ID	Partic	le Size D	Distribut	ion	pH R	latio 1:2		%	mg/kg	>Cmol/kg <				mg	g/kg		ds/m			
		Clay %	Silt %	Sand %	TC	H <sub>2</sub> 0	0.01m CaCl <sub>2</sub>	0.C	TN	Av. P	Ca	Mg	К	Na	EA	ECEC	Zn	Fe	Mn	Cu	EC
1	WGG02 S.S.	16.76	13.24	70.00	SL	7.20	6.55	0.152	0.028	1.24	1 991	0 305	0.156	0.677	0.501	3 610	12 70	14.10	12.22	4.02	0.1(00
2	NGD05 TS	12.76	7.24	80.00	SL	7.25	6.75	0.323	0.028	1.40	2.063	0.376	0.159	0.674	0.334	3.606	29.92	14.10	22.31	5.20	0.1906
3	NGA05 SS	3.12	28.92	67.96	SL	7.20	6.30	0.076	0.014	1.03	1.763	0.394	0.145	0.670	0.835	3.807	14.13	15.19	7.84	4.83	0.0609
4	WGG02 TS	4.12	25.92	69.96	SL	6.85	6.15	0.171	0.007	2.86	1.947	0.392	0.202	0.675	0.501	3.717	5.68	55.44	8.49	5.53	0.0218
5	TDG01 TS	3.12	27.92	68.96	SL	6.95	6.00	0.152	0.007	1.51	1.935	0.404	0.175	0.672	0.167	3.353	9.29	31.36	9.94	5.45	0.0484
6	MUT03 SS	5.12	25.92	68.96	SL	7.10	6.20	0.124	0.007	0.70	1.871	0.389	0.141	0.676	0.501	3.578	10.17	11.39	9.48	3.45	0.1078
7	BUK04 SS	6.12	24.92	68.96	SL	6.90	5.95	0.048	0.028	0.76	1.774	0.395	0.139	0.672	0.167	3.147	8.52	8.19	8.83	3.55	0.0594
8	BUK04 TS	5.12	25.92	68.96	SL	7.15	6.65	0.380	0.028	3.29	2.285	0.361	0.203	0.670	0.835	4.354	48.23	87.82	28.02	5.40	0.1000
9	BUK04 SD	4.12	17.92	77.96	LS	7.30	7.00	0.114	0.014	2.05	2.009	0.346	0.164	0.675	0.501	3.695	19.07	81.97	19.87	4.25	0.1172
10	MUT03 TS	5.12	21.92	72.96	SL	7.45	6.70	0.798	0.056	2.21	2.255	0.312	0.189	0.672	0.668	4.096	80.93	56.73	43.11	5.47	0.0219
11	WGG02 SD	0.00	0.00	100	S	7.15	6.80	0.019	0.014	0.97	0.121	0.120	0.051	0.673	0.167	1.232	5.36	9.23	4.09	2.94	0.0609
12	TDG01 SS	3.12	19.92	76.96	SL	6.60	6.50	0.019	0.014	0.54	1.680	0.395	0.143	0.672	0.501	3.391	8.02	7.00	6.21	3.80	0.2641

Sample location	Sample point	SPM mg/ms	СО РРМ	NO2 PPM	Н23 РРМ	302 PPM	VOC PPM
TDGOI	A1	0.19	0.01	0	0.01	0.02	0.01
11045'7"N	A2	0.26	0	0	0.01	0.01	0
11089'66"E	A3	0.17	0	0	0.03	0.01	0
	Mean	0.21	0	0	0.02	0.01	0.03
	FME LIMIT.	0.25	0.02	0.06	0.05	0.26	0.15
			0				
INAG02	A1	0.02	0	0.01	0	0.01	0.01
11035'74"N	A2	0.21	0	0	0	0.01	0.01
110 73′11″E	A3	0.19	0	0	0.01	0.01	0
	Mean	0.2	0	0	0	0.01	0.01
	FME limit	0.25	0.02	0.06	0.05	0.26	0.15
		Mg/m3	ppm	ppm	ppm	ppm	ppm
BUK 03	A1	0.25	0	0.01	0	0	0
110 31'86"N	A2	0.23	0	0	0.01	0	0.01
110 73′11″E	A3	0.21	0.01	0	0	0	0
	Mean FME Limit	0.23 0.25	0 0.02	0 0.06	0 0.05	0 0.26	0 0.15
		MG/M3	ppm	ppm	ppm	ppm	Ppm
MUT 04	A1	0.02	0	0	0.01	0.01	0
110 26′50″N	A2	0.16	0.01	0.01	0	0.01	0.01
110 71′88″E	A3	0.15	0	0	0.01	0.01	0.01
	Mean	0.17	0	0	0.01	0.01	0.01
	FME Limit.	0.25	0.02	0.06	0.05	0.26	0.15
		Mg/m3	Ppm	ppm	Ppm	ppm	Ppm
	A1	0.2	0	0	0.01	0.01	0
	A2	0.16	0.01	0.01	0	0.01	0.01
DNG 05	A3	0.15	U	0	0.01	0.01	0.01
	Mean	0.1/	0		0.01	0.01	0.01
	Limit	0.25	0.02	0.06	0.05	0.26	1.15
		Mg/m3	ppm		ppm	ppm	ppm

Annex 15: Air quality standards along 40km Gujba-Ngalda road

Source: Field Survey January, 2020.

Sample Location TDG 01	Position	Noise level DB (A)
110 45 `76"N, 110	n1	38.4
89′ 66″E	-	
	n2	42.3
	n3	35.1
	mean	38.6
110 35'74"N,11081'07"E	n1	48.7
WAG 02	n2	51.1
	n3	47.3
	mean	49
110 31'86"a 110 73'11"E	n1	36.8
BUK 03	n2	40.2
	n3	37.3
	mean	38.1
110 26′50″N, 110 71′ 88″E	n1	35.3
MUT 04	n2	38.6
	n3	32.9
	mean	35.6
	n1	40.8
	n2	42.3
UNG 05.	n3	45.1
	mean	42.7

Annex 16: Noise Levels along 40km Gujba-Ngalda road

Source: Field Survey, January 2020

PARAMETER	WGG02	WGG02US	BUK1	BUK2	MUT1	MUT2	NGD1	NGD2	TDG01	TDG02	BUK04US	WGG02DS
Temp. (oc)	28	28	28.1	27.5	29	27	28	29	28.2		28.2	28
PH	7.2	7.35	7.15	7.1	7.6	7.1	7.05	7.3	7	7.21	7.1	7.25
TDS (ppm)	66	91	336	377	201	114	184	416	26	510	316	169
CONDUCT (NS/cm)	122											
TURB. (NTU)	0.08	0.72	3.56	0.07	0.05		0.72	0.08	0.05		0.06	0.75
NITRATE (mg/cm)	42	80	140	16	20	240	170	250	53	330	91	340
NITRITE mg/cm	0.1	0.62	0.51	0.03	0.11		0,65	0.13	0.18		0.57	0.49
SULPHATE mg/L												
CHLORIDE mg/L	28.6	34	121.95	55.23	34.03	51	45.38	125	32	134.7	52.47	39.7
LEAD mg/L	ND	ND	ND	ND	ND	ND	ND	ND	0.07	ND	0.28	MD
CADMIUM mg/c	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
ZINC (mg/c	0.37	0.73	0.215	0.447	0.32	0.5	0.46	0.4	0.45	0.3	0.436	0.22
CALCIUM (mg/c)	0.93	0.75	0.84	0.72	0.98		0.76	0.83	0.82		0.69	
MAGNESSIUM Mg/c	0.27	0.35	0.29	0.3	0.25		0.28	0.19	0.26		0.3	0.33
NICKEL (mg/c)	ND											
CHROMIUM (mg/c)	ND	ND	ND	ND	ND		ND	ND	ND		ND	ND
IRON mg/c	0.19	0.34	0.24	0.2	0.26		0.31	0.22	0.18		0.26	0.21
POTASSIUM mg/c	0.32	0.91	0.93	0.25	0.18		0.84	0.31	0.26		0,76	0.66
SODIUM mg/c	12	10.3	9.21	10.32	13.6		10.5	15.4	12,1		13.2	11.8
TPH mg/c	ND	ND	ND	ND	ND		ND	ND	ND		ND	ND
BOD5 mg/c	1	0.31	1.2	0.1	0.1		0.I	0.1			0.21	0.46
COD	2	6.1	4.6	1.8	1.6		5.3	1.3	2.1		5,0	4.3
DO												

# Annex 17: Physico-chemical properties of water along 40km Gujba-Ngalda road

MPN/100ml	120	615	722	200	180	501	310	212	605	613
E.COL1spp.	AB	AB	>1	AB	AB	AB	AB	AB	>I	AB
SAMONELLA spp.	AB	AN	PR	AB						
SHIGELLA spp	AB	AB	PR	AB	AB	AB	AB	AB	PR	AN

Source: Field Survey, January 2020

Description	WGG02SS	WGG02TS	NGD05TS	NGD05SS	TDG01TS	TDG01SS	MUT03SS	BUK04SS	BUK04TS	BUK04SD	WGG02S
clay	16.76	4.12	12.76	3.12	3.12	3.12	5.12	6.12	5.12	4.12	0
Silt	13.24	25.29	7.24	28.92	27.92	19.92	25.92	24.92	25.92	17.92	0
Sand	70	69.96	80	67.96	68.96	76.96	68.96	68.96	68.96	77.96	100
ТС	SL	LS	S								
PH	7.2	6.85	7.25	7.2	6.95	6.6	7.1	6.9	7.15	7.3	7.15
% OC	0.152	0.171	0.323	0.076	0.152	0.019	0.124	0.048	0.38	0.114	0.019
%TN	0.028	0.007	0.028	0.014	0.01	0.014	0.01	0.028	0.03	0.014	0.014
P mg/kg	1.24	2.86	1.4	1.03	1.51	0.54	0.7	0.76	3.92	2.05	0.97
Ca mol/kg	1.881	1.947	2.063	1.763	1.94	1.68	1.871	1.774	2.29	2.009	0.121
Mg ,,	0.395	0.392	0.376	0.394	0.41	0.395	0.389	0.395	0.36	0.346	0.12
Κ,,	0.156	0.202	0.159	0.145	0.18	0.143	0.141	0.139	0.2I	0.164	0.051
Na ,,	0.677	0.675	0.674	0.67	0.67	0.672	0.676	0.672	0.67	0.675	0.673
ΕΑ,,	0.501	0.501	0.334	0.835	0.17	0.501	0.501	0.167	0.84	0.501	0.167
ECEC	3.61	3.717	3.606	3.807	3.35	3.391	3.578	3.147	4.35	3.695	1.232
Znmg/kg	12.7	5.68	29.92	14.13	9.29	8.02	10.17	8.52	48.23	19.07	5.36
Femg/kg	14.1	55.44	14.11	15.19	31.36	7	11.39	8.19	87.82	81.97	9.23
Mnmg/kg	12.22	8.49	22.31	7,84	9.94	6.21	9.48	8.83	28.02	19.87	4.09
Cumg/kg	9.22	5.53	5.2	4.83	5.45	3.8	3.45	3.55	5.4	4.25	2.94
EC	0.16	0.021	0.19	0.061	0.0485	0.2641	0.1078	0.0594	0.1	0.117	0.0609
Cdmg/g	ND	ND	ND								
Pbmg/g	53.5	ND	ND								
Cr	4	7.2									
Comg/g	21.1	7.1	45.7								
MCT %	2.58	2.61	2.6								
ТРН	22.6	16.9	24.1								
НВ	4X10	7X10	5X12								
HUB	5.5X10	7.3X10	4X10								

Annex 18: Physico-chemical properties of water along 40km Gujba-Ngalda road

HF	1.3X10	2.1X10	1I5X10				
HUF	2X10	3X10	2X10				

Source: Field Survey, January 2020

# Annex 19: Sample Copy of Grievance Procedure for Stakeholders

Community	Type of	Grieva	nce		Grievance Resolution					
project & Name of Complainant	Affected, but not informed about impacts and options	Compensation awarded is inadequate	Compensation not paid before assets acquisition	Resettlement benefits awarded are not provided	other	Date of complaint	Date received	Pending	Case referred to the Court	
Community Pr	oject 1									
Complainant A										
Complainant B										
Complainant C										
Community Pr	oject 2									
Complainant D										
Complainant E										
TOTAL										

### Annex 20: Chain of Custody for Sampling

The following procedures summarize the major aspects of chain of custody that guided the sampling for environmental media in this ESIA:

- The type of sample container used to store samples collected can affect the constituents of such samples. Therefore plastic containers with plastic screw caps were used for analysis of water; Glass containers are generally preferred with volatile organics (APHA, 1992).
- Sample labels: All samples were properly labeled to prevent wrong identification; labels were affixed or tags to samples containers before or at time of sampling. Each sample was number, name of collector; date and time of collection, and place of collection were all contained in the sample sheet attached here for your comment.
- Sample seals: labels were used to detect unauthorized tampering with samples up to time of analysis. Seal were attached in such a way that it would be necessary to break the seal to open the sample container.
- Field logbook: The sampling personnel have a log book where all information on the place of sample collection and the sample itself were recorded. The following basic elements are put down in the field logbook to aid in record keeping:
  - Date and time of sampling.
  - Name of sample.
  - Purpose of sampling
  - Location of sampling point (State, Town and Area)
  - Name and address of field contact
  - Type of sample
  - Number and volume of sample taken
  - Description of sampling point
  - Sampling method employed
  - Field observations and measurements
  - Signature and name of sampling personnel
  - Sample analysis request sheet
  - Sample delivery to Laboratory
  - Receipt and logging of sample
  - Assignment of sample for analysis